



December 16, 2024

Flood Resiliency Blueprint – December PAG Meeting



North Carolina Flood Resiliency Blueprint

- Introduction
- Phase II – Feedback and Progress
 - Modeling plan
 - Status of modeling
 - Future Scenarios
 - Blueprint Tool
 - Testing and Feedback
 - Methodology meeting
- Phase III (2024 - 2025)
 - River Basin Action Strategies
- Implementation Strategy
- Future of the Blueprint



Aaron Nelsen/Citizen Times / USA Today

Blueprint Overview

- **Phase I** (2022 - 2024) *Complete*
 - Research and evaluation, gap analysis, recommendations and decisions (Programmatic, Policy, Tools, Approaches, Needs),
 - Draft Neuse River Basin Action Strategy (Pilot)
 - Draft Blueprint
- **Phase II** (2023 - 2025) - *Ongoing*
 - Model improvement
 - Develop online decision support tool (Blueprint Tool)
- **Phase III** (2024 - 2026) - *Ongoing*
 - Develop Action Strategies for five prioritized areas
 - Refine Blueprint and Neuse Action Strategy (including additional data)
 - Refine Decision Support Tool
 - Additional River Basin Action Strategies as funding allows
- **Implementation** – (2024-____) *Ongoing*

Blueprint - Phase II



Department of Environmental Quality



Phase II – Modeling and Tool Development

Tool Development and Model Improvement

- April 2024 - Beta Testing
- September 2024 – Version 1 - *Testing*
- Spring 2025 – Version 2 - *Public*


| 2024 | | | | | | | | | | | | 2025 | | | | | | | |
|------------------|-----|-----|-----|------|-------------|--------------------------|-----|-----|-------------|--|-----|------|-----|--------------------|-----|-----|-----|-----|--|
| JAN | FEB | MAR | APR | MAY | JUN | JUL | AUG | SEP | OCT | NOV | DEC | JAN | FEB | MAR | APR | MAY | JUN | JUL | |
| TOOL DEVELOPMENT | | | | Beta | DEVELOPMENT | | | V1 | DEVELOPMENT | | | | | V2 Release and O&M | | | | | |
| | | | | | | Neuse Model Improvements | | | | | | | | | | | | | |
| | | | | | | | | | | Tar-Pam, White Oak, Cape Fear, Lumber Basin Model Improvements | | | | | | | | | |

Phase II – Modeling Strategy

Better define flood extent and depths

- Current Conditions
- Capture *future* flooding
 - Changes in precipitation patterns
 - Sea level rise
 - Increased impervious surfaces
- Facilitate future improvements
 - Storm surge and compound flooding

Support tool functionality



Phase II – Modeling Schedule

| | Item | Nov-24 | Dec-24 | Jan-25 | Feb-25 | Mar-25 | Apr-25 | May-25 | Jun-25 | Jul-25 | Aug-25 | Sep-25 | Oct-25 | Nov-25 | Dec-25 | Jan-26 |
|----------|--------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| MODELING | Neuse Modeling | | | | | | | | | | | | | | | |
| | Cape Fear Modeling | | | | | | | | | | | | | | | |
| | Lumber Modeling | | | | | | | | | | | | | | | |
| | Tar Pamlico Modeling | | | | | | | | | | | | | | | |
| | White Oak Modeling | | | | | | | | | | | | | | | |
| | FB LIDAR collection/processing | | | | | | | | | | | | | | | |
| | French Broad Modeling | | | | | | | | | | | | | | | |


Modeling Scenarios

| Simulation | Scenario | Number |
|-----------------------|---|--------|
| Existing condition | 20%, 10%, 4%, 2%, 1%, 1%-plus, 0.5%, 0.2% and 0.1% annual-chance storm events | 9 |
| Buildout w/o climate | 1% ICLUS 2050 and 1% ICLUS 2100 | 2 |
| Climate with buildout | 1% Mid Century low/high, 1% End Century low/high/severe | 5 |

Buildout – Based on Integrated Climate and Land Use Scenarios (ICLUS) projections.

<https://iclus.epa.gov/>

Department of Environmental Quality



Future Scenarios – Climate and Buildout

| Scenario | HEC Runs | | | | Surge Calculations | | |
|-----------------------|-------------------|-------------------|-------------------------|---|--|--|-----------------------|
| | | | SLR Boundary Conditions | | 1% AEP Storm Surge Adjustment (SLR+Subsidence) | | |
| | Precip Scenario | Buildout Scenario | Year, SSP, % of range | SL adjustment 2010 - scenario year (+ feet) | Year, SSP, % of range | SL adjustment 2010 to scenario year (+ feet) | Subsidence adjustment |
| Mid Century Lower | Y2050, RCP4.5 50% | ICLUS 2050 RCP4.5 | Y2050, SSP4.5 50% | 0.74 | Y2050, SSP4.5 50% | 0.74 | VLM Surface 2050 |
| Mid Century Higher | Y2050, RCP4.5 90% | ICLUS 2050 RCP4.5 | Y2050, SSP4.5 83% | 1.07 | Y2050, SSP4.5 83% | 1.07 | VLM Surface 2050 |
| End of Century Lower | Y2100, RCP4.5 50% | ICLUS 2100 RCP8.5 | Y2100, SSP4.5 50% | 1.89 | Y2100, SSP4.5 50% | 1.89 | VLM Surface 2100 |
| End of Century Higher | Y2100, RCP8.5 90% | ICLUS 2100 RCP8.5 | Y2100, SSP8.5 50% | 2.58 | Y2100, SSP8.5 50% | 2.58 | VLM Surface 2100 |
| End Of Century Severe | Y2100, RCP8.5 90% | ICLUS 2100 RCP8.5 | Y2100, SSP8.5 83% | 3.59 | Y2100, SSP8.5 83% | 3.59 | VLM Surface 2100 |

Data Sources:

NC State Climate Office / NCDOT (Atlas 14 Adjustments)

ICLUS v2
EPA

AR6 Models
IPCC

NC
CORS

Modeling Outputs

What will we see in the tool?

- **Flood Hazard Areas**
- **Existing Conditions** - Percent Annual Chance Flood **Extent** and **Flood Depth**

| | | | | | | | |
|-----|-----|----|----|----|------|------|------|
| 20% | 10% | 4% | 2% | 1% | 0.5% | 0.2% | 0.1% |
|-----|-----|----|----|----|------|------|------|

- **Future Conditions** 1% Annual Chance

| Mid Century (2050) | | | |
|-----------------------|-----------------|-----------------|---------------|
| Lower Scenario | Higher Scenario | Buildout Only | |
| | | | |
| End of Century (2100) | | | |
| Lower Scenario | Higher Scenario | Severe Scenario | Buildout Only |

Department of Environmental Quality




Modeling Outputs

What will we see in the tool?

- **Current Conditions** - Percent Annual Chance Flood **Extent** and **Flood Depth**

| | | | | | | | |
|-----|-----|----|----|----|------|------|------|
| 20% | 10% | 4% | 2% | 1% | 0.5% | 0.2% | 0.1% |
|-----|-----|----|----|----|------|------|------|



Variable flood depths and associated damage estimates for structures of varying elevation levels.

Modeling Outputs

What will we see in the tool?

- **Future Conditions** 1% Annual Chance

| Mid Century (2050) | | | |
|-----------------------|-----------------|-----------------|---------------|
| Lower Scenario | Higher Scenario | Buildout Only | |
| | | | |
| End of Century (2100) | | | |
| Lower Scenario | Higher Scenario | Severe Scenario | Buildout Only |


1% Annual Chance

Mid Century (2050) Higher Scenario

Mid Century (2050) Lower Scenario

Mid Century (2050) Development only

Current Conditions



Modeling Outputs

What will we see in the tool?

- **Future Conditions 1% Annual Chance**


| Mid Century (2050) | | | |
|-----------------------|-----------------|-----------------|---------------|
| Lower Scenario | Higher Scenario | Buildout Only | |
| End of Century (2100) | | | |
| Lower Scenario | Higher Scenario | Severe Scenario | Buildout Only |

Town Of Aberdeen - Housing

| Houses at Risk by Flood Depth Relative to First Floor Elevation ? | |
|---|--|
| (Based on 1% Annual Chance) | |
| More than 5 Feet | |
| 4 - 5 Feet | |
| 3 - 4 Feet | |
| 2 - 3 Feet | |
| 1 - 2 Feet | |
| 0 - 1 Feet | |
| Less than 0 Feet | |

Previous

Next



Phase II – Tool Development

Tool Development and Model Improvement

- April 2024 - Beta Testing
- **September 2024 – Version 1 – Testing and Feedback**
- Spring 2025 – Version 2 - *Public*


| 2024 | | | | | | | | | | | | 2025 | | | | | | |
|------------------|-----|-----|-----|------|-------------|--------------------------|-----|-----|-------------|--|-----|------|-----|--------------------|-----|-----|-----|-----|
| JAN | FEB | MAR | APR | MAY | JUN | JUL | AUG | SEP | OCT | NOV | DEC | JAN | FEB | MAR | APR | MAY | JUN | JUL |
| TOOL DEVELOPMENT | | | | Beta | DEVELOPMENT | | | V1 | DEVELOPMENT | | | | | V2 Release and O&M | | | | |
| | | | | | | Neuse Model Improvements | | | | | | | | | | | | |
| | | | | | | | | | | Tar-Pam, White Oak, Cape Fear, Lumber Basin Model Improvements | | | | | | | | |

Blueprint Tool Feedback

Unclear goals, too expansive

Resilience Actions

- Categories are not intuitive
- Why are we spending time on _____?
- In the tool methodologies are either not functional or the underlying logic driving the methodology is not apparent



Phase II – Decision Support Tool

- (Original) Goals:

- Be a resource for riverine and stream management to reduce flooding
- Reduce the cost and complexity for local government in the planning and implementation of flood risk reduction projects
- Lead to a prioritized set of projects

Develop a
Detailed
Community
Profile

Develop New
Resilience
Actions

Build a local
Action Plan

Explore Flood
Risk

Action
Management
(internal)

Fund Matching
Tool

Project
Complexity

Flood Risk
Scores

Ranking Actions

Estimating Impacts of
Flooding on People,
Environment,
Infrastructure, and
Economic Sustainability +

Community
Capacity

Data Repository

Blueprint Tool


- Goals:
 - Be a resource for communities, local governments, and other partners for the planning and implementation of resilience actions (that reduces the burden for local governments)
 - Provide users with accurate, data-driven flood risk and vulnerability assessments
 - Allow users to explore, develop, and define flood resilience actions
 - Allow users to evaluate and prioritize a set of cost-effective flood resilience actions – Local Action Plans
 - Be a resource to DEQ and partners in the development of River Basin Action Strategies.
 - Support DEQ/State funding decisions for planning and implementation.

Blueprint Tool




Phase II – Decision Support Tool

Local Planning Process Communities may have:




Phase II – Decision Support Tool




Blueprint Tool Feedback

Feedback on Resilience Actions

- Categories are not intuitive
- Why are we spending time on methodologies for rare, ineffective, or problematic mitigation measures?
- In the tool methodologies are either not functional or the underlying logic driving the methodology is not apparent



Phase II – Resilience Action Methodologies



Blueprint Tool

Methodology Workgroup Meeting – January TBD

| Categories | Flood Risk Reduction Measures | Categories | Flood Risk Reduction Measures |
|---------------------------|---------------------------------------|-------------------------------------|---|
| Building Level Mitigation | Relocation | Infrastructure & Control Structures | Levee/Dike/Berm |
| | Utility Elevation | | Dams – Existing Structures, New Structures |
| | Structural Elevation | | Roadway Elevation/Road Crossing Modification |
| | Reconstruction | | Storm Water Management Activities |
| | Wet Floodproofing | | Quarries |
| | Dry Floodproofing | Other | Beaver Management |
| | Critical Infrastructure | | Coastal Resiliency Action |
| Channel Modification | Acquisition/Demolition | | Enhanced Zoning |
| | Debris Removal | Policy & Planning | Land Use/Impervious Area Restrictions |
| | Channel Dredging, Widening, Diversion | | Multi-use Floodplains |
| Nature Based Solutions | Water Farming | | Stormwater, Water Quality, Floodplain Regulations |
| | Bioretention | Tool Methodologies | Funding |
| | Raingardens/Sand Filters/Bio-Swales | | Community Capacity |
| | Green Roofs | | Project Complexity |
| | Living Shorelines | | Flood Risk Scores |
| | Permeable Pavement | | Ranking Actions |
| | Afforestation | | Estimating Impacts to..... |
| | Flood Storage Wetlands | | |
| | Floodplain Restoration | | |
| | Riparian Buffers | | |
| | Floodplain Preservation | | |

Phase III - Process and Schedule



Department of Environmental Quality



Overview

- Implementation
- Phase I (2022 - 2024) Complete
 - Research and evaluation, gap analysis, recommendations and decisions (Programmatic, Policy, Tools, Approaches, Needs),
 - Neuse River Basin Action Strategy (Pilot)
 - Draft Blueprint
- Phase II (2023 - 2025) - Ongoing
 - Model improvement
 - Develop online decision support tool (Blueprint Tool)
- **Phase III (2024 - 2025) - Ongoing**
 - **Develop RBAS for five prioritized areas**
 - Refine Blueprint and Neuse RBAS (including additional data)
 - Refine Decision Support Tool
 - Additional River Basin Action Strategies as funding allows

Phase 3 Process and Schedule

- Develop River Basin Action Strategies for Five Priority Basins – or as funding allows
 - Cape Fear, French Broad*, Lumber, Tar Pamlico, White Oak
- Complete the Neuse River Basin Action Strategy
- River Basin Action Strategy Timeline (Cape Fear, Lumber, Tar Pamlico, White Oak)
 - Contracts Awarded 10/28/24
 - Kick-off Meeting 11/4/24
 - Initial SOWs Approved **12/18**
 - Cape Fear, White Oak, Lumber, Tar-Pamlico,
 - **Draft RBAS for 12/1/2025**
 - **Final RBAS for 1/31/2026**

Phase III – River Basin Action Strategies

DRAFT

| | Item | Dec-24 | Jan-25 | Feb-25 | Mar-25 | Apr-25 | May-25 | Jun-25 | Jul-25 | Aug-25 | Sep-25 | Oct-25 | Nov-25 | Dec-25 | Jan-26 |
|-------------------------------|-----------------------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| MODELING | Neuse Modeling | | | | | | | | | | | | | | |
| | Cape Fear Modeling | | | | | | | | | | | | | | |
| | Lumber Modeling | | | | | | | | | | | | | | |
| | Tar Pamlico Modeling | | | | | | | | | | | | | | |
| | White Oak Modeling | | | | | | | | | | | | | | |
| | LIDAR collection/processing | | | | | | | | | | | | | | |
| | French Broad Modeling | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | End of Year report | | | | | | | | | | | | | | |
| RIVER BASIN ACTION STRATEGIES | French Broad RBAS (Phase 1) | | | | | | | | | | | | | | |
| | French Broad RBAS (Phase 2) | | | | | | | | | | | | | | →→→ |
| | Neuse River RBAS (Phase 2) | | | | | | | | | | | | | | |
| | Cape Fear RBAS | | | | | | | | | | | | | | |
| | Lumber RBAS | | | | | | | | | | | | | | |
| | Tar Pamlico RBAS | | | | | | | | | | | | | | |
| | White Oak RBAS | | | | | | | | | | | | | | |

Phase 3 Process and Schedule

- 6.4 Draft Basin Priority Resilience Actions - Initial Vetting
 - An annotated list of priority flood resilience actions for the basin based on information gathered initial data collection (1.1-1.3), initial community engagement.
 - Actions should be prioritized using best professional judgement and based on criteria developed for the blueprint rankings and should consider the likelihood of adverse impacts.
- Projects evaluated based on
 - their ability to reduce risk to human life
 - their ability to reduce flood impact to critical community infrastructure (e.g. emergency facilities, evacuation routes, and utilities)
 - their ability to reduce flood damage to other infrastructure, homes, businesses, etc.,
 - whether the projects had been identified in a Hazard Mitigation or other Resilience Planning efforts,
 - whether the projects are in a high-risk area,
 - their likelihood of reducing flood risk to, or improving flood resilience for, underserved communities,
 - whether the projects serve additional public benefit (e.g. parks, trails, schools, critical infrastructure, etc).

Blueprint - Implementation Strategy



Department of Environmental Quality




Implementation Strategy – Committed Funds

| Partner / Source | Amount | Individual Projects |
|--|-------------------------|---------------------|
| Department of Agriculture - StRAP 2023 | \$ 4,721,991.00 | 32 |
| Department of Natural and Cultural Resources – Land Water Fund (21-23) | \$ 9,047,404.00 | 15 |
| Direct Funding Local Gov | \$ 3,679,476.00 | 4 |
| NC Emergency Management - 2023 Disaster Relief and Mitigation Fund | \$ 3,910,000.00 | 3 |
| 3% Administration | \$ 2,880,000.00 | |
| Out-the Door and Committed Total | \$ 24,238,871.00 | |

| Partner / Source | Amount | Individual Projects |
|---|-------------------------|---------------------|
| Department of Agriculture - Farm Pond Pilot | \$ 10,000,000.00 | ? |
| Committed, but estimated total | \$ 10,000,000.00 | |



Implementation Strategy – Committed Funds



Implementation Strategy

Projects evaluated based on

- their ability to reduce risk to human life
- their ability to reduce flood impact to critical community infrastructure (e.g. emergency facilities, evacuation routes, and utilities)
- their ability to reduce flood damage to other infrastructure, homes, businesses, etc.,
- whether the projects had been identified in a Hazard Mitigation or other Resilience Planning efforts,
- whether the projects are in a high-risk area,
- their likelihood of reducing flood risk to underserved communities,
- whether the projects serve additional public benefit (e.g. parks, trails, etc).
- ...no regrets

Possible Implementation Strategy

Partnering with Existing Programs

- NCDCM - Resilient Coastal Communities
- NCDEQ - Water Resources Development Grants programs
- NCORR – Community Development
- DNCR- Land Water Fund New Solicitation 24-25



Possible Implementation Strategy

Resilient Recovery Opportunities

Identify opportunities to provide incremental funding that leads to more resilient recovery

- DOT Resilient Recovery
 - Coordinating w/ DOT. Upsizing stream crossings, improving/hardening infrastructure
- Direct French Broad Opportunities
 - Projects that meet Blueprint Criteria

Possible Implementation Strategy

DEQ Direct Funding

- Direct Funding to Local Government
 - Unfunded BRIC proposals
- High Hazard Dams
- NCDEQ - NIFMP project
- Direct RFP
- USACE Matching Funds



Future of Blueprint



Department of Environmental Quality



Future of Blueprint - Vision

- Planning
 - Permanent staff, consistent funding for:
 - A Statewide Flood Resiliency Blueprint (all basins and a statewide action strategy)
 - Direct support for local governments
 - Local planning process / Project development
 - Blueprint Tool Support/Training
 - Capacity Support – marshalling funds, administering projects
 - Adaptive Management
 - Ongoing model and tool improvements, documentation, third-party review
 - Cyclical RBAS Updates

Future of Blueprint - Vision

- Implementation
 - Ongoing funding to 'fill gaps' and incentivize flood resilience
 - Project management, grant administration
 - Long-term maintenance, monitoring, and stewardship of implemented projects

Thank You



Department of Environmental Quality

