









# MONITORING YEAR 3 ANNUAL REPORT

Final

# **BIG HARRIS CREEK MITIGATION SITE**

Cleveland County, NC DMS Project No. 739 DEQ Contract 006256 DWR 401 Project No. 10-0811 USACE Action ID No. SAW-2009-0475 Broad River Basin HUC 03050105

Data Collection Period: February – November 2020

Final Submission Date: February 15, 2021

## PREPARED FOR:



NC Department of Environmental Quality Division of Mitigation Services 1652 Mail Service Center Raleigh, NC 27699-1652

# **PREPARED BY:**



1430 South Mint Street, Suite 104 Charlotte, NC 28203

> Phone: 704.332.7754 Fax: 704.332.3306



February 15, 2021

Mr. Paul Wiesner NC Department of Environmental Quality Division of Mitigation Services 5 Ravenscroft Dr., Suite 102 Asheville, NC 28801

RE: Big Harris Creek Mitigation Site – Monitoring Year 3 Report

Final Submittal for DMS

Contract Number 006256, RFP Number 16-006119, DMS# 739 Broad River Basin – CU# 03050105; Cleveland County, NC

Dear Mr. Wiesner:

Wildlands Engineering, Inc. (Wildlands) has reviewed the Division of Mitigation Services (DMS) comments and observations from the Big Harris Creek Mitigation Site Draft Monitoring Year 3 Report and included them below in **bold**. Wildlands' responses to your comments from the report noted in *italics*.

DMS' Comment: General – The MY3 (2020) report indicates that invasive areas of concern were observed in 9% of the easement acreage (12.9 acres). The MY2 (2019) report noted that invasive areas of concern were observed in 8% of the easement acreage (12.0 acres). Please continue to treat invasive species on a regular basis through the monitoring term to reduce invasive coverage as much as possible on the project site. The IRT may require additional invasive treatments and monitoring if the invasive areas of concern on the project are not reduced a significant amount prior to project closeout.

Wildlands' Response: Wildlands will continue invasive treatments across the site.

DMS' Comment: General – Janet Whisnant Property: Please provide a brief update in the response letter (not the MY3 report). If Mrs. Whisnant is unwilling to sign the revised conservation easement and associated plat prior to project closeout, mitigation assets and the associated contract invoices will need to be revised accordingly.

Wildlands' Response: Wildlands will continue to reach out to Ms. Whisnant and understands that the mitigation assets and associated contract invoices will need to be revised prior to closeout if an updated conservation easement and plat is not signed.

DMS' Comment: Section 1.2.2 – Stream Areas of Concern & Section 1.2.5 Vegetation Areas of Concern/ Adaptive Management Plan: DMS understands that WEI will review stream and vegetation areas of concern documented in the MY3 (2020) report and will implement stream repairs, structure repairs and supplemental planting as necessary. DMS recommends implementing any necessary repairs and/or supplemental planting early in MY4 (2021) to allow 1.5 to 2 full growing seasons before the proposed IRT project closeout in 2023. The IRT has historically required 1.5 to 2 years post repair/supplemental planting before allowing formal regulatory closure.

Wildlands' Response: Wildlands will implement repairs in the first half of MY4 (2021) to allow as much time as possible before the proposed regulatory closure in 2023.

DMS' Comment: Digital Support Files – During MY2 (2019) DMS noted that certain features did not match reported assets. Shapefiles were resubmitted, and all features were accurate except for Lower



Fletcher Creek R1, which was off by 21 feet relative to the asset table. Additionally, in the resubmittal Upper Stick Elliot Creek R4A and R4B were merged, which is not how they are presented in the asset table. Please attempt to resolve the issue with Lower Fletcher Creek R1 and ensure that Upper Stick Elliot Creek R4A and R4B are segmented so that each feature represents an entry in the asset table.

Wildlands' Response: Based on further discussions with DMS the shapefile comment on Lower Fletcher Creek R1 has been resolved. Upper Stick Elliot R4A and R4B have been segmented and now reflect linear footage reported in the asset table.

DMS' Comment: Digital Support Files – The stream gage data Excel sheets are not able to be opened, and Excel suggest they are corrupted. Please ensure these files can be opened and resubmit with the final digital submittal.

Wildlands' Response: The Excel spreadsheets have been reviewed and re-copied into the folder for the final digital submittal. Please let us know if they continue to be an issue.

DMS' Comment: Digital Support Files – Please include figures displaying gage data for all gages in the report.

Wildlands' Response: Figures with gage data for all stream gages have been added to Appendix 5.

DMS' Comment: Technical Memo Reporting/Water Quality Data Comments – Western Carolina University (WCU) monthly baseflow grab sampling for conductivity, TSS, and fecal designated in the technical memo/monitoring plan were originally expected to begin in January 2020. Due to equipment issues and issues related to COVID, sampling was not initiated by WCU until June 2020. Monthly grab samples for these parameters have a scheduled duration of 36 months and will currently finish up in approximately June 2023 (post MY5). DMS anticipates that project closeout will be in mid-2023. WEI should discuss this directly with both DMS and WCU in early 2021 to make certain all parties understand that WQ monitoring will not terminate until mid-2023.

Wildlands' Response: Wildlands has communicated with DMS and WCU to make certain all parties understand WQ monitoring will terminate in June 2023. Text was added in Section 1.2.6 to acknowledge the updated sampling schedule. Email correspondence including WEI, WCU, and DMS was added to Appendix 7.

DMS' Comment: Technical Memo Reporting/Water Quality Data Comments – Conductivity data was not included in the report as documented in the technical memo. Please include conductivity data in the revised MY3 report.

Wildlands' Response: Conductivity data has been added in the final MY3 report.

DMS' Comment: Technical Memo Reporting/Water Quality Data Comments – The report is using WCU's station numbers. WEI should provide data with the station numbers from the technical memo (Tables and Graphs).

Wildlands' Response: Stations numbers have been updated to match the technical memo.

DMS' Comment: Technical Memo Reporting/Water Quality Data Comments – The report includes the SSC data that is being collected with WCU. That is a separate effort and not part of the technical memo. The SSC data should be removed from the final MY3 report.

Wildlands' Response: The SSC data has been removed from the final MY3 report.



DMS' Comment: Technical Memo Reporting/Water Quality Data Comments – Actual analysis (as per the memo) is not slated until the end of the project monitoring. DMS recommends the data be presented by Station similar to the table below. Not all of the parameters will be populated. For example, baseflow nutrient samples don't start until MY4, but something similar to this is more useful than what is currently presented in the draft report.

	Station 2										
Date	Flow Type	Cond (Units)	TSS (mg/L)	Fecal (CFU/100)	NOx	NH3-4	TKN	TN	TP		
06/XX/XX	Base										
07/XX/XX	Base										
	Base										
11/XX/XX	Storm										

Wildlands' Response: The WQ data presentation has been revised into a format that is similar to the template provided above.

DMS' Comment: Technical Memo Reporting/Water Quality Data Comments – Please include all unreported baseflow and stormwater results collected in 2020. All of the 2020 samples are analyzed and should be included in the tables.

Wildlands' Response: All available data collected in 2020 have been included in Table 15. Results from several stormwater samples collected between September and December 2020 have not yet been reported by the lab.

DMS' Comment: Technical Memo Reporting/Water Quality Data Comments – Please indicate the approximate storm sampling events in the hydrographs.

Wildlands' Response: The storm sampling event on 10/13/20 has been called out on the hydrograph of the corresponding station. Additional storming events between September and December 2020 are not called out on the hydrographs because no data is currently available.

Enclosed please find two (2) hard copies of the Final Monitoring Year 3 Report and one (1) USB with the final corrected electronic files for DMS distribution. Please contact me at 704-332-7754 x110 if you have any questions.

Sincerely,

Kristi Suggs

Senior Environmental Scientist ksuggs@wildlandseng.com

### **EXECUTIVE SUMMARY**

Wildlands Engineering, Inc. (Wildlands) implemented a design-build project for the North Carolina Department of Environmental Quality (DEQ) Division of Mitigation Services (DMS) to restore 10,071 linear feet (LF) of streams, enhance 23,421 LF of streams, preserve 669 LF of streams, and provide water quality treatment for 171 acres of drainage area in Cleveland County, NC. The streams proposed for mitigation credit include Big Harris Creek and 25 tributaries. Buffer restoration also occurred but is not proposed for buffer mitigation credit. The project is expected to provide 25,329.916 stream mitigation units (SMUs) in the Broad River Basin. An additional 507.000 SMU's are proposed for statistical improvement in water quality parameters per revised post-construction water quality sampling approved by the Interagency Review Team (IRT) in 2019.

The Big Harris Creek Mitigation Site (Site) is located within the DMS targeted watershed for the Broad River Basin Hydrologic Unit Code (HUC) 03050105080060 and the North Carolina Division of Water Resources (NCDWR) Subbasin 03-08-04. The Big Harris Creek and Magness Creek HUC 03050105080060 was identified as a Targeted Local Watershed (TLW) in DMS's 2009 Broad River Basin Restoration Priority (RBRP) Plan (DMS, 2009). The Cleveland County Natural Resources Conservation Service has also identified this watershed as a priority area.

The watershed has a long history of agricultural activity and most of the stressors to stream functions are related to historic and current land use practices. Prior to restoration, the major stream stressors for the Site were cattle access, erosion from lateral instability, and gully headcutting in the headwater ephemeral reaches. The effects of these stressors resulted in degraded water quality and habitat throughout the watershed when compared to reference conditions. The design approach for the Site focused on evaluating the Site's existing functional condition and evaluating its potential for recovery and need for intervention.

The major goals established for the project; which align with the overall goals of the Broad River Basin RBRP, are to reduce sediment and nutrient inputs, reduce fecal coliform inputs through cattle exclusion, and reestablish native riparian corridors while preserving existing headwater aquatic habitats and riparian corridors.

The following specific project goals were established in the Mitigation Plan (Wildlands, 2016).

- Improve stream stability and reduce stream bed and bank erosion;
- Restore hydrologic connection between bankfull channels and floodplains, wetlands, and vernal pools;
- Improve instream habitat and instream habitat connectivity;
- Reduce agricultural pollutant loading to project streams; and
- Create and improve forested riparian buffers.

The Site construction and as-built surveys were completed between April 2017 and May 2018. Post-construction monitoring will be conducted for five years to evaluate project success. Planting and baseline vegetation data collection occurred between March and May 2018. Monitoring Year (MY) 1 assessments were completed between September and December 2018.

MY3 assessments and site visits were completed between February and November of 2020. The Site has met the required stream, vegetation, and hydrology success criteria for MY3. Overall, restored streams are stable and functioning as designed with minor fluctuation in channel dimension related to bed/bank scour and/or deposition documented in some of the annual cross-sections. Isolated pockets of instability were observed across the Site during visual assessment. Stream repairs were completed in April 2020 to areas of bank erosion noted during MY2 and early MY3 on Upper Big Harris Reaches 5 and 6 and Lower

Stick Elliott Creek. The average planted stem density for the Site is 427 stems per acre; which meets the MY3 interim requirement of 320 stems per acre; however, 11 of the 56 vegetation plots individually do not meet MY3 stem density criteria. Seven of these 11 vegetation plots do not meet final stem density success criteria (260 stems per acre). Bankfull and geomorphically significant events were recorded on all restoration and El reaches during MY3.

## **BIG HARRIS CREEK MITIGATION SITE**

Monitoring Year 3 Annual Report

TABLE OF C	
Section 1:	PROJECT OVERVIEW
1.1	Project Goals and Objectives
1.2	Monitoring Year 3 Data Assessment
1.2.1	Stream Assessment
1.2.2	Stream Areas of Concern
1.2.3	Stream Hydrology Assessment
1.2.4	Vegetative Assessment
1.2.5	Vegetation Areas of Concern/Adaptive Management Plan 1-8
1.2.6	Additional Monitoring1-9
1.3	Monitoring Year 3 Summary1-9
Section 2:	METHODOLOGY2-1
Section 3:	REFERENCES
APPENDICE	es s
Appendix 1	General Figures and Tables
Figure 1	Project Vicinity Map
Figure 2.0-2	
Table 1	Project Components and Mitigation Credits
Table 2	Project Activity and Reporting History
Table 3	Project Contact Table
Table 4a-4f	•
Table 5a-5e	,
	,
Appendix 2	
Figure 3.0-3	
Table 6a-6u	Visual Stream Morphology Stability Assessment Table
Table 7	Vegetation Condition Assessment Table
	Stream Photographs
	Vegetation Photographs
	Areas of Concern Photographs
Appendix 3	Vegetation Plot Data
Table 8	Vegetation Plot Criteria Attainment Table
Table 9	CVS Vegetation Tables - Metadata
Table 10a-1	
Appendix 4	Morphological Summary Data and Plots
Table 11a-f	Baseline Stream Data Summary
Table 12a-c	Morphology and Hydraulic Summary (Dimensional Parameters – Cross Section)
Table 13a-s	Monitoring Data – Stream Reach Data Summary
	Cross-Section Plots
	Reachwide and Cross-section Pebble Count Plots
Appendix 5	Hydrology Summary Data and Plots
Table 14	Verification of Bankfull Events



Bankfull and In-stream Flow Event Plots

# Appendix 6 Revised Water Quality Monitoring Correspondence and Technical Memo

# Appendix 7 Water Quality Monitoring Data (MY3)

Table 15 Western Carolina University Water Quality Data

Western Carolina University Stage Gage Plots

Updated Water Quality Monitoring Sampling Schedule Correspondence

# Section 1: PROJECT OVERVIEW

The Site is located in western Cleveland County, approximately 2.5 miles west of the Town of Lawndale in the Broad River Basin HUC 03050105080060 and NCDWR Subbasin 03-08-04 and is being submitted for mitigation credit in the Broad River Basin HUC 03050105. (Figure 1). Located in the Inner Piedmont geologic belt within the Piedmont physiographic province (NCGS, 1985), the project watershed is dominated by agricultural and forested land. Big Harris Creek drains 3.9 square miles of rural land.

The development of the mitigation project for this Site has a long history. The Site was first identified in 2008 by DMS staff as a watershed-scale mitigation opportunity. The Site is located in a HUC that was designated as a high priority agricultural TLW and as a "focus area" for DMS in the 2009 Broad River Basin Restoration Priority (RBRP) Plan. The initial Environmental Resources Technical Report (ERTR) for the Site was completed in March 2009. Easement acquisition on 12 parcels, totaling 144.7 acres, was completed on the project area by the end of 2009. The IRT originally walked the Site in 2010 and requested a "light touch" approach to much of the Site. Water quality, benthic, fish, and storm water sampling has been collected for the project by multiple agencies and organizations between 2009 and 2013.

The availability of the pre-construction monitoring led to more precise management recommendations for the Site. The project approach incorporated previous and recent IRT feedback and minimized construction phase impacts to existing channels and riparian areas while providing the targeted uplifts to the system. Project components include intermittent and perennial stream restoration, enhancement, and preservation, as well as water quality treatment on ephemeral drainages. Stream restoration, enhancement, and preservation components include Big Harris Creek and 25 unnamed tributaries.

The watershed has a long history of agricultural activity and most of the stressors to stream functions are related to this historic and current land use. Prior to restoration, the major stream stressors for the project were cattle access, erosion from lateral instability, and gully headcutting in the headwater ephemeral reaches. The effects of these stressors resulted in degraded water quality and habitat throughout the watershed when compared to reference conditions.

Table 4 in Appendix 1 and Tables 6 in Appendix 2 present the pre-restoration conditions in more detail.

## 1.1 Project Goals and Objectives

The Site was identified by DMS to address major agricultural stressors within the watershed with specific focus on gully erosion, streambank erosion, and livestock access to streams. Restoration and enhancement of streams and buffers on the Site addressed those identified stressors and thereby improving water quality in the Big Harris Creek watershed.

The major goals of this stream mitigation project were to reduce sediment and nutrient sources, reduce fecal coliform sources through cattle exclusion, and reestablish healthy riparian corridors while preserving existing, high quality headwater aquatic habitats. These goals were primarily achieved by creating functional and stable stream channels by: 1) increasing and improving the interaction of stream hydrology with the riparian zone, 2) improving in-stream habitat and bed form diversity, 3) introducing large woody debris, and 4.) beginning the establishment of a native, forested riparian corridor along the stream reaches. These activities are known to support higher order functions like the processing of organic matter, nutrient cycling, and temperature regulation.

The project includes the majority of the headwater tributaries to Big Harris Creek and 35% of the 11-square mile Big Harris Creek watershed before it flows into the First Broad River. Within the project

limits, approximately 34,161 LF of stream channel were restored, enhanced, or preserved. Water quality BMPs were also implemented to stabilize eroding ephemeral channels and provide water quality treatment on 171 acres of headwater drainage systems during the period after construction until the riparian buffer vegetation becomes established. A total of 5,536 LF of ephemeral drainages were buffered and conserved, enhancing the overall watershed water quality and function.

The following specific goals and objectives established in the Mitigation Plan (Wildlands, 2016) address the identified stressors in the Big Harris Creek and Magness Creek TLW.

Goals	Objectives
	Grade back eroding stream and headwater gully slopes and/or install bioengineering. Add bank revetments and instream structures to protect enhanced streams.
Improve stream stability and reduce stream bed and bank erosion.	Construct new stream channels that will maintain a stable pattern and profile considering the hydrologic and sediment inputs to the system, the landscape setting, and the watershed conditions.
Restore hydrologic connection between bankfull channels and floodplains, wetlands, and vernal pools.	Construct new stream channels with appropriate dimension and depth relative to their functioning floodplain elevation.
Improve instream habitat and instream habitat connectivity.	Install habitat features such as constructed riffles and brush toes into restored/enhanced streams, adding woody materials to channel beds and constructing pools of varying depth.
nabitat connectivity.	Replace existing culverts with bottomless arch culverts, partially buried culverts, or ford crossings and enhance profile by removing vertical steps at culvert outlets.
	Install BMPs at concentrated flow locations in the watershed headwaters to treat agricultural runoff until riparian buffer vegetation becomes established and reduce gully erosion. Plant riparian buffers that will uptake runoff and reduce pollutants once established.
Reduce agricultural pollutant loading to project streams.	Construct new stream channels with floodplain connectivity, allowing flood flows to filter through a vegetated floodplain.
	Install fencing around conservation easements adjacent to cattle pastures to exclude cattle from the easement.
Create and improve forested riparian buffers.	Plant native tree and understory species in riparian zone.

# 1.2 Monitoring Year 3 Data Assessment

Annual monitoring and quarterly site visits were conducted during MY3 to assess the condition of the project. The stream, vegetation, and hydrologic success criteria for the Site follows the approved success criteria presented in the Big Harris Creek Mitigation Plan (Wildlands, 2016).

### 1.2.1 Stream Assessment

In general, project streams appear stable with most cross-sections showing minimal change in bankfull width, maximum depth ratio, and width-to-depth ratio. Cross-section dimensions generally fell within the parameters defined for channels of the designed stream type (Rosgen, 1994 & 1996). During the fall of MY1, significant adjustments in channel dimension related to bed and/or bank scour were documented at cross-sections 3, 4, 43 and 44 as a result of multiple large storm events (precipitation greater than two inches per event) that included the remnants of Hurricanes Florence and Michael. Cross-section 3 has stabilized since MY1; however, during MY3 the cross-section exhibited minor adjustments commonly associated with meander pools. Cross-section 4 was repaired during MY2 but experienced significant bed and right bank scour during MY3 similar to MY1. Cross-section 43 has remained stable since MY1 with no repair work. Cross-section 44 has stabilized in MY3 after bed and bank scour were documented MY1 and MY2. During MY2, bed and bank erosion were documented at cross-section 11 on Scott Creek, resulting in a wider and deeper channel. In MY3, cross-section 11 has stabilized with little to no change in channel dimension.

The majority of the cross-sections showed small fluctuations in channel dimension related to minor scour or deposition, which are normal and not indicative of instability. Cross-sections 9, 13, 18, 29, and 37 exhibited channel narrowing likely the result of deposition coupled with the establishment of streambank vegetation. Aggradation was also documented at cross-section 32 and 33 on Upper Fletcher Creek Reach 2. The source of in-stream sediment may be offsite since no erosion was noted along Upper Fletcher Reaches 1 or 2.

Pebble counts conducted in the restoration and EI reaches indicate maintenance of coarser substrate in the riffle features and finer particles in the pool features. Minor shifts in particle size distribution during MY3 included coarser particles on Elliott and UT1 to Elliott, Bridges, and Upper Stick Elliott Creek UT3 Cross-section 9 near the upstream end of Royster Creek exhibited a significant increase in finer particles than in previous monitoring years. The increase coincides with mapped aggradation noted on the CCPV maps. The source of in-stream sediment appears to be offsite because no erosion is documented along this portion of Royster Creek. Refer to Appendix 2 for the visual stability assessment table, Current Condition Plan View (CCPV) map, and reference photographs. Refer to Appendix 4 for the morphological data and plots.

In addition to annual geomorphic cross-section, at least three sets of hydraulic geometry measurements (water surface slopes) are to be collected within distinct restoration and enhancement I design reaches following a geomorphically significant discharge (Qgs) event as described in the DMS Stream and Wetland Mitigation Monitoring Guidelines (February 2014). During MY3 water surface slopes were collected on representative wavelengths within Upper Big Harris Reach 2A, Scott Creek, Upper Stick Elliott Creek Reach 1, Elliott Creek, UT1 Elliott Creek, Bridges Creek, and Lower Big Harris Creek. Refer to Tables 13a-13s in Appendix 4 for water slope data.

### 1.2.2 Stream Areas of Concern

Previously documented areas of erosion along Upper Big Harris Creek (Reaches 5 and 6) were repaired in April 2020. In addition to repairs, the continued establishment of bank vegetation has improved overall bank stability. Areas of minor, isolated erosion were documented across the Site. Three failed structures including one log vane at Station 145+40 of Upper Big Harris Creek, one boulder sill at Station 806+75 of Royster Creek, and one log sill at Station 317+50 of Lower Big Harris Creek were documented. Wildlands will review these areas and implement repairs, as necessary. A total of three small beaver dams were documented on-site in November 2020: Lower Big Harris Reaches 1B and 2 and UT2 to Lower Big Harris. Wildlands will coordinate with trappers with the U.S. Department of Agriculture (USDA) Animal and Plant Health Inspection Services (APHIS) to remove beaver in these locations.

Reach 2 Refer to the CCPV maps in Appendix 2 for the locations of stream areas of concern.

### 1.2.3 Stream Hydrology Assessment

At the end of the five-year monitoring period, two or more bankfull events and geomorphically significant (≥ 60% of bankfull flow) events must have occurred in separate years within the restoration and EI reaches. All 14 automated stream gages across the Site documented at least one bankfull event and an additional geomorphically significant event in MY3. At the end of MY3, all 14 stream gages have recorded two geomorphically significant events in separate years and 12 of the 14 stream gages have recorded two bankfull events in separate years. The two exceptions are Scott Creek and Bridges Creek. Refer to Table 14 in Appendix 5 for specific reaches.

In addition to monitoring bankfull events, the presence of baseflow must be documented along intermittent reaches (Royster Creek Reach 1, Scott Creek, and Bridges Creek) constructed with a Priority 1 Restoration approach. Flow must be present for at least 30 consecutive days of the year with normal rainfall conditions. All three reaches exceeded the 30 days of baseflow. Royster Creek Reach 1, Scott Creek, and Bridges Creek stream flow gages recorded 79, 33, and 165 days of consecutive flow, respectively. Refer to Appendix 5 for hydrology summary data and plots.

### 1.2.4 Vegetative Assessment

A total of 56 vegetation plots were established during the baseline monitoring within the project easement area. The vegetation plots were installed using a 100 square meter quadrant ( $10m \times 10m$  or  $5m \times 20m$ ). The final vegetative success criteria will be the survival of 260 planted stems per acre in the planted riparian corridor at the end of the required monitoring period (MY5). The interim measure of vegetative success for the Site will be the survival of at least 320 planted stems per acre at the end of the third monitoring year (MY3).

The MY3 vegetation monitoring planted stem densities among the vegetation plots ranged from 81 stems/acre to 647 stems/acre with an overall average stem density of 427 planted stems per acre, which is greater than the interim requirement of 320 planted stems per acre required at MY3. Planted stem counts within individual plots ranged from 2 to 16 stems with an average of 11 planted stems per plot. Most of the plots (45 of 56 plots) met the interim stem density success criteria for planted stems in MY3; however, seven plots (12, 25, 27, 29, 31, 50, 51) did not meet the interim or final stem density success criteria. During MY3, individual volunteers in plots 25, 29, 50, and 51 were identified for possible inclusion in future planted stem density. Vegetation plots not meeting stem density success criteria will continue to be evaluated for inclusion of volunteer species. A majority of planted woody stems (67%) had a vigor rating of 3 or more indicating that the stem is healthy and likely to survive to MY5. Refer to Appendix 2 for vegetation plot photographs and the vegetation condition assessment table and Appendix 3 for vegetation data tables.

# 1.2.5 Vegetation Areas of Concern/Adaptive Management Plan

Scattered areas of invasive species including Asian spiderwort (*Murdannia keisak*), Chinaberry (*Melia azedarach*), Chinese privet (*Ligustrum sinense*), hardy orange (*Poncirus trifolata*), Japanese honeysuckle (*Lonicera japonica*), kudzu (*Pueraria lobata*), multiflora rose (*Rosa multiflora*), and tree-of-heaven (*Ailanthus altissima*) were observed during MY3. Areas of heavy fescue (*Festuca* sp.) were documented within designed BMPs on Eaker and Royster Creeks. Portions of the mapped invasives occurring within existing forested areas of the easement pose less of a threat to established vegetation. Invasive species are only present on approximately nine percent or 13 acres of the total easement acreage of 145 acres. Areas of Chinese privet and hardy orange were treated in January 2020. Asian spiderwort, kudzu, and

tree-of-heaven were treated in October 2020. Areas of effective treatment are not shown on CCPV maps in Appendix 2. Future treatments will be performed as needed.

During MY3, minor easement encroachment (mowing) impacted approximately 0.2 acres in the vicinity of vegetation plot 53 along Lower Big Harris Reach 1A. The encroachment has been addressed with the landowner.

Refer to Appendix 2 for the vegetation condition assessment table and the CCPV maps.

### 1.2.6 Additional Monitoring

A post-construction water quality monitoring plan was approved by the IRT during MY2. Components of the plan include water quality sampling in MY3 – MY5 with benthic macroinvertebrate and fishery assessments to be conducted during MY4 – MY5. Water quality sampling was originally scheduled to being in January 2020 and last for three years; however, due to unforeseen issues was not initiated until June 2020. Based on the adjusted start date, water quality sampling is now anticipated to run through June 2023. Refer to Appendices 6 and 7 for the Revised Water Quality Monitoring Technical Memo, associated IRT correspondence, MY3 water quality data provided by Western Carolina University (WCU), and updated sampling schedule correspondence with WCU.

# 1.3 Monitoring Year 3 Summary

Overall, streams within the Site appear to be stable and functioning as designed except for minor areas of erosion and aggradation. In MY3, bankfull events and additional geomorphically significant events were documented on all 14 gaged streams, with 12 of the 14 stream gages already meeting the MY5 success criteria of two bankfull and two additional geomorphically significant events occurring in separate years. With an average planted stem density of 427 stems per acre for the Site, the project is on track to meet the MY5 success criteria. However, eleven plots did not meet the interim MY3 success criteria and seven of those plots (12, 25, 27, 29, 31, 50, and 51) currently do not meet the MY5 success criteria. Volunteers in plots 25, 29, 50, and 51 were identified in MY3 for possible inclusion in future planted stem density. Adaptive management will be implemented as necessary to address areas of stream and vegetation areas of concern.

Summary information and data related to the performance of various project and monitoring elements can be found in the tables and figures of the report appendices. Narrative background and supporting information formerly found in these reports can be found in the Mitigation Plan (Wildlands, 2016) documents available on the DMS' website. All raw data supporting the tables and figures in the appendices are available from DMS upon request.


# Section 2: METHODOLOGY

Geomorphic data were collected following the standards outlined in The Stream Channel Reference Site: An Illustrated Guide to Field Techniques (Harrelson et al., 1994) and in the Stream Restoration: A Natural Channel Design Handbook (Doll et al., 2003). All Integrated Current Condition Mapping was recorded using either a Trimble or Topcon handheld GPS with sub-meter accuracy and processed using Pathfinder and ArcGIS. Crest gages were installed in surveyed riffle cross sections and monitored quarterly. Hydrologic monitoring instrument installation and monitoring methods are in accordance with the United States Army Corps of Engineers (USACE, 2003) standards. Planted woody vegetation is being monitored in accordance with the guidelines and procedures developed by the Carolina Vegetation Survey-EEP Level 2 Protocol (Lee et al., 2006).

# Section 3: REFERENCES

- Doll, B.A., Grabow, G.L., Hall, K.A., Halley, J., Harman, W.A., Jennings, G.D., and Wise, D.E. 2003. Stream Restoration A Natural Channel Design Handbook.
- Harrelson, Cheryl C; Rawlins, C.L.; Potyondy, John P. 1994. *Stream Channel Reference Sites: An Illustrated Guide to Field Technique*. Gen. Tech. Rep. RM-245. Fort Collins, CO: U.S. Department of Agriculture, Forest Service, Rocky Mountain Forest and Range Experiment Station. 61 p.
- Lee, Michael T., Peet, Robert K., Steven D., Wentworth, Thomas R. 2006. CVS-EEP Protocol for Recording Vegetation Version 4.0. Retrieved from http://deq.nc.gov/document/cvs-eep-protocol-v42-lev1-2
- North Carolina Division of Water Resources (NCDWR), 2015. Surface Water Classifications. http://portal.ncdenr.org/web/wq/ps/csu/classifications
- North Carolina Division of Mitigation Services (DMS), 2009. Broad River Basin Restoration Priorities. https://files.nc.gov/ncdeq/Mitigation%20Services/Watershed\_Planning/Broad\_River\_Basin/Broad\_RB RP\_2009\_final.pdf
- North Carolina Division of Mitigation Services (DMS), February 2014. DMS Annual Monitoring and Closeout Reporting Template.
- North Carolina Geological Survey (NCGS), 1985. Geologic Map of North Carolina: North Carolina Survey, General Geologic Map, scale 1:500,000. https://deq.nc.gov/about/divisions/energy-mineral-land-resources/north-carolina-geological-survey/ncgs-maps/1985-geologic-map-of-nc4
- Rosgen, D. L. 1994. A classification of natural rivers. Catena 22:169-199.
- Rosgen, D.L. 1996. Applied River Morphology. Pagosa Springs, CO: Wildland Hydrology Books.
- United States Army Corps of Engineers (USACE), 2003. Stream Mitigation Guidelines. USACE, NCDENR-DWQ, USEPA, NCWRC.
- Wildlands Engineering, Inc (Wildlands), 2016. Big Harris Creek Mitigation Site Mitigation Plan. DMS, Raleigh, NC.
- Wildlands Engineering, Inc (Wildlands), 2018. Big Harris Creek Mitigation Site Baseline Monitoring Document and As-Built Baseline Report, DMS, Raleigh, NC.





2 Miles










Figure 1 Project Vicinity Map Big Harris Creek Mitigation Site DMS Project No. 739 Monitoring Year 3 - 2020 Cleveland County, NC













500 1,000 Feet Figure 2.1 Project Component/Asset Map Big Harris Creek Mitigation Site - Area A DMS Project No. 739 Monitoring Year 3 - 2020 Cleveland County, NC








Figure 2.2 Project Component/Asset Map Big Harris Creek Mitigation Site - Area B DMS Project No. 739 Monitoring Year 3 - 2020 Cleveland County, NC



150

300 Feet





Figure 2.3 Project Component/Asset Map Big Harris Creek Mitigation Site - Area C Monitoring Year 3 - 2020

DMS Project No. 739

Cleveland County, NC

Table 1. Project Components and Mitigation Credits

Big Harris Creek Mitigation Site DMS Project No. 739 Monitoring Year 3 - 2020

	Mitigation Credits								
	Strea	am	Riparia	n Wetland	Non-riparian We	tland	Buffer	Nitrogen Nutrient Offset	Phosphorus Nutrient Offset
Туре	R	RE	R	RE	R	RE			
Totals	25,228.121	101.795	N/A	N/A	N/A	N/A	N/A	N/A	N/A

	/pe	R		RE	R		RE	R	RE								
To	tals	25,228.12	1	101.795	N/A		N/A	N/A	N/A	N/A	N,	A		N/A			
							Proj	ect Components									
Project Area	Project	t Reach	Existing Fo		ationing/Lo	ocation		Approach		Restoration (R) Restoration	Footage	Miti	gation atio	Total Buffer Width	Proposed Credit <sup>2, 3, 4</sup>		
			, ,					(P1, P2, etc.)		Equivalent (RE	) (LF) <sup>1</sup>			Adjustments			
	Cornwell	Creek R1	2,144	40	3+44	425+20		cattle fencing; buffer planting		EII	2,144	:	2.5	25	883.000		
	Cornwell	Creek R2	286	42	5+20	428+27		Full restoration with structures		EII	307	:	2.5	0	123.000		
	UT1 to Cor	nwell Creek	78	43	0+27	431+05		cattle fencing; buffer planting		EII	78	:	2.5	0	31.000		
	Eaker	Creek	135	51	3+11	514+45	cattle	fencing, bank grading and in-st structures	ream	EI	134		1	0	134.000		
	Eaker Cree	k SPSC BMP	N/A	N	I/A	N/A		headwater BMP		N/A	1309	ı	N/A	N/A	N/A		
	Scism	Creek	1,189	60	6+92	618+81	ВМР,	oank grading and in-stream stru	ıctures	tures EII			1.5	12	805.000		
	Scism C	reek EC	N/A	N	I/A	N/A		headwater BMP		N/A	358	ı	N/A	N/A	N/A		
	Royster	Creek R1	438	80	2+54	807+13		Priority 2 Restoration		R	459		1	-5	454.000		
	Royster	Creek R2	3,185	80	7+40	839+40		cattle fencing; buffer planting		EII	3,170		2	21	1606.000		
А	Royste	r BMP2	N/A	N	I/A	N/A		headwater BMP		N/A	539	ı	N/A	N/A	N/A		
	Royste	r BMP3	N/A	N	I/A	N/A		headwater BMP		N/A	399	ı	N/A	N/A	N/A		
	Royste	r BMP4	N/A	N	I/A	N/A		headwater BMP		N/A	1022	١	N/A	N/A	N/A		
	Royste	r BMP5	N/A	N	I/A	N/A		headwater BMP		N/A	669	ı	N/A	N/A	N/A		
	Lower Stick	Elliott Creek	1,422	110	)1+13	1115+34		cattle fencing; buffer planting		EII	1,389	:	2.5	-29	527.000		
	Scott	Creek	630	121	.0+12	1216+74		Priority 1 Restoration	R		R		662		1	19	681.000
	Scott Creel	SPSC BMP	N/A	N	I/A	N/A		headwater BMP		N/A	734	1	N/A	N/A	N/A		
	Carrol	l Creek	553	130	1+68	1307+63		Priority 2 Restoration		R	595		1	-56	539.000		
	Upper Big Ha	arris Creek R1	2,615	5 10	4+25	129+81	bank g	rading and in-stream structure removal and buffer planting	s; pine	EII	2,556		2.5	119	1141.000		
	Upper Big Ha	arris Creek R2	990	12	9+81	139+15		Priority 2 Restoration		R	934		1	126	1060.000		

Table 1. Project Components and Mitigation Credits

Big Harris Creek Mitigation Site DMS Project No. 739 Monitoring Year 3 - 2020

						Mi	itigation Credits							
			Stream		Riparian \	/etland	Non-riparian Wet	land	Buffer	Nitrogen Nut Offset	rient	osphorus Nutri	ent Offset	
Ту	pe	R	RE		R	RE	R	RE						
To	tals	25,228.12	1 101.79	5 N	I/A	N/A	N/A	N/A	N/A	N/A		N/A		
Project Area	Project	t Reach	Existing Footage	Stationin	g/Location	Pro	Approach		Restoration (R) or Restoration	Restoration Footage	Mitigation Ratio	Total Buffer Width	Proposed Credit <sup>2, 3, 4</sup>	
			, ,	100 75	140.4	catt	(P1, P2, etc.) le fencing; bank grading and in-s	tream	Equivalent (RE)	(LF) 1		Adjustments	540.000	
	Upper Big Ha	arris Creek R3	880	139+75	148+4	•	structures		EII	870	2	75	510.000	
	Upper Big Ha	arris Creek R4	1,203	148+76	159+1		Priority 2 Restoration		R	1,039	1	11	1050.000	
	Upper Big Harris Creek R5		845	159+58	168+0	5	le fencing; bank grading and in-s structures		EII	845	1.5	41	604.000	
	Upper Big Ha	rris Creek R6A	824	168+63	177+5	cattle	fencing; benching; bank grading stream structures	and in-	EII	855	1.5	1	571.000	
A	Upper Big Ha	rris Creek R6B	1,434	177+50	191+8	cattle f	cattle fencing; benching; bank grading and bank structures			1,403	1.5	-10	925.000	
	Upper Big	Harris BMP	N/A	N/A	N/A	headv	headwater BMP into Upper Big Harris Reach 5			166	N/A	N/A	N/A	
	UT1 to Upper E	Big Harris Creek	84	197+13	197+9	, bank	grading and in-stream structure removal and buffer planting	s; pine	EII	84	2.5	-8	26.000	
	UT2 to Upper E	Big Harris Creek	97	200+42	200+42 201+39 b		grading and in-stream structure removal and buffer planting	s; pine	EII	97	2.5	-4	35.000	
	UT3 to Upper E	Big Harris Creek	105	202+00	203+0	5	preservation		Р	105	10	0	11.000	
	UT4 to Upper E	Big Harris Creek	84	204+00	204+8	1	preservation		Р	84	10	-1	7.000	
	Elliott	Creek	1,389	1400+85	1412+0	6 bank	grading, segments of profile and restoration, in-stream structure		EI	1,121	1	42	1163.000	
	UT1 to Ell	liott Creek	141	1415+87	1417+2	8 bank	grading, segments of profile and restoration, in-stream structure		EI	141	1	-19	122.000	
	Bridges	Creek R1	445	1500+91	1504+6	7	Priority 1 Restoration		R	376	1	15	391.000	
	Bridges	Creek R2	366	1504+67	1507+8	4 ba	ank grading and in-stream struct	nd in-stream structures		317	2	9	168.000	
	UT1 to Bri	dges Creek	58	1510+46	1511+0	1	Priority 1 Restoration		R	55	1	-28	27.000	
В	Upper Stick Elli BN	iott Creek SPSC MP	N/A	N/A	N/A		headwater BMP into USEC		N/A	206	N/A	N/A	N/A	
	Upper Stick E	lliott Creek R1	352	1002+89	1006+9	8	Priority 1 Restoration		R	409	1	-55	354.000	
	Upper Stick Ell	liott Creek R2A	535	1006+98	1012+0	+00 bank grading and in-stream structures		EII	471	2	4	240.000		
	Upper Stick Ell	liott Creek R2B	334	1012+00	1015+1	bank grading and in-stream structures		5+10 bank grading and in-stream structures		EII	310	2	0	155.000
	Upper Stick Ell	liott Creek R3A	209	1015+10	1018+2	25 bank grading and benching			EII	315	2	17	175.000	
	Upper Stick Elliott Creek R3B 1,336 1018+25 1027+44 bank grading, benching, and in-stream structu			tructures	EII	889	2	21	465.000					

Table 1. Project Components and Mitigation Credits

Big Harris Creek Mitigation Site DMS Project No. 739 Monitoring Year 3 - 2020

								Mit	igation Credits																																												
			Stream	m		Ripa	ırian Wetl	land	Non-riparian Wet	land	Buff	er	Nitrogen Nut Offset	rient	Phos	phorus Nutrie	ent Offset																																				
Ty	rpe	R		RE		R		RE	R	RE																																											
То	tals	25,228.12	1	101.795	5	N/A		N/A	N/A	N/A	N/A	١	N/A			N/A																																					
					·		•	Proj	ect Components		•			•																																							
Project Area	Project	Reach		ing Footage	Statio	ning/Lo	cation		Approach		Restoration ( Restoration	n	Restoration Footage	Mitigati Ratio	on	Total Buffer Width	Proposed Credit <sup>2, 3, 4</sup>																																				
				(2.7)					(P1, P2, etc.)		Equivalent (	RE)	(LF) 1			Adjustments	Credit																																				
	Upper Stick Ell	iott Creek R4A		428	1038+1	.1 1	1042+08	attle fencing, bank grading and in-stream structure EII					397	2		-17	182.000																																				
	Upper Stick Ell	liott Creek R4B		113	1042+2	1042+28 1043+21		in-stream structures EII				in-stream structures		EII		113	1.5	-6		69.000																																	
	Upper Stick E	lliott Creek R5		1,909	1043+7	7 1	1058+84	F	Priority 2 -> Priority 1 Restoratio	n	R		1,507	1		89	1596.000																																				
	Upper Stick E	lliott Creek R6		1,036	1059+1	.4 1	1069+83	F	Priority 1 -> Priority 2 Restoratio	n	R		1,069	1		0	1069.000																																				
	UT1 to Upper S	tick Elliott Creek		50	1078+0	18 1	1078+80	bar	nk grading and in-stream structi	ures	EII		EII		72	1.5		-9	39.000																																		
В	UT2 to Upper S	tick Elliott Creek		56	1080+0	0 1	1081+54	re	connection; Priority 1 Restorati	on	R		154	1		-10	144.000																																				
	UT3 to Upper S	tick Elliott Creek		107	1082+0	00 1	1083+18	re	connection; Priority 1 Restorati	on	R		118	1		0	118.000																																				
	Upper Fletcl	ner Creek R1		1,493	1600+0	00 1	1615+71	1	isolated bank grading and in-stream structures, livestock fencing, invasives treatment			EII		EII		EII		EII		EII		EII		EII		EII		EII		EII		EII		EII		EII		EII		EII		EII		EII		EII		EII		2.5		16	644.000
	Upper Fletcl	ner Creek R2		1,465	1616+0	12 1	1630+09		Priority 2 Restoration			R		R		R		R		1		33	1440.000																														
	Lower Fletch	ner Creek R1		574	1641+2	18 1	1647+02	bank gra	ank grading, benching, and in-stream structures			EI		EI		EI		EI		EI		EI		EI		EI		EI		EI		EI		EI		EI		1		-81	493.000												
	Lower Fletch	ner Creek R2		467	1647+3	3 1	1651+60	bank gra	ding, benching, and in-stream s	s EI		EI		427	1		37	464.000																																			

### **Table 1. Project Components and Mitigation Credits**

Big Harris Creek Mitigation Site DMS Project No. 739

Monitoring Year 3 - 2020

								Mitigation C	redits							
			Stream			Riparian	Wetland		Non-riparian Wet	land	Buffer	Nitrogen N		Phosphoru	s Nutrie	ent Offset
Ту	pe	R		RE		R	RE		R	RE						
To	tals	25,228.12	1	101.79	5	N/A	N/A		N/A	N/A	N/A	N/A	4		N/A	
								Project Compo	onents							
Project Area	Project	t Reach		Footage	Stationi	ing/Locatio	on		Approach		Restoration (R) or Restoration	Restoration Footage	Mitiga Rati	, WI	dth	Proposed Credit <sup>2, 3, 4</sup>
			(1.1	,				•	P1, P2, etc.)		Equivalent (RE)	(LF) 1	(LF) 1		ments	Credit
	Lower Big Ha	rris Creek R1A	50	09	300+13	305+	-13 ba		gments of profile and n, in-stream structure		EI	500	1.5	-2	29	304.000
	Lower Big Harris Creek R1B		38	85	305+13	308+	-33	Prior	ity 2 Restoration		R	320	1	1	3	333.000
	Lower Big Harris Creek R2			87	308+33	318+	-00	Prior	ity 2 Restoration	R	967	1	12	25	1092.000	
c	Lower Big Ha	arris Creek R3	41	14	318+00		+14 isola	-	ding and in-stream st sives treatment	ructures,	EII	414	2.5	3	2	198.000
				229		332+	332+96 isolated		ding and in-stream stream stream streatment	ructures,	EII	228	2.5	-3	39	53.000
	UT2 to Lower Big Harris Creek 5.			11	334+20		-60 hea	•	ment with in-stream structures, wasives treatment		EII	440	2	-3	37	183.000
	UT3 to Lower E	Big Harris Creek	9	9	341+69	342+	-87	preservation			Р	118	10	-	1	11.000
	UT4 to Lower E	Big Harris Creek	36	62	343+12	346+	÷74	ı	preservation		Р	362	10		)	36.000
							Total Intermittent/Perennial (I/P				Perennial (I/P) Strear	ns 39,563				23,451.000
					Additional 4% Credit Based on I/P Stream Length for Extra Project Monitoring							g				1,366.000
						Add	ditional 1.5%	6 Credit Based	on I/P Stream Length	for Water	shed Nature of Proje	ct				512.000
						Additio	nal 2% Credi	it Based on Tot	tal SMUs for Statistic	al Improve	ment in Water Qualit	y <sup>5</sup>				507.000
											Potential Total Credit	s <sup>5</sup>				25,329.916
							Co	omponent Sun	nmation							
	Restoratio	on Level		Strear	n (linear fee	t) Rip	arian Wetla	nd (acres)	Non-Riparian	Wetland (a	acres) Buffe	r (square feet)		Upland	(acres)	
	Restora	ation			10,071											
	Enhance	ment			N/A											
	Enhancei	ment I			2,897											
	Enhancement II				20,524											
	Creation				N/A											
	Wetland Rehabilitation				N/A											
	Wetland Re-Es	tablishment			N/A											
	Preserva	ation			669											
	High Quality P	reservation			N/A											
Notes:				_							-		•			

- 1. Existing and proposed lengths include only reach length located within the conservation easement. No direct credit for BMPs. BMP lengths not included in proposed footage.
- 2. Credits reported have been adjusted based on buffer width deviations from standard 50-foot buffer width. Detailed calculations included in Appendix I of the Mitigation Plan (Wildlands, 2016).
- 3. The lengths of Royster Reach 2 and Scott Creek that are located underneath the existing overhead electric power line corridor have credits reduced by 100%.
- 4. The SMUs reported in this table were determined in the mitigation plan utilizing the design center line.
- The potential SMU total does not include the 2% increase for statistical improvement in water quality. If revised monitoring plan is approved, an addendum will be prepared and submitted.

Table 2. Project Activity and Reporting History
Big Harris Creek Mitigation Site
DMS Project No. 739
Maritaria No. 2000 Monitoring Year 3 - 2020

Activity or Report		Data Collection Complete	Completion or Scheduled Delivery
Mitigation Plan		February - July 2015	November 2016
Final Design - Construction Plans		May 2018	June 2018
Construction		April 2017 - May 2018	April 2017 - May 2018
Temporary S&E mix applied to entire project area <sup>1</sup>		April 2017 - May 2018	April 2017 - May 2018
Permanent seed mix applied to reach/segments		April 2017 - May 2018	April 2017 - May 2018
Bare root and live stake plantings for reach/segmer	nts	February 2018 - March 2018	February 2018 - March 2018
Develop Maritarian Develop (Version)	Stream Assessment	April 2018	2010
Baseline Monitoring Document (Year 0)	Vegetation Assessment	May 2018	June 2018
	Invasive Treatment	N/A	Summer 2018
Versión Maritaria	Stream Assessment	November 2018	D
Year 1 Monitoring	Vegetation Assessment	November 2018	December 2018
Version 2 Maritagina	Stream Assessment	March - October 2019	D
Year 2 Monitoring	Vegetation Assessment	August 2019	December 2019
Stream Repairs (l	JBHC R2B & R6, USEC R2 & R3, and LSEC)	August 2019	August 2019
	Invasive Treatments	October & December 2019	October & December 2019
Isolated bank remati	ing & live stakes (UBHC R6 and LBHC R2)	November 2019	November 2019
	Invasive Treatments	January & September 2020	January & September 2020
Si	ream Repairs (UBHC R5 & R6, and LSEC)	April 2020	April 2020
Voca 2 Monitorio	Stream Assessment	February - November 2020	Newson 2020
Year 3 Monitoring	Vegetation Assessment	July - August 2020	November 2020
Year 4 Monitoring		2021	December 2021
Year 5 Monitoring		2022	December 2022

<sup>&</sup>lt;sup>1</sup>Seed and mulch is added as each section of construction is completed.

Table 3. Project Contact Table Big Harris Creek Mitigation Site DMS Project No. 739 Monitoring Year 3 - 2020

Designers	Wildlands Engineering, Inc.
Emily Reinicker, PE, CFM	1430 South Mint Street, Suite 104
Angela Allen, PE - Area A	Charlotte, NC 28203
Jake McLean, PE, CFM - Area C	704.332.7754
	Ecosystem Planning & Restoration
Kevin Tweedy, PE - Area B	559 Jones Franklin Road, Suite 150
	Raleigh, NC 27606
	Land Mechanics Designs Incorporated
	780 Landmark Road
	Willow Springs, NC 27611
Construction Contractors	Fluvial Solutions Incorporated
	P.O. Box 28749
	Raleigh, NC 27611
	Bruton Natural Systems, Inc.
Planting Contractor	150 Old Black Creek Rd
	Freemont, NC 27830
Seeding Contractor	Land Mechanics Designs Incorporated
Seeding Contractor	Fluvial Solutions Incorporated
	Green Resource, LLC
	5204 Highgreen Court
Seed Mix Sources	Colfax, NC 27235
Seed With Sources	ACF Environmental
	3313 Durham Drive
	Raleigh, NC 27603
Nursery Stock Suppliers	Dykes & Son Nursery
Bare Roots	825 Maude Etter Rd.
	McMinnville, TN 37110
Live Stakes	Foggy Mountain Nursery
	797 Helton Creek Road
	Lansing, NC 28643
	Bruton Natural Systems, Inc.
Herbaceous Plugs	Wetland Plants Incorporated
	812 Drummonds Point Road
	Edenton, NC 27932
Monitoring Performers	Wildlands Engineering, Inc.
Monitoring, POC	Kristi Suggs
	704.332.7754, ext. 110

## Table 4a. Project Information and Attributes

Big Harris Creek Mitigation Site DMS Project No. 739 Monitoring Year 3 - 2020

### AREA A

AREA A																				
					Proj	ect In	format	tion												
Project Name	Big Harris	Creek Mi	tigation	Site																
	Cleveland	County																		
	145																			
Project Coordinates (latitude and longitude)	34° 24' 32	.70"N, 81	° 36' 41.	55"W																
		Project Watershed Summary Information																		
Physiographic Province	Piedmont	Physiogra	aphic Pro	ovince																
River Basin	Broad																			
	Warm																			
	03050105																			
	03050105	080060																		
	03-08-04																			
Project Drainage Area (acres)	2,509																			
Project Drainage Area Percentage of Impervious Area	<10%																			
CGIA Land Use Classification	Pasture (4	6%); Deci	iduous F	orest (22%); Ev	ergreen Forest (14%	s); Develo	oped (109	%); Herbace	ous (2%); Sh	rub/Scrub (	2%); Cul	tivated	Crops (	2%); Mix	ed Forest	t (1%); an	d Wood	y Wetla	nds (1%	
					Reach Su	ımmaı	ry Info	rmation												
		Area A																		
Parameters	Carroll Creek																			
		R 1 & 2		R1	R1	R1	R2			R1	R2a	R2b	R3	R4	R5	R6				
Length of reach (linear feet) - Post-Restoration	595	2,451	78	134	1,389	459	3,170	1,189	662	2,556	93	4	870	1,039	845	2,258	84	97	105	84
Drainage area (acres)	203	21	11	27	943	1	49	40	42						1,969					
NCDWR stream identification score	38	-	30	31.5/20.5	-	22.5	32	34/22.5	28.5	25 (I only)	-	-	-	-	-	-	-	-	-	24
NCDWR Water Quality Classification	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV
Morphological Description (stream type)	Р	Р	Р	P/I	Р	- 1	Р	P/I	I	P/I	Р	Р	Р	Р	Р	Р	Р	- 1	- 1	Р
Evolutionary trend (Simon's Model) - Pre- Restoration	IV/V	V	<b>′</b> I	IIIa	V	III/IV	V/VI	III, IV, V	III	III	II		IV	IV	III	Ш	III	III	III	III
Underlying mapped soils	Pacolet- Saw complex (PtD)	Chewac (Ch		Pacolet- Bethlehem complex (PbC2)	Toccoa loam (ToA)		cla loam hA)	Pacolet-Sa (P	w complex tD)					Chewa	cla loam	(ChA)				
Drainage class	Well drained Somewhat poorly drained Well drained Well drained Moderately well drained Well drained Somewhat poorly drained Somewhat poorly drained Somewhat poorly drained																			
Soil hydric status	No	Ye		No	No		'es		lo						Yes					
Slope	15-25%	0-2	2%	8-15%	0-2%	0-	2%	15-	25%						0-2%					
FEMA classification	-				LBHC Reache	es 1a, 1b,	, and 2 ar	e a mapped	Zone AE flo	odplain wit	h define	d base	flood el	evations						
Native vegetation community  Percent composition exotic invasive vegetation -Post- Restoration		Piedmont Alluvial Forest, Mesic Mixed Hardwood Forest, and Timber Forest (applies to UBHC - Reach 1, Reach 2, UT1, UT2, UT3 only)  0%																		

## Table 4b. Project Information and Attributes

Big Harris Creek Mitigation Site DMS Project No. 739 Monitoring Year 3 - 2020

### AREA A

		Regulatory Consider	rations
Regulation	Applicable?	Resolved?	Supporting Documentation
Waters of the United States - Section 404	Yes	Yes	USACE Nationwide Permit No.27 and DWQ 401 Water Quality Certification No. 4087.
Waters of the United States - Section 401	Yes	Yes	USACE Action ID #SAW-2009-0045
Division of Land Quality (Erosion and Sediment Contro	Yes	Yes	NPDES Construction Stormwater General Permit NCG010000
Endangered Species Act	Yes	Yes	Big Harris Creek Mitigation Plan; Wildlands determined "no effect" on Cleveland County listed endangered species. USFWS indicates project will have no impact on possible endangered plants and the possibility of incidental take of the northern long-eared bat is exempt under the 4(d) rule at this location (email correspondence from 12/18/2008 and 05/09/2016).
Historic Preservation Act	Yes	Yes	No historic resources were found to be impacted (letter from SHPO dated 6/25/2008).
Coastal Zone Management Act (CZMA)/Coastal Area Management Act (CAMA)	No	N/A	N/A
FEMA Floodplain Compliance	Yes	Yes	LBHC Reaches 1a, 1b, and 2 are a mapped Zone AE floodplain with defined base flood elevations. (FEMA Zone AE, FIRM panels 2620 and 2621).  Cleveland County Floodplain Development Permit #153715.
Essential Fisheries Habitat	No	N/A	N/A

# Table 4c. Project Information and Attributes

Big Harris Creek Mitigation Site DMS Project No. 739

Monitoring Year 3 - 2020

### AREA B

AREA B																			
				Pro	ject Inf	ormat	ion												
Project Name	Big Harr	is Creek Mit	tigation S	Site															
County		nd County	-																
Project Area (acres)	145.00	•																	
Project Coordinates (latitude and longitude)	34° 24' 3	32.70"N, 81	° 36' 41.5	55"W															
		Pro	oject V	<b>Vater</b>	shed Su	ımma	ry Info	rmati	on										
Physiographic Province	Piedmoi	nt Physiogra	aphic Pro	vince															
River Basin	Broad	Broad																	
Temperature Regime	Warm	Warm																	
USGS Hydrologic Unit 8-digit	0305010	03050105																	
USGS Hydrologic Unit 14-digit	0305010	33050105080060																	
DWR Sub-basin	03-08-0	4																	
Project Drainage Area (acres)	2509																		
Project Drainage Area Percentage of Impervious Area	<10%																		
CGIA Land Use Classification		Pasture (46%); Deciduous Forest (22%); Evergreen Forest (14%); Developed (10%); Herbaceous (2%); Shrub/Scrub (2%); Cultivated Crops (2%); Mixed Forest (1%); and Woody Wetlands (1%)																	
		,		ach C	ummar	ar Info	rmati												
			KE	acn 5	ummar	y inio	rmatic	)N	Λ	- P									
			1			1			Are	a B						1	1		
Parameters	Elliott Creek	Elliott Creek UT1	Bridges Creek		Bridges Creek UT1	LFC		USEC								USEC UT2	USEC UT3		O.P.C
	R1		R1	R2	<u>a</u>	R1	R2	R1	R2	R3	R4a	R4b	R5	R6				R1	R2
Length of reach (linear feet) - Post-Restoration	1,121	141	376	317	55	574	427	409	781	1,204	397	113	1,507	1,069	72	154	118	1,571	1 1,407
Drainage area (acres)		82		38		2	56						487						185
NCDWR stream identification score	33.5	33.5	33/25.5	-	24	38	-	33.5	-	-	-	-	-	-	25.5	33	25.5	-	-
NCDWR Water Quality Classification	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	/ WS-IV
Morphological Description (stream type)	Р	P	P/I	Р	ı	Р	P	P	P	Р	Р	Р	Р	P	- 1	Р	I	Р	Р
Evolutionary trend (Simon's Model) - Pre- Restoration	IV/V	III		III/IV/V/	VI	IV/V	III/IV	III/IV	IV/V	V	III/\	//VI	IV	IV/V	-	-	-		VI
Underlying mapped soils		acla loam ChA)	Pacole	t sandy ( (PaC2)	clay loam						Cl	newacla	loam (	ChA)	•	•			
Drainage class		hat poorly ained	V	Vell drai	ned	Somewhat poorly drained													
Soil hydric status		Yes		No								,	Yes						
Slope	(	)-2%		8-15%	)							0	-2%						
FEMA classification			•			•		no	regulate	d flood	plain								
Native vegetation community						Pied	lmont Al	luvial Fo	est and	Mesic N	1ixed H	ardwoo	d Fores	t					
Percent composition exotic invasive vegetation -Post-Restoration									0	%									

# **Table 4d. Project Information and Attributes**

Big Harris Creek Mitigation Site DMS Project No. 739 Monitoring Year 3 - 2020

## AREA B

	R	egulatory Consid	erations
Regulation	Applicable?	Resolved?	Supporting Documentation
Waters of the United States - Section 404	Yes	Yes	USACE Nationwide Permit No.27 and DWQ 401 Water Quality Certification No. 4087.
Waters of the United States - Section 401	Yes	Yes	USACE Action ID #SAW-2009-0045
Division of Land Quality (Erosion and Sediment Control)	Yes	Yes	NPDES Construction Stormwater General Permit NCG010000
Endangered Species Act	Yes	Yes	Big Harris Creek Mitigation Plan; Wildlands determined "no effect" on Cleveland County listed endangered species. USFWS indicates project will have no impact on possible endangered plants and the possibility of incidental take of the northern long-eared bat is exempt under the 4(d) rule at this location (email correspondence from 12/18/2008 and 05/09/2016).
Historic Preservation Act	Yes	Yes	No historic resources were found to be impacted (letter from SHPO dated 6/25/2008).
Coastal Zone Management Act (CZMA)/Coastal Area Management Act (CAMA)	No	N/A	N/A
FEMA Floodplain Compliance	Yes	Yes	LBHC Reaches 1a, 1b, and 2 are a mapped Zone AE floodplain with defined base flood elevations. (FEMA Zone AE, FIRM panels 2620 and 2621).  Cleveland County Floodplain Development Permit #153715.
Essential Fisheries Habitat	No	N/A	N/A

# **Table 4e. Project Information and Attributes**

Big Harris Creek Mitigation Site DMS Project No. 739 **Monitoring Year 3 - 2020** 

### ARFA C

AREA C												
Proje	ect Information											
Project Name	Big Har	ris Cree	k Mitigat	tion Site								
County	Cleveland County											
Project Area (acres)	145.00											
Project Coordinates (latitude and longitude)	34° 24'	32.70"N	V, 81° 36	' 41.55"V	V							
Project Watersh	ed Su	mmar	y Info	rmatio	on							
Physiographic Province	Piedmo	ont Phys	iographi	c Provinc	e							
River Basin	Broad											
Temperature Regime	Warm											
USGS Hydrologic Unit 8-digit	030501	.05										
USGS Hydrologic Unit 14-digit	030501	050800	60									
DWR Sub-basin	03-08-0	)4										
Project Drainage Area (acres)	2509											
Project Drainage Area Percentage of Impervious Area	<10%											
	Pasture	e (46%);	Deciduo	us Fores	t (22%); Eve	rgreen Fore	st (14%); Dev	eloped				
CGIA Land Use Classification	(10%);	Herbace	ous (2%	); Shrub/	Scrub (2%);	Cultivated (	Crops (2%); M	ixed Forest				
Reach Sui	nmary	/ Info	rmatic	on								
	Area C											
Parameters		į	ГВНС		LBHC UT1	LBHC UT2	LВНС UT3	LBHC UT4				
	R1a	R1b	R2	R3								
Length of reach (linear feet) - Post-Restoration	500	320	967	414	228	440	118	362				
Drainage area (acres)					2,509	)						
NCDWR stream identification score	-	-	1	-	-	35.5	32	35.5				
NCDWR Water Quality Classification	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV	WS-IV				
Morphological Description (stream type)	Р	P	P	Р	Р	Р	Р	Р				
Evolutionary trend (Simon's Model) - Pre- Restoration					IV/V			VI				
Underlying mapped soils					Toccoa Ioan	n (ToA)						
Drainage class			We	II draine	d and mode	rately well o	drained					
Soil hydric status					No							
Slope					0-2%							
FEMA classification		Zone AE	Ī		no	regulated f	loodplain					
Native vegetation community		Pied	lmont Al	luvial Fo	rest and Me	sic Mixed H	ardwood Fore	est				
Percent composition exotic invasive vegetation -Post-Restoration	invasive vegetation -Post-Restoration 0%											

# **Table 4f. Project Information and Attributes**

Big Harris Creek Mitigation Site DMS Project No. 739 Monitoring Year 3 - 2020

## AREA C

	Regulatory	Consider	ations						
Regulation	Applicable?	Resolved?	Supporting Documentation						
Waters of the United States - Section 404	Yes	Yes	USACE Nationwide Permit No.27 and DWQ 401 Water Quality Certification No. 4087.						
Waters of the United States - Section 401	Yes	Yes	USACE Action ID #SAW-2009-0045.						
Division of Land Quality (Erosion and Sediment Control)	Yes	Yes	NPDES Construction Stormwater General Permit NCG010000						
Endangered Species Act	Yes	Yes	Big Harris Creek Mitigation Plan; Wildlands determined "no effect" on Cleveland County listed endangered species. USFWS indicates project will have no impact on possible endangered plants and the possibility of incidental take of the northern long-eared bat is exempt under the 4(d) rule at this location (email correspondence from 12/18/2008 and 05/09/2016).						
Historic Preservation Act	Yes	Yes	No historic resources were found to be impacted (letter from SHPO dated 6/25/2008).						
Coastal Zone Management Act (CZMA)/Coastal Area Management Act (CAMA)	No	N/A	N/A						
FEMA Floodplain Compliance	Yes	Yes	LBHC Reaches 1a, 1b, and 2 are a mapped Zone AE floodplain with defined base flood elevations.  (FEMA Zone AE, FIRM panels 2620 and 2621). Cleveland County Floodplain Development Permit  #153715.						
Essential Fisheries Habitat	No	N/A	N/A						

### **Table 5a. Monitoring Component Summary**

Big Harris Creek Mitigation Site DMS Project No. 739 Monitoring Year 3 - 2020

Area A - Restoration and Enhancement I Reaches

Area A - Restoration and I				Quantity / Le	ngth by Reach				
Parameter	Monitoring Feature	Carroll Royster Creek Creek R1		Scott Creek UBHC R2		UBHC R4	Eaker Creek	Frequency	Notes
Dimension	Riffle Cross-Section 1 1 1		2	2	N/A	Annual			
Dimension	Pool Cross-Section	1	1	1	2	2 2		Alliudi	
Pattern	Pattern	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
Profile	Longitudinal Profile	N/A	N/A	N/A	N/A	N/A	N/A	N/A	1
Substrate	Reach Wide (RW) / Riffle (RF) 100 Pebble Count	1 RW, 1 RF	1 RW, 1 RF	1 RW, 1 RF	1 RW, 2RF 1 RW, 2RF		N/A	Annual	
Hydrology	Crest Gage/Transducer	1	1	1	1	N/A	Quarterly	2	
Vegetation	CVS Level 2			16			N/A	Annual	3
Water Quality	4 baseflow, 4 stormflow grab samples						N/A	Years 3, 4, and 5	
Benthic Macroinvertebrates	NCDWR Qual 4	up to 10 loca	tions throughout p	roject areas A,	B, & C and 1 refe	erence location	N/A	Years 3, 4, and 5	
Fisheries	NCDWR SOP						N/A	Year 5	
Exotic and Nuisance Vegetation								Semi-Annual	4
Project Boundary								Semi-Annual	5
Reference Photos	Photographs			Annual					

### Notes

- 1. Pattern and profile will be assessed visually during semi-annual site visits. Longitudinal profile will be collected during as-built baseline monitoring only, unless observations indicate a lack of stability and a profile survey is warranted in additional years.
- 2. Crest gages and/or transducers will be inspected quarterly or semi-annually, evidence of bankfull events will be documented with a photo when possible. Transducers will be set to record stage once every hour. Devices will be inspected and downloaded semi-annually. In addition, Scott Creek and Royster Creek Reach 1 will be monitored for the presence of baseflow (minimun of 30 consecutives days).
- 3. The total number of vegetation monitoring plots represents 2% of the open planted area. This is a reduction from the number of vegetation plots proposed in the Mitigation Plan, which was based on 2% of the entire conservation easement. IRT and DMS approved the change in January 2018.
- 4. Locations of exotic and nuisance vegetation will be mapped.
- 5. Locations of vegetation damage, boundary encroachments, etc. will be mapped.

## **Table 5b. Monitoring Component Summary**

Big Harris Creek Mitigation Site DMS Project No. 739 **Monitoring Year 3 - 2020** 

### Area A - Enhancement II Reaches

Area A - Ennancemer					Quar	ntity / Leng	th by Rea	ach					
Parameter	Monitoring Feature	Cornwell Creek	Cornwell Creek UT1	LSEC	Royster Creek R2	Scism Creek	UBHC R1	UBHC R3	UBHC R5	UBHC R6	UBHC UT1 & UT2	Frequency	Notes
Dimension	Riffle Cross-Section	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Annual	
Differsion	Pool Cross-Section	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Annuai	
Pattern	Pattern	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Annual	
Profile	Longitudinal Profile	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Annual	
Substrate	Reach Wide (RW) / Riffle (RF) 100 Pebble Count	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Annual	
Hydrology	Crest Gage/Transducer	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Quarterly	
Vegetation	CVS Level 2					18						Annual	1
Exotic and Nuisance Vegetation													
Project Boundary													
Reference Photos	Photographs					38						Annual	4

### Notes:

- 1. The total number of vegetation monitoring plots represents 2% of the open planted area. This is a reduction from the number of vegetation plots proposed in the Mitigation Plan, which was based on 2% of the entire conservation easement. IRT and DMS approved this change in January 2018.
- 2. Locations of exotic and nuisance vegetation will be mapped.
- 3. Locations of vegetation damage, boundary encroachments, etc. will be mapped.
- 4. Photographs will be taken along preservation reaches not noted above (3 photographs total).

### **Table 5c. Monitoring Component Summary**

Big Harris Creek Mitigation Site DMS Project No. 739 Monitoring Year 3 - 2020

Area B - Restoration and Enhancement I Reaches

	Limancement i ke	Quantity / Length by Reach													
Parameter	Monitoring Feature	Elliott Creek	Elliott Creek UT1	Bridges Creek R1	Bridges Creek UT1	LFC R1	LFC R2	Upper Stick Elliott Creek R1	USEC R5	USEC R6	USEC UT2	USEC UT3	UFC R2	Frequency	Notes
a	Riffle Cross-Section	2	1	1	N/A	1	1	1	3	2	1	1	3		
Dimension	Pool Cross-Section	1	0	0	N/A	1	1	0	2	1	0	0	3	Annual	
Pattern	Pattern	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Annual	
Profile	Longitudinal Profile	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Annual	1
Substrate	Reach Wide (RW) / Riffle (RF) 100 Pebble Count	1 RW, 2 RF	1 RW, 1 RF	1 RW, 1 RF	N/A	1 RW, 1 RF	1 RW, 1 RF	1 RW, 1 RF	1 RW, 3 RF	1 RW, 2 RF	1 RW, 1 RF	1 RW, 1 RF	1 RW, 3RF	Annual	
Hydrology	Crest Gage/Transducer	1	1	1	N/A	:	1	1	:	1	1	1	1	Quarterly	2
Vegetation	CVS Level 2						13							Annual	3
Water Quality	4 baseflow, 4 stormflow grab samples													Years 3, 4, and 5	
Benthic Macroinvertebrates	NCDWR Qual 4			up to 10 l	ocations throu	ghout pro	ject areas	s A, B, & C and 1	reference	location				Years 3, 4, and 5	
Fisheries	NCDWR SOP													Year 5	
Exotic and Nuisance Vegetation														Semi-Annual	4
Project Boundary														Semi-Annual	5
Reference Photos	Photographs						27							Annual	

### Notes:

- 1. Pattern and profile will be assessed visually during semi-annual site visits. Longitudinal profile will be collected during as-built baseline monitoring survey only, unless observations indicate a lack of stability and a profile survey is warranted in additional years.
- 2. Crest gages and/or transducers will be inspected quarterly or semi-annually, evidence of bankfull events will be documented with a photo when possible. Transducers will be set to record stage once every hour. Device will be inspected and downloaded semi-annually. In addition, Bridges Creek will be monitored for the presence of baseflow (minimum of 30 consecutives days).
- 3. The total number of vegetation monitoring plots represents 2% of the open planted area. This is a reduction from the number of vegetation plots proposed in the Mitigation Plan, which was based on 2% of the entire conservation easement. IRT and DMS approved this change in January 2018.
- 4. Locations of exotic and nuisance vegetation will be mapped.
- 5. Locations of vegetation damage, boundary encroachments, etc. will be mapped.

## **Table 5d. Monitoring Component Summary**

Big Harris Creek Mitigation Site DMS Project No. 739 **Monitoring Year 2 - 2019** 

**Area B - Enhancement II Reaches** 

Area B - Ellitaricement ii r				Quantity / Ler	ngth by Reach				
Parameter	Monitoring Feature	Bridges Creek R2	USEC R2	USEC R3	USEC R4a/4b	USEC UT1	UFC R1	Frequency	Notes
Dimension	Riffle Cross-Section	N/A	N/A	N/A	N/A	N/A	N/A	Annual	
Difficision	Pool Cross-Section	N/A	N/A	N/A	N/A	N/A	N/A	Ailliudi	
Pattern	Pattern	N/A	N/A	N/A	N/A	N/A	N/A	Annual	
Profile	Longitudinal Profile	N/A	N/A	N/A	N/A	N/A	N/A	Annual	
Substrate	Reach Wide (RW) / Riffle (RF) 100 Pebble Count	N/A	N/A	N/A	N/A	N/A	N/A	Annual	
Hydrology	Crest Gage/Transducer	N/A	N/A	N/A	N/A	N/A	N/A	Quarterly	
Vegetation	CVS Level 2			Ę	5			Annual	1
Exotic and Nuisance Vegetation								Semi-Annual	2
Project Boundary								Semi-Annual	3
Reference Photos	Photographs			1	2			Annual	

#### Notes:

- 1. The total number of vegetation monitoring plots represents 2% of the open planted area. This is a reduction from the number of vegetation plots proposed in the Mitigation Plan, which was based on 2% of the entire conservation easement that included supplemental planting areas. IRT and DMS approved this change in January 2018.
- 2. Locations of exotic and nuisance vegetation will be mapped
- 3. Locations of vegetation damage, boundary encroachments, etc. will be mapped.

#### **Table 5e. Monitoring Component Summary**

Big Harris Creek Mitigation Site DMS Project No. 739 **Monitoring Year 3 - 2020** 


Area C - Restoration, Enhancement I, and II Reaches

Area C - Restoration, Enha	incement i, and it is	uciics	Quantity / Leng				
Parameter	Monitoring Feature	LBHC Reach 1a	LBHC Reaches 1b & 2	LBHC UT1	LBHC UT2	Frequency	Notes
Dimension	Riffle Cross-Section	1	1	N/A	N/A	Annual	
Dimension	Pool Cross-Section	1	1	N/A	N/A	Alliudi	
Pattern	Pattern	N/A	N/A	N/A	N/A	Annual	
Profile	Longitudinal Profile	N/A	N/A	N/A N/A N/A		Annual	1
Substrate	Reach Wide (RW) / Riffle (RF) 100 Pebble Count	1 RW, 1 RF	1 RW, 1 RF	N/A	N/A	Annual	
Hydrology	Crest Gage/Transducer	1	1	N/A	N/A	Quarterly	2
Vegetation	CVS Level 2		4			Annual	3
Water Quality	4 baseflow, 4 stormflow grab samples	un to 10 loca	tions throughout p	roject areas A	P. & Cand 1	Years 3, 4, and 5	
Benthic Macroinvertebrates	NCDWR Qual 4	up to 10 loca	reference le		b, & C and 1	Years 3, 4, and 5	
Fisheries	NCDWR SOP					Year 5	
Exotic and Nuisance Vegetation					Semi-Annual	4	
Project Boundary					Semi-Annual	5	
Reference Photos	Photographs		12		Annual	6	

#### Notes:


- 1. Pattern and profile will be assessed visually during semi-annual site visits. Longitudinal profile will be collected during as-built baseline monitoring survey only, unless observations indicate a lack of stability and a profile survey is warranted in additional years.
- 2. Crest gages and/or transducers will be inspected quarterly or semi-annually, evidence of bankfull events will be documented with a photo when possible. Transducers will be set to record stage once every hour. Device will be inspected and downloaded semi-annually.
- 3. The total number of vegetation monitoring plots represents 2% of the open planted area. This is a reduction from the number of vegetation plots proposed in the Mitigation Plan, which was based on 2% of the entire conservation easement. IRT and DMS approved this change in January 2018.
- 4. Locations of exotic and nuisance vegetation will be mapped.
- 5. Locations of vegetation damage, boundary encroachments, etc. will be mapped.
- 6. Photographs will be taken along preservation reaches not noted above (2 photographs total).
















0 125 250 Feet L \_\_\_\_\_\_\_




Figure 3.1 Integrated Current Condition Plan View
Big Harris Creek Mitigation Site - Area A
DMS Project No. 739
Monitoring Year 3 - 2020
Cleveland County, NC


















0 125 250 Feet


Figure 3.3 Integrated Current Condition Plan View
Big Harris Creek Mitigation Site - Area A
DMS Project No. 739
Monitoring Year 3 - 2020


































Figure 3.6 Integrated Current Condition Plan View
Big Harris Creek Mitigation Site - Area A
DMS Project No. 739
Monitoring Year 3 - 2020
























Figure 3.8 Integrated Current Condition Plan View
Big Harris Creek Mitigation Site - Area A
DMS Project No. 739
Monitoring Year 3 - 2020








0 150 300 Feet

Figure 3.9 Integrated Current Condition Plan View
Big Harris Creek Mitigation Site - Area A
DMS Project No. 739
Monitoring Year 3 - 2020
Cleveland County, NC








0 150 300 Feet




Figure 3.10 Integrated Current Condition Plan View
Big Harris Creek Mitigation Site - Area B
DMS Project No. 739
Monitoring Year 3 - 2020
Cleveland County, NC

















0 100 200 Feet

Figure 3.12 Integrated Current Condition Plan View
Big Harris Creek Mitigation Site - Area B
DMS Project No. 739
Monitoring Year 3 - 2020
Cleveland County, NC








0 125 250 Feet



Figure 3.13 Integrated Current Condition Plan View
Big Harris Creek Mitigation Site - Area B
DMS Project No. 739
Monitoring Year 3 - 2020
Cleveland County, NC



100

200 Feet






Figure 3.14 Integrated Current Condition Plan View
Big Harris Creek Mitigation Site - Area B

DMS Project No. 739

Monitoring Year 3 - 2020







) 125 250 Feet



# Table 6a. Visual Stream Morphology Stability Assessment Table

Big Harris Creek Stream Mitigation Site DMS Project No. 95 739 Monitoring Year 3 - 2020

Area A- Eaker Creek - 134 LF

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-Built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjust % for Stabilizing Woody Vegetation
	1. Vertical Stability	Aggradation			0	0	100%			
	(Riffle and Run units)	Degradation			0	0	100%			
	2. Riffle Condition	Texture/Substrate	1	1			100%			
	3. Meander Pool	Depth Sufficient	1	1			100%			
1. Bed	Condition	Length Appropriate	1	1			100%			
	4. Thalweg Position	Thalweg centering at upstream of meander bend (Run)	1	1			100%			
	4. Illaiweg Position	Thalweg centering at downstream of meander bend (Glide)	1	1			100%			
	1. Scoured/Eroded	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			0	0	100%	0	0	100%
2. Bank	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does NOT include undercuts that are modest, appear sustainable and are providing habitat.			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
	•			Totals	0	0	100%	0	0	100%
	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	n/a	n/a			n/a			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill	n/a	n/a			n/a			
3. Engineered	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	n/a	n/a			n/a			
Structures <sup>1</sup>	3. Bank Protection	Bank erosion within the structures extent of influence does not exceed 15%.	n/a	n/a			n/a			
	4. Habitat	Pool forming structures maintaining  ~Max Pool Depth: Bankfull Depth ≥ 1.6  Rootwads/logs providing some cover at baseflow.	n/a	n/a			n/a			

<sup>&</sup>lt;sup>1</sup>Excludes constructed riffles since they are evaluated in section 1.

# Table 6b. Visual Stream Morphology Stability Assessment Table

Big Harris Creek Stream Mitigation Site DMS Project No. 95 739 Monitoring Year 3 - 2020

Area A- Royster Creek R1 - 459 LF

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-Built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjust % for Stabilizing Woody Vegetation
	1. Vertical Stability	Aggradation			1	43	91%			
	(Riffle and Run units)	Degradation			0	0	100%			
	2. Riffle Condition	Texture/Substrate	8	9			89%			
	3. Meander Pool	Depth Sufficient	7	7			100%			
1. Bed	Condition	Length Appropriate	7	7			100%			
	4 Thehuse Besition	Thalweg centering at upstream of meander bend (Run)	7	7			100%			
	4. Thalweg Position	Thalweg centering at downstream of meander bend (Glide)	7	7			100%			
		•								
	1. Scoured/Eroded	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			0	0	100%	0	0	100%
2. Bank	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does NOT include undercuts that are modest, appear sustainable and are providing habitat			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
			<u> </u>	Totals	0	0	100%	0	0	100%
	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	13	14			93%			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill	11	12			92%			
3. Engineered	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	12	12			100%			
Structures <sup>1</sup>	3. Bank Protection	Bank erosion within the structures extent of influence does not exceed 15%.	3	3			100%			
	4. Habitat	Pool forming structures maintaining	12	12			100%			

<sup>&</sup>lt;sup>1</sup>Excludes constructed riffles since they are evaluated in section 1.

# Table 6c. Visual Stream Morphology Stability Assessment Table

Big Harris Creek Stream Mitigation Site DMS Project No. 95 739 Monitoring Year 3 - 2020

# Area A- Scott Creek - 662 LF

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-Built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjust % for Stabilizing Woody Vegetation
	1. Vertical Stability	Aggradation			0	0	100%			
	(Riffle and Run units)	Degradation			1	11	98%			
	2. Riffle Condition	Texture/Substrate	10	10			100%			
4.5.4	3. Meander Pool	Depth Sufficient	5	5			100%			
1. Bed	Condition	Length Appropriate	5	5			100%			
	4. Thalweg Position	Thalweg centering at upstream of meander bend (Run)	5	5			100%			
	4. Malweg Fusition	Thalweg centering at downstream of meander bend (Glide)	5	5			100%			
	1. Scoured/Eroded	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			1	11	99%	0	0	99%
2. Bank	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does NOT include undercuts that are modest, appear sustainable and are providing habitat			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
				Totals	1	11	99%	0	0	99%
	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	19	19			100%			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill	19	19			100%			
3. Engineered	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	19	19			100%			
Structures <sup>1</sup>	3. Bank Protection	Bank erosion within the structures extent of influence does not exceed 15%.	2	2			100%			
	4. Habitat	Pool forming structures maintaining ~Max Pool Depth : Bankfull Depth ≥ 1.6 Rootwads/logs providing some cover at baseflow.	19	19			100%			

<sup>&</sup>lt;sup>1</sup>Excludes constructed riffles since they are evaluated in section 1.

# Table 6d. Visual Stream Morphology Stability Assessment Table

Big Harris Creek Stream Mitigation Site DMS Project No. 95 739 Monitoring Year 3 - 2020

Area A- Carroll Creek - 595 LF

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-Built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjust % for Stabilizing Woody Vegetation
	1. Vertical Stability	Aggradation			0	0	100%			
	(Riffle and Run units)	Degradation			0	0	100%			
	2. Riffle Condition	Texture/Substrate	10	10			100%			
	3. Meander Pool	Depth Sufficient	9	9			100%			
1. Bed	Condition	Length Appropriate	9	9			100%			
	4 Thelius Desition	Thalweg centering at upstream of meander bend (Run)	9	9			100%			
	4. Thalweg Position	Thalweg centering at downstream of meander bend (Glide)	9	9			100%			
	1. Scoured/Eroded	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			0	0	100%	0	0	100%
2. Bank	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does NOT include undercuts that are modest, appear sustainable and are providing habitat			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
				Totals	0	0	100%	0	0	100%
	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	1	1			100%			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill	1	1			100%			
3. Engineered Structures <sup>1</sup>	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	1	1			100%			
Structures	3. Bank Protection	Bank erosion within the structures extent of influence does not exceed 15%.	1	1			100%			
	4. Habitat	Pool forming structures maintaining ~Max Pool Depth: Bankfull Depth ≥ 1.6 Rootwads/logs providing some cover at baseflow.	1	1			100%			

<sup>&</sup>lt;sup>1</sup>Excludes constructed riffles since they are evaluated in section 1.

# Table 6e. Visual Stream Morphology Stability Assessment Table

Big Harris Creek Stream Mitigation Site DMS Project No. 95 739 Monitoring Year 3 - 2020

# Area A- UBHC R2 - 934 LF

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-Built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjust % for Stabilizing Woody Vegetation
	1. Vertical Stability	Aggradation			0	0	100%			
	(Riffle and Run units)	Degradation			1	28	97%			
	2. Riffle Condition	Texture/Substrate	16	17			94%			
	3. Meander Pool	Depth Sufficient	15	15			100%			
1. Bed	Condition	Length Appropriate	15	15			100%			
	4. Thalweg Position	Thalweg centering at upstream of meander bend (Run)	15	15			100%			
	4. Inalweg Position	Thalweg centering at downstream of meander bend (Glide)	15	15			100%			
	1. Scoured/Eroded	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			1	34	98%	0	0	98%
2. Bank	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does NOT include undercuts that are modest, appear sustainable and are providing habitat			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
	<del> </del>			Totals	1	34	98%	0	0	98%
	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	7	7			100%			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill	7	7			100%			
3. Engineered	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	7	7			100%			
Structures <sup>1</sup>	3. Bank Protection	Bank erosion within the structures extent of influence does not exceed 15%.	7	7			100%			
	4. Habitat	Pool forming structures maintaining  "Max Pool Depth: Bankfull Depth ≥ 1.6  Rootwads/logs providing some cover at baseflow.	9	9			100%			

<sup>&</sup>lt;sup>1</sup>Excludes constructed riffles since they are evaluated in section 1.

# Table 6f. Visual Stream Morphology Stability Assessment Table

Big Harris Creek Stream Mitigation Site DMS Project No. 95 739 Monitoring Year 3 - 2020

# Area A- UBHC R4 - 1,039 LF

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-Built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjust % for Stabilizing Woody Vegetation
	1. Vertical Stability	Aggradation			0	0	100%			
	(Riffle and Run units)	Degradation			0	0	100%			
	2. Riffle Condition	Texture/Substrate	10	10			100%			
	3. Meander Pool	Depth Sufficient	10	10			100%			
1. Bed	Condition	Length Appropriate	10	10			100%			
	4 Thebase Besision	Thalweg centering at upstream of meander bend (Run)	10	10			100%			
	4. Thalweg Position	Thalweg centering at downstream of meander bend (Glide)	10	10			100%			
	1. Scoured/Eroded	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			1	36	98%	0	0	98%
2. Bank	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does NOT include undercuts that are modest, appear sustainable and are providing habitat			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
				Totals	1	36	98%	0	0	98%
	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	1	1			100%			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill	n/a	n/a			n/a			
3. Engineered	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	n/a	n/a			n/a			
Structures <sup>1</sup>	3. Bank Protection	Bank erosion within the structures extent of influence does not exceed 15%.	1	1			100%			
	4. Habitat	Pool forming structures maintaining ~Max Pool Depth: Bankfull Depth ≥ 1.6 Rootwads/logs providing some cover at baseflow.	1	1			100%			

<sup>&</sup>lt;sup>1</sup>Excludes constructed riffles since they are evaluated in section 1.

# Table 6g. Visual Stream Morphology Stability Assessment Table

Big Harris Creek Stream Mitigation Site DMS Project No. 95 739 Monitoring Year 3 - 2020

Area B- Elliot Creek - 1,121 LF

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-Built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjust % for Stabilizing Woody Vegetation
	1. Vertical Stability	Aggradation			1	17	98%			
	(Riffle and Run units)	Degradation			0	0	100%			
	2. Riffle Condition	Texture/Substrate	19	19			100%			
	3. Meander Pool	Depth Sufficient	17	17			100%			
1. Bed	Condition	Length Appropriate	17	17			100%			
	4 Thehuse Besition	Thalweg centering at upstream of meander bend (Run)	17	17			100%			
	4. Thalweg Position	Thalweg centering at downstream of meander bend (Glide)	17	17			100%			
	1. Scoured/Eroded	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			4	50	98%	0	0	98%
2. Bank	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does NOT include undercuts that are modest, appear sustainable and are providing habitat			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
				Totals	4	50	98%	0	0	98%
	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	4	4			100%			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill	4	4			100%			
3. Engineered	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	4	4			100%			
Structures <sup>1</sup>	3. Bank Protection	Bank erosion within the structures extent of influence does not exceed 15%.	11	11			100%			
	4. Habitat	Pool forming structures maintaining  ~Max Pool Depth: Bankfull Depth ≥ 1.6  Rootwads/logs providing some cover at baseflow.	11	11			100%			

<sup>&</sup>lt;sup>1</sup>Excludes constructed riffles since they are evaluated in section 1.

# Table 6h. Visual Stream Morphology Stability Assessment Table

Big Harris Creek Stream Mitigation Site DMS Project No. 95 739 Monitoring Year 3 - 2020

## Area B- UT1 to Elliot Creek - 141 LF

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-Built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjust % for Stabilizing Woody Vegetation
	1. Vertical Stability	Aggradation			0	0	100%			
	(Riffle and Run units)	Degradation			0	0	100%			
	2. Riffle Condition	Texture/Substrate	5	5			100%			
	3. Meander Pool	Depth Sufficient	4	4			100%			
1. Bed	Condition	Length Appropriate	4	4			100%			
	A Theliuse Decision	Thalweg centering at upstream of meander bend (Run)	4	4			100%			
	4. Thalweg Position	Thalweg centering at downstream of meander bend (Glide)	4	4			100%			
	1. Scoured/Eroded	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			0	0	100%	0	0	100%
2. Bank	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does NOT include undercuts that are modest, appear sustainable and are providing habitat			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
				Totals	0	0	100%	0	0	100%
	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	2	2			100%			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill	2	2			100%			
3. Engineered	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	2	2			100%			
Structures <sup>1</sup>	3. Bank Protection	Bank erosion within the structures extent of influence does not exceed 15%.	n/a	n/a			n/a			
	4. Habitat	Pool forming structures maintaining ~Max Pool Depth : Bankfull Depth ≥ 1.6 Rootwads/logs providing some cover at baseflow.	2	2			100%			

<sup>&</sup>lt;sup>1</sup>Excludes constructed riffles since they are evaluated in section 1.

# Table 6i. Visual Stream Morphology Stability Assessment Table

Big Harris Creek Stream Mitigation Site DMS Project No. 95 739 Monitoring Year 3 - 2020

Area B- Bridges Creek R1 - 376 LF

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-Built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjust % for Stabilizing Woody Vegetation
	1. Vertical Stability	Aggradation			0	0	100%			
	(Riffle and Run units)	Degradation			0	0	100%			
	2. Riffle Condition	Texture/Substrate	10	10			100%			
	3. Meander Pool	Depth Sufficient	10	10			100%			
1. Bed	Condition	Length Appropriate	10	10			100%			
	4 Thebuse Besition	Thalweg centering at upstream of meander bend (Run)	10	10			100%			
	4. Thalweg Position	Thalweg centering at downstream of meander bend (Glide)	10	10			100%			
	1. Scoured/Eroded	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			0	0	100%	0	0	100%
2. Bank	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does NOT include undercuts that are modest, appear sustainable and are providing habitat			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
				Totals	0	0	100%	0	0	100%
	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	7	7			100%			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill	n/a	n/a			n/a			
3. Engineered	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	7	7			100%			
Structures <sup>1</sup>	3. Bank Protection	Bank erosion within the structures extent of influence does not exceed 15%.	7	7			100%			
	4. Habitat	Pool forming structures maintaining  ~Max Pool Depth: Bankfull Depth ≥ 1.6  Rootwads/logs providing some cover at baseflow.	7	7			100%			

<sup>&</sup>lt;sup>1</sup>Excludes constructed riffles since they are evaluated in section 1.

# Table 6j. Visual Stream Morphology Stability Assessment Table

Big Harris Creek Stream Mitigation Site DMS Project No. 95 739 Monitoring Year 3 - 2020

Area B- UT1 to Bridges Creek - 55 LF

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-Built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjust % for Stabilizing Woody Vegetation
	1. Vertical Stability	Aggradation			0	0	100%			
	(Riffle and Run units)	Degradation			0	0	100%			
	2. Riffle Condition	Texture/Substrate	2	2			100%			
	3. Meander Pool	Depth Sufficient	1	1			100%			
1. Bed	Condition	Length Appropriate	1	1			100%			
	4. Thalweg Position	Thalweg centering at upstream of meander bend (Run)	1	1			100%			
	4. Inalweg Position	Thalweg centering at downstream of meander bend (Glide)	1	1			100%			
	1. Scoured/Eroded	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			0	0	100%	0	0	100%
2. Bank	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does NOT include undercuts that are modest, appear sustainable and are providing habitat			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
	_			Totals	0	0	100%	0	0	100%
	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	2	2			100%			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill	n/a	n/a			n/a			
3. Engineered Structures <sup>1</sup>	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	2	2			100%			
Structures	3. Bank Protection	Bank erosion within the structures extent of influence does not exceed 15%.	2	2			100%			
	4. Habitat	Pool forming structures maintaining  ~Max Pool Depth: Bankfull Depth ≥ 1.6  Rootwads/logs providing some cover at baseflow.	2	2			100%			

<sup>&</sup>lt;sup>1</sup>Excludes constructed riffles since they are evaluated in section 1.

# Table 6k. Visual Stream Morphology Stability Assessment Table

Big Harris Creek Stream Mitigation Site DMS Project No. 95 739 Monitoring Year 3 - 2020

# Area B- USEC R1 - 409 LF

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-Built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjust % for Stabilizing Woody Vegetation
	Vertical Stability (Riffle and Run units)	Aggradation			0	0	100%			
		Degradation			1	58	86%			
	2. Riffle Condition	Texture/Substrate	11	15			73%			
	3. Meander Pool	Depth Sufficient	2	2			100%			
1. Bed	Condition	Length Appropriate	2	2			100%			
	4. Thalweg Position	Thalweg centering at upstream of meander bend (Run)	2	2			100%			
	4. Inalweg Position	Thalweg centering at downstream of meander bend (Glide)	2	2			100%			
	1. Scoured/Eroded	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			4	60	93%	0	0	93%
2. Bank	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does NOT include undercuts that are modest, appear sustainable and are providing habitat			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
				Totals	4	60	93%	0	0	93%
	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	2	2			100%			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill	2	2			100%			
3. Engineered	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	2	2			100%			
Structures <sup>1</sup>	3. Bank Protection	Bank erosion within the structures extent of influence does not exceed 15%.	n/a	n/a			n/a			
	4. Habitat	Pool forming structures maintaining  ~Max Pool Depth: Bankfull Depth ≥ 1.6  Rootwads/logs providing some cover at baseflow.	2	2			100%			

<sup>&</sup>lt;sup>1</sup>Excludes constructed riffles since they are evaluated in section 1.

#### Table 6l. Visual Stream Morphology Stability Assessment Table

Big Harris Creek Stream Mitigation Site DMS Project No. 95 739 Monitoring Year 3 - 2020

Area B- USEC R5 - 1,507 LF

Major Channel Category	Channel Sub-Category	Metric	Stable, Performing as Intended	Total Number in As-Built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Stabilizing Woody Vegetation	Stabilizing Woody Vegetation	Stabilizing Woody Vegetation
	1. Vertical Stability	Aggradation			0	0	100%		,	
	(Riffle and Run units)	Degradation			0	0	100%			
	2. Riffle Condition	Texture/Substrate	15	15			100%			
	3. Meander Pool	Depth Sufficient	13	13			100%			
1. Bed	Condition	Length Appropriate	13	13			100%			
	4. Thalweg Position	Thalweg centering at upstream of meander bend (Run)	13	13			100%			
	4. Thatweg Position	Thalweg centering at downstream of meander bend (Glide)	13	13			100%			
	1. Scoured/Eroded	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			0	0	100%	0	0	100%
2. Bank	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does NOT include undercuts that are modest, appear sustainable and are providing habitat			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
				Totals	0	0	100%	0	0	100%
	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	19	19			100%			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill	3	3			100%			
3. Engineered	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	3	3			100%			
Structures <sup>1</sup>	3. Bank Protection	Bank erosion within the structures extent of influence does not exceed 15%.	19	19			100%			

3

3

Number

Number with Footage with Adjust % for

100%

4. Habitat

extent of influence does not exceed 15%.

Pool forming structures maintaining

"Max Pool Depth: Bankfull Depth ≥ 1.6

Rootwads/logs providing some cover at

baseflow.

<sup>&</sup>lt;sup>1</sup>Excludes constructed riffles since they are evaluated in section 1.

# Table 6m. Visual Stream Morphology Stability Assessment Table

Big Harris Creek Stream Mitigation Site DMS Project No. 95 739 Monitoring Year 3 - 2020

Area B- USEC R6 - 1,069 LF

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-Built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjust % for Stabilizing Woody Vegetation
	1. Vertical Stability	Aggradation		·	0	0	100%			
	(Riffle and Run units)	Degradation			0	0	100%			
	2. Riffle Condition	Texture/Substrate	12	12			100%			
	3. Meander Pool	Depth Sufficient	9	9			100%			
1. Bed	Condition	Length Appropriate	9	9			100%			
	4. Thalweg Position	Thalweg centering at upstream of meander bend (Run)	9	9			100%			
	4. Illaiweg Fosition	Thalweg centering at downstream of meander bend (Glide)	9	9			100%			
	1. Scoured/Eroded	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			0,	0	100%	0	0	100%
2. Bank	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does NOT include undercuts that are modest, appear sustainable and are providing habitat			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
			<u> </u>	Totals	0	0	100%	0	0	100%
	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	12	12			100%			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill	2	2			100%			
3. Engineered Structures <sup>1</sup>	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	12	12			100%			
	3. Bank Protection	Bank erosion within the structures extent of influence does not exceed 15%.	12	12			100%			
	4. Habitat	Pool forming structures maintaining ~Max Pool Depth: Bankfull Depth ≥ 1.6 Rootwads/logs providing some cover at baseflow.	7	7			100%			

<sup>&</sup>lt;sup>1</sup>Excludes constructed riffles since they are evaluated in section 1.

# Table 6n. Visual Stream Morphology Stability Assessment Table

Big Harris Creek Stream Mitigation Site DMS Project No. 95 739 Monitoring Year 3 - 2020

## Area B- UT2 to USEC - 154 LF

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-Built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjust % for Stabilizing Woody Vegetation
	1. Vertical Stability	Aggradation			1	20	87%			
	(Riffle and Run units)	Degradation			0	0	100%			
	2. Riffle Condition	Texture/Substrate	2	3			67%			
	3. Meander Pool	Depth Sufficient	2	2			100%			
1. Bed	Condition	Length Appropriate	2	2			100%			
	4. Thalweg Position	Thalweg centering at upstream of meander bend (Run)	2	2			100%			
	4. Illaiweg Position	Thalweg centering at downstream of meander bend (Glide)	2	2			100%			
	1	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			0	0	100%	0	0	100%
2. Bank	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does NOT include undercuts that are modest, appear sustainable and are providing habitat			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
			<b>'</b>	Totals	0	0	100%	0	0	100%
	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	n/a	n/a			n/a			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill	n/a	n/a			n/a			
3. Engineered Structures <sup>1</sup>	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	n/a	n/a			n/a			
	3. Bank Protection	Bank erosion within the structures extent of influence does not exceed 15%.	n/a	n/a			n/a			
	4. Habitat	Pool forming structures maintaining ~Max Pool Depth : Bankfull Depth ≥ 1.6 Rootwads/logs providing some cover at baseflow.	n/a	n/a			n/a			

<sup>&</sup>lt;sup>1</sup>Excludes constructed riffles since they are evaluated in section 1.

# Table 60. Visual Stream Morphology Stability Assessment Table

Big Harris Creek Stream Mitigation Site DMS Project No. 95 739 Monitoring Year 3 - 2020

## Area B- UT3 to USEC - 118 LF

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-Built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjust % for Stabilizing Woody Vegetation
	1. Vertical Stability	Aggradation			0	0	100%			
	(Riffle and Run units)	Degradation			0	0	100%			
	2. Riffle Condition	Texture/Substrate	4	4			100%			
	3. Meander Pool	Depth Sufficient	2	2			100%			
1. Bed	Condition	Length Appropriate	2	2			100%			
	4 Thelius Pesition	Thalweg centering at upstream of meander bend (Run)	2	2			100%			
	4. Thalweg Position	Thalweg centering at downstream of meander bend (Glide)	2	2			100%			
	1. Scoured/Eroded	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			0	0	100%	0	0	100%
2. Bank	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does NOT include undercuts that are modest, appear sustainable and are providing habitat			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
				Totals	0	0	100%	0	0	100%
	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	n/a	n/a			n/a			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill	n/a	n/a			n/a			
3. Engineered	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	n/a	n/a			n/a			
Structures <sup>1</sup>	3. Bank Protection	Bank erosion within the structures extent of influence does not exceed 15%.	n/a	n/a			n/a			
	4. Habitat	Pool forming structures maintaining "Max Pool Depth: Bankfull Depth ≥ 1.6 Rootwads/logs providing some cover at baseflow.	n/a	n/a			n/a			

<sup>&</sup>lt;sup>1</sup>Excludes constructed riffles since they are evaluated in section 1.

# Table 6p. Visual Stream Morphology Stability Assessment Table

Big Harris Creek Stream Mitigation Site DMS Project No. 95 739 Monitoring Year 3 - 2020

Area B- UFC R2 - 1,407 LF

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-Built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjust % for Stabilizing Woody Vegetation
	1. Vertical Stability	Aggradation			2	56	96%			
	(Riffle and Run units)	Degradation			0	0	100%			
	2. Riffle Condition	Texture/Substrate	18	18			100%			
	3. Meander Pool	Depth Sufficient	14	16			88%			
1. Bed	Condition	Length Appropriate	16	16			100%			
	4 Thehuse Besition	Thalweg centering at upstream of meander bend (Run)	16	16			100%			
	4. Thalweg Position	Thalweg centering at downstream of meander bend (Glide)	16	16			100%			
	1. Scoured/Eroded	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			0	0	100%	0	0	100%
2. Bank	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does NOT include undercuts that are modest, appear sustainable and are providing habitat			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
				Totals	0	0	100%	0	0	100%
	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	19	19			100%			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill	2	2			100%			
3. Engineered	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	19	19			100%			
Structures <sup>1</sup>	3. Bank Protection	Bank erosion within the structures extent of influence does not exceed 15%.	19	19			100%			
	4. Habitat	Pool forming structures maintaining "Max Pool Depth : Bankfull Depth ≥ 1.6 Rootwads/logs providing some cover at baseflow.	2	2			100%			

<sup>&</sup>lt;sup>1</sup>Excludes constructed riffles since they are evaluated in section 1.

# Table 6q. Visual Stream Morphology Stability Assessment Table

Big Harris Creek Stream Mitigation Site DMS Project No. 95 739 Monitoring Year 3 - 2020

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-Built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjust % for Stabilizing Woody Vegetation
	1. Vertical Stability	Aggradation			0	0	100%			
	(Riffle and Run units)	Degradation			0	0	100%			
	2. Riffle Condition	Texture/Substrate	6	6			100%			
	3. Meander Pool	Depth Sufficient	5	5			100%			
1. Bed	Condition	Length Appropriate	5	5			100%			
	4 Thehuse Besition	Thalweg centering at upstream of meander bend (Run)	5	5			100%			
	4. Thalweg Position	Thalweg centering at downstream of meander bend (Glide)	5	5			100%			
		Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			0	0	100%	0	0	100%
2. Bank	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does NOT include undercuts that are modest, appear sustainable and are providing habitat			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
				Totals	0	0	100%	0	0	100%
	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	5	5			100%			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill	n/a	n/a			n/a			
3. Engineered	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	5	5			100%			
Structures <sup>1</sup>	3. Bank Protection	Bank erosion within the structures extent of influence does not exceed 15%.	5	5			100%			
	4. Habitat	Pool forming structures maintaining "Max Pool Depth: Bankfull Depth ≥ 1.6 Rootwads/logs providing some cover at baseflow.	5	5			100%			

<sup>&</sup>lt;sup>1</sup>Excludes constructed riffles since they are evaluated in section 1.

# Table 6r. Visual Stream Morphology Stability Assessment Table

Big Harris Creek Stream Mitigation Site DMS Project No. 95 739 Monitoring Year 3 - 2020

### Area B- LFC R2 - 427 LF

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-Built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjust % for Stabilizing Woody Vegetation
	1. Vertical Stability	Aggradation			0	0	100%			
	(Riffle and Run units)	Degradation			0	0	100%			
	2. Riffle Condition	Texture/Substrate	3	3			100%			
	3. Meander Pool	Depth Sufficient	2	2			100%			
1. Bed	Condition	Length Appropriate	2	2			100%			
	4 Thehuas Basitian	Thalweg centering at upstream of meander bend (Run)	2	2			100%			
	4. Thalweg Position	Thalweg centering at downstream of meander bend (Glide)	2	2			100%			
	1. Scoured/Eroded	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			0	0	100%	0	0	100%
2. Bank	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does NOT include undercuts that are modest, appear sustainable and are providing habitat			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
				Totals	0	0	100%	0	0	100%
	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	2	2			100%			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill	n/a	n/a			n/a			
3. Engineered Structures <sup>1</sup>	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	2	2			100%			
	3. Bank Protection	Bank erosion within the structures extent of influence does not exceed 15%.	2	2			100%			
	4. Habitat	Pool forming structures maintaining ~Max Pool Depth : Bankfull Depth ≥ 1.6 Rootwads/logs providing some cover at baseflow.	n/a	n/a			n/a			

<sup>&</sup>lt;sup>1</sup>Excludes constructed riffles since they are evaluated in section 1.

# Table 6s. Visual Stream Morphology Stability Assessment Table

Big Harris Creek Stream Mitigation Site DMS Project No. 95 739 Monitoring Year 3 - 2020

### Area C- LBHC R1A - 500 LF

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-Built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjust % for Stabilizing Woody Vegetation
	1. Vertical Stability	Aggradation			0	0	100%			
	(Riffle and Run units)	Degradation			0	0	100%			
	2. Riffle Condition	Texture/Substrate	4	4			100%			
_	3. Meander Pool	Depth Sufficient	4	4			100%			
1. Bed	Condition	Length Appropriate	4	4			100%			
	4. The large Decition	Thalweg centering at upstream of meander bend (Run)	4	4			100%			
	4. Thalweg Position	Thalweg centering at downstream of meander bend (Glide)	4	4			100%			
	1. Scoured/Eroded	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			0	0	100%	0	0	100%
2. Bank	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does NOT include undercuts that are modest, appear sustainable and are providing habitat			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
				Totals	0	0	100%	0	0	100%
	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	1	1			100%			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill	n/a	n/a			n/a			
3. Engineered	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	1	1			100%			
Structures <sup>1</sup>	3. Bank Protection	Bank erosion within the structures extent of influence does not exceed 15%.	1	1			100%			
	4. Habitat	Pool forming structures maintaining ~Max Pool Depth : Bankfull Depth ≥ 1.6 Rootwads/logs providing some cover at baseflow.	1	1			100%			

<sup>&</sup>lt;sup>1</sup>Excludes constructed riffles since they are evaluated in section 1.

# Table 6t. Visual Stream Morphology Stability Assessment Table

Big Harris Creek Stream Mitigation Site DMS Project No. 95 739 Monitoring Year 3 - 2020

### Area C- LBHC R1B - 320 LF

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-Built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjust % for Stabilizing Woody Vegetation
	1. Vertical Stability	Aggradation			0	0	100%			
	(Riffle and Run units)	Degradation			0	0	100%			
	2. Riffle Condition	Texture/Substrate	3	3			100%			
	3. Meander Pool	Depth Sufficient	2	2			100%			
1. Bed	Condition	Length Appropriate	2	2			100%			
	4. The large Decision	Thalweg centering at upstream of meander bend (Run)	2	2			100%			
	4. Thalweg Position	Thalweg centering at downstream of meander bend (Glide)	2	2			100%			
	1. Scoured/Eroded	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			0	0	100%	0	0	100%
2. Bank	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does NOT include undercuts that are modest, appear sustainable and are providing habitat			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
				Totals	0	0	100%	0	0	100%
	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	2	2			100%			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill	n/a	n/a			n/a			
3. Engineered	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	2	2			100%			
Structures <sup>1</sup>	3. Bank Protection	Bank erosion within the structures extent of influence does not exceed 15%.	2	2			100%			
	4. Habitat	Pool forming structures maintaining ~Max Pool Depth : Bankfull Depth ≥ 1.6 Rootwads/logs providing some cover at baseflow.	2	2			100%			

<sup>&</sup>lt;sup>1</sup>Excludes constructed riffles since they are evaluated in section 1.

# Table 6u. Visual Stream Morphology Stability Assessment Table

Big Harris Creek Stream Mitigation Site DMS Project No. 95 739 Monitoring Year 3 - 2020

### Area C- LBHC R2 - 967 LF

Major Channel Category	Channel Sub-Category	Metric	Number Stable, Performing as Intended	Total Number in As-Built	Number of Unstable Segments	Amount of Unstable Footage	% Stable, Performing as Intended	Number with Stabilizing Woody Vegetation	Footage with Stabilizing Woody Vegetation	Adjust % for Stabilizing Woody Vegetation
	1. Vertical Stability	Aggradation			0	0	100%			
	(Riffle and Run units)	Degradation			0	0	100%			
	2. Riffle Condition	Texture/Substrate	6	6			100%			
	3. Meander Pool	Depth Sufficient	6	6			100%			
1. Bed	Condition	Length Appropriate	6	6			100%			
	4. Thalweg Position	Thalweg centering at upstream of meander bend (Run)	6	6			100%			
	4. maiweg Position	Thalweg centering at downstream of meander bend (Glide)	6	6			100%			
	1. Scoured/Eroded	Bank lacking vegetative cover resulting simply from poor growth and/or scour and erosion			5	121	94%	0	0	94%
2. Bank	2. Undercut	Banks undercut/overhanging to the extent that mass wasting appears likely. Does NOT include undercuts that are modest, appear sustainable and are providing habitat			0	0	100%	0	0	100%
	3. Mass Wasting	Bank slumping, calving, or collapse			0	0	100%	0	0	100%
				Totals	5	121	94%	0	0	94%
	1. Overall Integrity	Structures physically intact with no dislodged boulders or logs.	2	3			67%			
	2. Grade Control	Grade control structures exhibiting maintenance of grade across the sill	0	1			0%			
Structures <sup>1</sup>	2a. Piping	Structures lacking any substantial flow underneath sills or arms.	2	3			67%			
	3. Bank Protection	Bank erosion within the structures extent of influence does not exceed 15%.	2	2			100%			
	4. Habitat	Pool forming structures maintaining ~Max Pool Depth : Bankfull Depth ≥ 1.6 Rootwads/logs providing some cover at baseflow.	2	2			100%			

<sup>&</sup>lt;sup>1</sup>Excludes constructed riffles since they are evaluated in section 1.

### **Table 7. Vegetation Condition Assessment Table**

Big Harris Creek Mitigation Site DMS Project No. 739

Monitoring Year 3 - 2020

Planted Acreage

61.5

riunted Acreuge	0113				
Vegetation Category	Definitions	Mapping Threshold (acres)	Number of Polygons	Combined Acreage	% of Planted Acreage
Bare Areas	Very limited cover of both woody and herbaceous material	0.1	0	0.0	0%
woody stem densities clearly below target levels based on MY3, 4, 5, or 7 stem count criteria.		0.1	11	0.3	0%
		Total	11	0.3	0%
Areas of Poor Growth Rates or Vigor	Areas with woody stems of a size class that are obviously small given the monitoring year.	0	0	0.0	0%
		Cumulative Total	11	0.3	0%

Easement Acreage 144.7

Vegetation Category	Definitions	Mapping Threshold (SF)	Number of Polygons	Combined Acreage	% of Easement Acreage
Invasive Areas of Concern  Areas or points (if too small to render as polygons at map scale).		1000	117	12.9	9%
Easement Encroachment Areas	Areas or points (if too small to render as polygons at map scale).	none	1	0.2	0%

<sup>&</sup>lt;sup>1</sup>Acreage calculated from vegetation plots monitored for site.

# **STREAM PHOTOGRAPHS**

Big Harris Creek - Area A Monitoring Year 3





**UBHC R1 Photo Point 4** – view upstream (6/11/2020)



UBHC R1 Photo Point 4 – view downstream (6/11/2020)



**UBHC R1 Photo Point 5** – view upstream (6/11/2020)



**UBHC R1 Photo Point 5** – view downstream (6/11/2020)



**UBHC R2A Photo Point 6** – view upstream (6/11/2020)



**UBHC R2A Photo Point 6** – view downstream (6/11/2020)



**UBHC R2A Photo Point 7** – view upstream (6/11/2020)



**UBHC R2A Photo Point 7** – view downstream (6/11/2020)



**UBHC R2B Photo Point 8** – view upstream (6/11/2020)



**UBHC R2B Photo Point 8** – view downstream (6/11/2020)



**UBHC R2B Photo Point 9** – view upstream (6/11/2020)



**UBHC R2B Photo Point 9** – view downstream (6/11/2020)



**UBHC R3 Photo Point 10** – view upstream (5/5/2020)



**UBHC R3 Photo Point 10** – view downstream (5/5/2020)



**UBHC R3 Photo Point 11** – view upstream (5/5/2020)



**UBHC R3 Photo Point 11** – view downstream (5/5/2020)



**UBHC R4 Photo Point 12** – view upstream (5/5/2020)



**UBHC R4 Photo Point 12** – view downstream (5/5/2020)



**UBHC R4 Photo Point 13** – view upstream (5/5/2020)



**UBHC R4 Photo Point 13** – view downstream (5/5/2020)



**UBHC R4 Photo Point 14** – view upstream (5/5/2020)



**UBHC R4 Photo Point 14** – view downstream (5/5/2020)



**UBHC R4 Photo Point 15** – view upstream (5/5/2020)



**UBHC R4 Photo Point 15** – view downstream (5/5/2020)





**UBHC R4 Photo Point 16** – view downstream (5/5/2020)



**UBHC R5 Photo Point 17** – view upstream (5/5/2020)



**UBHC R5 Photo Point 17** – view downstream (5/5/2020)



**UBHC R5 Photo Point 18** – view upstream (5/5/2020)



**UBHC R5 Photo Point 18** – view downstream (5/5/2020)



**UBHC R6 Photo Point 19** – view upstream (5/5/2020)



**UBHC R6 Photo Point 19** – view downstream (5/5/2020)



**UBHC R6 Photo Point 20** – view upstream (5/5/2020)



**UBHC R6 Photo Point 20** – view downstream (5/5/2020)



**UBHC R6 Photo Point 21** – view upstream (5/5/2020)



**UBHC R6 Photo Point 21** – view downstream (5/5/2020)



**UBHC R6 Photo Point 22** – view upstream (5/5/2020)



**UBHC R6 Photo Point 22** – view downstream (5/5/2020)




**UBHC R6 Photo Point 23** – view upstream (5/5/2020)



**UBHC R6 Photo Point 23** – view downstream (5/5/2020)




**UBHC UT1 Photo Point 24** – view upstream (6/11/2020)



**UBHC UT1 Photo Point 24** – view downstream (6/11/2020)











Scism Creek Photo Point 37 – view upstream (5/5/2020)



Scism Creek Photo Point 37 – view downstream 5/5/2020)



Scism Creek Photo Point 38 – view upstream (5/5/2020)



Scism Creek Photo Point 38 – view downstream (5/5/2020)



Royster Creek Photo Point 39 – view upstream (4/2/2020)



Royster Creek Photo Point 39 – view downstream (4/2/2020)



Royster Creek Photo Point 40 – view upstream (4/2/2020)



Royster Creek Photo Point 40 – view downstream (4/2/2020)



Royster Creek Photo Point 41 – view upstream (4/2/2020)



Royster Creek Photo Point 41 – view downstream (4/2/2020)



Royster Creek Photo Point 42 – view upstream (5/5/2020)



**Royster Creek Photo Point 42** – view downstream (5/5/2020)





Royster Creek Photo Point 43 – view downstream (5/5/2020)



**Royster Creek Photo Point 44** – view upstream (5/5/2020)



**Royster Creek Photo Point 44** – view downstream (5/5/2020)



**Royster Creek Photo Point 45** – view upstream (5/5/2020)



**Royster Creek Photo Point 45** – view downstream (5/5/2020)



**Royster Creek Photo Point 46** – view upstream (5/5/2020)



**Royster Creek Photo Point 46** – view downstream (5/5/2020)



**Royster Creek Photo Point 47** – view upstream (5/5/2020)



**Royster Creek Photo Point 47** – view downstream (5/5/2020)



LSEC Photo Point 48 – view upstream (5/5/2020)



**LSEC Photo Point 48** – view downstream (5/5/2020)



LSEC Photo Point 49 – view upstream (5/5/2020)



LSEC Photo Point 49 – view downstream (5/5/2020)



**LSEC Photo Point 50** – view upstream (5/5/2020)



**LSEC Photo Point 50** – view downstream (5/5/2020)



Scott Creek Photo Point 51 – view upstream (4/2/2020)



Scott Creek Photo Point 51 – view downstream (4/2/2020)



Scott Creek Photo Point 52 – view upstream (4/2/2020)



Scott Creek Photo Point 52 – view downstream (4/2/2020)



Scott Creek Photo Point 53 – view upstream (4/2/2020)



Scott Creek Photo Point 53 – view downstream (4/2/2020)



Carroll Creek Photo Point 54 – view upstream (5/5/2020)



Carroll Creek Photo Point 54 – view downstream (5/5/2020)



Carroll Creek Photo Point 55 – view upstream (5/5/2020)



Carroll Creek Photo Point 55 – view downstream (5/5/2020)



Carroll Creek Photo Point 56 – view upstream (5/5/2020)



Carroll Creek Photo Point 56 – view downstream (5/5/2020)

# STREAM PHOTOGRAPHS

Big Harris Creek - Area B Monitoring Year 3











**USEC R6 Photo Point 71** – view downstream (5/6/2020)

**USEC R6 Photo Point 71** – view upstream (5/6/2020)











**USEC UT3 Photo Point 84** – view upstream (5/6/2020)



**USEC UT3 Photo Point 84** – view downstream (5/6/2020)



**UFC R1 Photo Point 85** – view upstream (5/5/2020)



**UFC R1 Photo Point 85** – view downstream (5/5/2020)



**UFC R1 Photo Point 86** – view upstream (5/5/2020)



**UFC R1 Photo Point 86** – view downstream (5/5/2020)





**UFC R2 Photo Point 90** – view upstream (5/5/2020)



**UFC R2 Photo Point 90** – view downstream (5/5/2020)



**UFC R2 Photo Point 91** – view upstream (5/5/2020)



**UFC R2 Photo Point 91** – view downstream (5/5/2020)



**UFC R2 Photo Point 92** – view upstream (5/5/2020)



**UFC R2 Photo Point 92** – view downstream (5/5/2020)



# **STREAM PHOTOGRAPHS**

Big Harris Creek - Area C Monitoring Year 3



**LBHC R1A Photo Point 96** – view upstream (5/6/2020)



LBHC R1A Photo Point 96 – view downstream (5/6/2020)



LBHC R1A Photo Point 97 – view upstream (5/6/2020)



LBHC R1A Photo Point 97 – view downstream (5/6/2020)



LBHC R1B Photo Point 98 – view upstream (5/6/2020)



LBHC R1B Photo Point 98 – view downstream (5/6/2020)



LBHC R2 Photo Point 99 – view upstream (5/6/2020)



LBHC R2 Photo Point 99 – view downstream (5/6/2020)



LBHC R2 Photo Point 100 – view upstream (5/6/2020)




LBHC R2 Photo Point 100 – view downstream (5/6/2020)



LBHC R2 Photo Point 101 – view upstream (5/6/2020)



LBHC R2 Photo Point 101 – view downstream (5/6/2020)







LBHC UT2 Photo Point 105 – view downstream (5/6/2020)



LBHC UT3 Photo Point 106 – view upstream (5/6/2020)



LBHC UT3 Photo Point 106 – view downstream (5/6/2020)




LBHC UT4 Photo Point 107 – view upstream (5/6/2020)



LBHC UT4 Photo Point 107 – view downstream (5/6/2020)

# **VEGETATION PHOTOGRAPHS**

Monitoring Year 3





















# **AREAS OF CONCERN PHOTOGRAPHS**

Monitoring Year 3



**UBHC R2B Bank Scour (STA 137+33 – 137+67)** – view downstream (10/22/2020)



**USEC R1 Bank Scour (STA 1005+57 – 1005+75)** – view downstream *(10/20/2020)* 



**USEC R3 Aggradation (STA 1026+74 – 1026+89)** – view downstream *(10/20/2020)* 



**Scott Creek Incision (STA 1211+25 – 1211+36)** – view upstream (11/2/2020)



LBHC R1A Kudzu – view downstream (10/27/2020)



LBHC R2 Chinese Privet - view downstream (10/27/2020)



**UBHC R3 Log Dislodged (STA 145+48)** – view upstream (10/27/2020)



LBHC R2 Log Sill Bypassed (STA 317+45) – view upstream (10/27/2020)



**Royster Creek R1 Rock Sill Failed (STA 806+74)** – view upstream (10/27/2020)



**LBHC R2 Beaver Dam (STA 310+10)** – view upstream (10/27/2020)



### **Table 8. Vegetation Plot Criteria Attainment Table**

Big Harris Creek Mitigation Site DMS Project No. 739

	Success Criteria	
Plot	Met (Y/N)	Tract Mean
1	Y	
2	N N	
3	Y	
4	Y	
5	Y	
6	Y	
7	Y	
8	Y	
9	Y	
10	Y	
11	Y	
12	N	
13	Y	
14	Y	
15	Y	
16	Y	
17	Y	
18	Y	
19	N N	
20	Y	
21	Y	
22	Y	
	Y	
23		
24	N	
25	N	
26	Y	
27	N	
28	N	80%
29	N	
30	Y	
31	N	
32	Y	
33	Y	
34	Y	
35	Y	
36	Y	
37	Y	
38	Υ	
39	Y	
40	Υ	
41	Υ	
42	Υ	
43	Υ	
44	Y	
45	Υ	
46	Υ	
47	Υ	
48	Y	
49	Y	
50	N	
51	N	
52	Υ	
53	Υ	
54	Υ	
55	Υ	
56	Υ	

### Table 9. CVS Vegetation Tables - Metadata

Big Harris Creek Mitigation Site

DMS Project No. 739

Report Prepared By	lan Eckardt
Date Prepared	11/19/2020 12:23
Database Name	BHC MY3 cvs-eep-entrytool-v2.5.0.mdb
Database Location	Q:\ActiveProjects\005-02149 Big Harris Creek\Monitoring\Monitoring Year 3 (2020)\Vegetation Assessment
Computer Name	IAN
File Size	96366592
DESCRIPTION OF WORKSHEETS IN THIS DOCUMENT	
Metadata	Description of database file, the report worksheets, and a summary of project(s) and project data.
Project Planted	Each project is listed with its PLANTED stems per acre, for each year. This excludes live stakes.
Project Total Stems	Each project is listed with its TOTAL stems per acre, for each year. This includes live stakes, all planted stems, and all natural/volunteer stems.
Plots	List of plots surveyed with location and summary data (live stems, dead stems, missing, etc.).
Vigor	Frequency distribution of vigor classes for stems for all plots.
Vigor by Spp	Frequency distribution of vigor classes listed by species.
Damage	List of most frequent damage classes with number of occurrences and percent of total stems impacted by each.
Damage by Spp	Damage values tallied by type for each species.
Damage by Plot	Damage values tallied by type for each plot.
Planted Stems by Plot and Spp	A matrix of the count of PLANTED living stems of each species for each plot; dead and missing stems are excluded.
ALL Stems by Plot and Spp	A matrix of the count of total living stems of each species (planted and natural volunteers combined) for each plot; dead and missing stems are excluded.
PROJECT SUMMARY	
Project Code	739
Project Name	Big Harris Creek Mitigation Site
Sampled Plots	56

### Table 10a. Planted and Total Stems

Big Harris Creek Mitigation Site DMS Project No. 739 Monitoring Year 3 - 2020

											Curre	ent Plot D	ata (MY3	2020) - A	rea A								
			Ve	getation Plo	ot 1	Ve	getation Pl	ot 2	Ve	getation Pl	ot 3	Ve	getation Plo	ot 4	Ve	getation Pl	ot 5	Ve	getation Plo	ot 6	Ve	getation Plo	ot 7
Scientific Name	Common Name	Species Type	PnoLS	P-all	T	PnoLS	P-all	Т	PnoLS	P-all	T	PnoLS	P-all	Т	PnoLS	P-all	T	PnoLS	P-all	Т	PnoLS	P-all	T
Acer negundo	Boxelder maple	Tree																				J	
Acer rubrum	Red maple	Tree	3	3	3	1	1	1	3	3	3	2	2	2	4	4	4	2	2	2	3	3	3
Betula nigra	River birch	Tree							1	1	1				2	2	2	1	1	1	1	1	1
Diospyros virginiana	American Persimmon	Tree																		1		J	
Fagus	Beech	Tree																					
Fraxinus pennsylvanica	Green ash	Tree	2	2	2	1	1	1	4	4	4	2	2	2	3	3	3	5	5	5	1	1	1
Ilex opaca	American Holly	Shrub Tree																					
Juglans nigra	Black Walnut	Tree																					
Liquidambar styraiflua	Sweet Gum	Tree			65			81			55						40			20			25
Liriodendron tulipifera	Tulip Poplar	Tree			70						25						4						
Nyssa sylvatica	Blackgum	Tree	1	1	1				2	2	2	1	1	1				1	1	1	2	2	2
Pinus rigida	Pitch pine	Tree									25						40						
Pinus Virginiana	Virginia Pine	Tree																					
Platanus occidentalis	American sycamore	Tree	4	4	4	5	5	5	1	1	1	2	2	2	5	5	5				4	4	4
Quercus sp.	Oak	Tree																					
Quercus alba	White Oak	Tree																					
Quercus falcata	Spanish Oak	Tree																					
Quercus nigra	Water Oak	Tree																					
Quercus pagoda	Cherrybark oak	Tree	1	1	1							1	1	1				1	1	1	1	1	1
Quercus phellos	Willow oak	Tree							1	1	1												
Quercus rubra	Red oak	Tree	1	1	1				2	2	2												
Rhus copallinum	Shining sumac	Shrub Tree																					
Rhus typhina	Staghorn Sumac	Shrub																					
Salix nigra	Black willow	Tree																					
Sambucus Canadensis	Common Elderberry	Shrub Tree																					
	,	Stem count	12	12	147	7	7	88	14	14	119	8	8	8	14	14	98	10	10	31	12	12	37
		Size (ares)		1	•		1	•		1	•		1	•		1	•		1	•		1	
		Size (ACRES)		0.0247			0.0247			0.0247			0.0247			0.0247			0.0247			0.0247	
		Species count	6	6	8	3	3	4	7	7	10	5	5	5	4	4	7	5	5	7	6	6	7
	9	Stems per ACRE	486	486	5951	283	283	3,563	567	567	4,818	324	324	324	567	567	3,968	405	405	1,255	486	486	1,498

											Curr	ent Plot C	ata (MY3	2020) - A	rea A								
			Ve	getation Plo	ot 8	Ve	getation Pl	ot 9	Ve	etation Plo	t 10	Ve	getation Plo	t 11	Veg	etation Plo	t 12	Veg	getation Plo	t 13	Veg	getation Plo	t 14
Scientific Name	Common Name	Species Type	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	Т
Acer negundo	Boxelder maple	Tree																					1
Acer rubrum	Red maple	Tree	3	3	13	3	3	3	5	5	5	3	3	3	1	1	1	4	4	4	2	2	2
Betula nigra	River birch	Tree	1	1	1																1	1	1
Diospyros virginiana	American Persimmon	Tree									2			2									1
Fagus	Beech	Tree																					1
Fraxinus pennsylvanica	Green ash	Tree	5	5	5	4	4	4	3	3	4	4	4	4	1	1	1	2	2	2	3	3	3
Ilex opaca	American Holly	Shrub Tree																					1
Juglans nigra	Black Walnut	Tree																					1
Liquidambar styraiflua	Sweet Gum	Tree			75			35															47
Liriodendron tulipifera	Tulip Poplar	Tree			160			23			2			3						2			75
Nyssa sylvatica	Blackgum	Tree				1	1	1										1	1	1	1	1	1
Pinus rigida	Pitch pine	Tree																					1
Pinus Virginiana	Virginia Pine	Tree																					1
Platanus occidentalis	American sycamore	Tree	4	4	4	7	7	7	5	5	5	5	5	6	1	1	1	1	1	1	5	5	5
Quercus sp.	Oak	Tree																					1
Quercus alba	White Oak	Tree																					1
Quercus falcata	Spanish Oak	Tree																					1
Quercus nigra	Water Oak	Tree																					1
Quercus pagoda	Cherrybark oak	Tree	1	1	1				1	1	1										1	1	1
Quercus phellos	Willow oak	Tree	1	1	1													1	1	1	1	1	1
Quercus rubra	Red oak	Tree										1	1	1				2	2	2			1
Rhus copallinum	Shining sumac	Shrub Tree																					1
Rhus typhina	Staghorn Sumac	Shrub																					1
Salix nigra	Black willow	Tree																					1
Sambucus Canadensis	Common Elderberry	Shrub Tree																					1
		Stem count	15	15	260	15	15	73	14	14	19	13	13	19	3	3	3	11	11	13	14	14	136
		Size (ares)		1			1			1			1			1			1			1	
		Size (ACRES)		0.0247			0.0247			0.0247			0.0247			0.0247			0.0247			0.0247	
		Species count	6	6	8	4	4	6	4	4	6	4	4	6	3	3	3	6	6	7	7	7	9
·	9	Stems per ACRE	607	607	10,526	607	607	2,955	567	567	769	526	526	769	121	121	121	445	445	526	567	567	5,506

### Table 10b. Planted and Total Stems

Big Harris Creek Mitigation Site DMS Project No. 739

											Curre	ent Plot D	ata (MY3	2020) - A	rea A								
			Veg	etation Plo	t 15	Veg	etation Plo	t 16	Veg	etation Plo	t 17	Veg	etation Plo	t 18	Veg	etation Plo	t 19	Veg	getation Plo	ot 20	Veg	getation Plot	t 21
Scientific Name	Common Name	Species Type	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	Т
Acer negundo	Boxelder maple	Tree																					
Acer rubrum	Red maple	Tree	1	1	1	1	1	1	2	2	42				2	2	2			1	1	1	1
Betula nigra	River birch	Tree	2	2	2				1	1	36	2	2	2				1	1	1	2	2	2
Diospyros virginiana	American Persimmon	Tree																					
Fagus	Beech	Tree																					
Fraxinus pennsylvanica	Green ash	Tree	2	2	2	4	4	4	3	3	3	5	5	5	1	1	1	1	1	57	1	1	1
Ilex opaca	American Holly	Shrub Tree																					
Juglans nigra	Black Walnut	Tree																					
Liquidambar styraiflua	Sweet Gum	Tree						3			60									10			190
Liriodendron tulipifera	Tulip Poplar	Tree						3			55			45									
Nyssa sylvatica	Blackgum	Tree							1	1	1				1	1	2				1	1	1
Pinus rigida	Pitch pine	Tree																					
Pinus Virginiana	Virginia Pine	Tree																					
Platanus occidentalis	American sycamore	Tree	1	1	1	4	4	4	3	3	28				3	3	3	5	5	5	2	2	2
Quercus sp.	Oak	Tree				1	1	1															
Quercus alba	White Oak	Tree																					
Quercus falcata	Spanish Oak	Tree																					
Quercus nigra	Water Oak	Tree																					
Quercus pagoda	Cherrybark oak	Tree	2	2	2							2	2	2									
Quercus phellos	Willow oak	Tree										1	1	1							1	1	1
Quercus rubra	Red oak	Tree							1	1	1	1	1	1				1	1	1			
Rhus copallinum	Shining sumac	Shrub Tree																					
Rhus typhina	Staghorn Sumac	Shrub																					
Salix nigra	Black willow	Tree																					
Sambucus Canadensis	Common Elderberry	Shrub Tree																					
		Stem count	8	8	8	10	10	16	11	11	226	11	11	56	7	7	8	8	8	75	8	8	198
		Size (ares)		1			1			1			1			1			1			1	
		Size (ACRES)		0.0247			0.0247			0.0247			0.0247			0.0247			0.0247			0.0247	
		Species count	5	5	5	4	4	6	6	6	8	5	5	6	4	4	4	4	4	6	6	6	7
	S	items per ACRE	324	324	324	405	405	648	445	445	9150	445	445	2267	283	283	324	324	324	3,036	324	324	8016

											Curr	ent Plot D	ata (MY3	2020) - A	rea A								
			Veg	getation Plo	t 22	Veg	getation Plo	ot 23	Ve	getation Plo	t 24	Ve	getation Plo	t 25	Ve	getation Plo	t 26	Veg	getation Plo	t 27	Veg	getation Plot	t 28
Scientific Name	Common Name	Species Type	PnoLS	P-all	T	PnoLS	P-all	Т	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	Т
Acer negundo	Boxelder maple	Tree									3												
Acer rubrum	Red maple	Tree	3	3	3	5	5	5	3	3	3			1	1	1	1						
Betula nigra	River birch	Tree				2	2	2										1	1	1	1	1	1
Diospyros virginiana	American Persimmon	Tree									3						25						
Fagus	Beech	Tree																					
Fraxinus pennsylvanica	Green ash	Tree	3	3	3	2	2	2	1	1	1	1	1	1	4	4	4	2	2	2	3	3	3
Ilex opaca	American Holly	Shrub Tree																					
Juglans nigra	Black Walnut	Tree																					
Liquidambar styraiflua	Sweet Gum	Tree																					
Liriodendron tulipifera	Tulip Poplar	Tree															2						1
Nyssa sylvatica	Blackgum	Tree							2	2	2												
Pinus rigida	Pitch pine	Tree																					
Pinus Virginiana	Virginia Pine	Tree																					
Platanus occidentalis	American sycamore	Tree	4	4	4	2	2	2				1	1	1	7	7	7				3	3	3
Quercus sp.	Oak	Tree																					
Quercus alba	White Oak	Tree																					
Quercus falcata	Spanish Oak	Tree																					
Quercus nigra	Water Oak	Tree																					
Quercus pagoda	Cherrybark oak	Tree				1	1	1	1	1	1	1	1	1				1	1	1			
Quercus phellos	Willow oak	Tree													1	1	1						
Quercus rubra	Red oak	Tree				1	1	1				1	1	1	1	1	1	2	2	2			
Rhus copallinum	Shining sumac	Shrub Tree																					
Rhus typhina	Staghorn Sumac	Shrub																					
Salix nigra	Black willow	Tree																					
Sambucus Canadensis	Common Elderberry	Shrub Tree																					
		Stem count	10	10	10	13	13	13	7	7	13	4	4	5	14	14	41	6	6	6	7	7	8
		Size (ares)		1			1			1			1	•		1	•		1			1	
		Size (ACRES)		0.0247			0.0247			0.0247			0.0247			0.0247			0.0247			0.0247	
		Species count	3	3	3	6	6	6	4	4	6	4	4	5	5	5	7	4	4	4	3	3	4
	9	Stems per ACRE	405	405	405	526	526	526	283	283	526	162	162	202	567	567	1,660	243	243	243	283	283	324

### Table 10c. Planted and Total Stems

Big Harris Creek Mitigation Site DMS Project No. 739

										Current P	lot Data (	MY3 202	0) - Area <i>A</i>	4						
			Veg	etation Plo	t 29	Veg	etation Plo	t 30	Veg	etation Plo	t 31	Veg	getation Plo	t 32	Veg	etation Plo	t 33	Veg	etation Plo	t 34
Scientific Name	Common Name	Species Type	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T
Acer negundo	Boxelder maple	Tree																		1
Acer rubrum	Red maple	Tree				2	2	3				1	1	1	3	3	3	1	1	1
Betula nigra	River birch	Tree							1	1	1	1	1	1						1
Diospyros virginiana	American Persimmon	Tree																		1
Fagus	Beech	Tree																		1
Fraxinus pennsylvanica	Green ash	Tree				3	3	3	3	3	3	2	2	2	3	3	3	2	2	2
Ilex opaca	American Holly	Shrub Tree																		1
Juglans nigra	Black Walnut	Tree																		1
Liquidambar styraiflua	Sweet Gum	Tree												30			90			1
Liriodendron tulipifera	Tulip Poplar	Tree												5			30			1
Nyssa sylvatica	Blackgum	Tree										2	2	2				1	1	1
Pinus rigida	Pitch pine	Tree																		
Pinus Virginiana	Virginia Pine	Tree																		
Platanus occidentalis	American sycamore	Tree	1	1	2	5	5	5				3	3	3	2	2	2	1	1	2
Quercus sp.	Oak	Tree																		1
Quercus alba	White Oak	Tree																		1
Quercus falcata	Spanish Oak	Tree																		1
Quercus nigra	Water Oak	Tree																		1
Quercus pagoda	Cherrybark oak	Tree				1	1	1				1	1	1	1	1	1	1	1	1
Quercus phellos	Willow oak	Tree	1	1	1							1	1	1						1
Quercus rubra	Red oak	Tree	1	1	1				1	1	1	1	1	1	1	1	1	2	2	2
Rhus copallinum	Shining sumac	Shrub Tree																		1
Rhus typhina	Staghorn Sumac	Shrub																		1
Salix nigra	Black willow	Tree																		1
Sambucus Canadensis	Common Elderberry	Shrub Tree																		1
		Stem count	3	3	4	11	11	12	5	5	5	12	12	47	10	10	130	8	8	9
		Size (ares)		1			1			1			1			1			1	
		Size (ACRES)		0.0247			0.0247			0.0247			0.0247			0.0247			0.0247	
		Species count	3	3	3	4	4	4	3	3	3	8	8	10	5	5	7	6	6	6
	9	Stems per ACRE	121	121	162	445	445	486	202	202	202	486	486	1903	405	405	5263	324	324	364

											Curr	ent Plot D	ata (MY3	2020) - A	rea B								
			Veg	etation Plo	t 35	Veg	etation Plo	t 36	Veg	etation Plo	t 37	Veg	etation Plo	t 38	Veg	etation Plo	t 39	Veg	etation Plo	t 40	Veg	etation Plot	t 41
Scientific Name	Common Name	Species Type	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	Т	PnoLS	P-all	Т	PnoLS	P-all	T	PnoLS	P-all	Т
Acer negundo	Boxelder maple	Tree																					
Acer rubrum	Red maple	Tree	1	1	2	1	1	1	1	1	1	2	2	2	3	3	8	1	1	1	4	4	4
Betula nigra	River birch	Tree	2	2	2				1	1	1			1									
Diospyros virginiana	American Persimmon	Tree																					
Fagus	Beech	Tree																					
Fraxinus pennsylvanica	Green ash	Tree	1	1	1	3	3	3	3	3	3	5	5	7	3	3	3	2	2	2	4	4	4
Ilex opaca	American Holly	Shrub Tree																					
Juglans nigra	Black Walnut	Tree																					
Liquidambar styraiflua	Sweet Gum	Tree																					300
Liriodendron tulipifera	Tulip Poplar	Tree			16									14									22
Nyssa sylvatica	Blackgum	Tree	3	3	3													1	1	1	2	2	2
Pinus rigida	Pitch pine	Tree																					
Pinus Virginiana	Virginia Pine	Tree																					
Platanus occidentalis	American sycamore	Tree	3	3	3	4	4	4	3	3	3	5	5	5	5	5	5	6	6	6	1	1	1
Quercus sp.	Oak	Tree																					
Quercus alba	White Oak	Tree																					
Quercus falcata	Spanish Oak	Tree																					
Quercus nigra	Water Oak	Tree																					
Quercus pagoda	Cherrybark oak	Tree							1	1	1				2	2	2	2	2	2			
Quercus phellos	Willow oak	Tree										1	1	1							2	2	2
Quercus rubra	Red oak	Tree	3	3	3										1	1	1				1	1	1
Rhus copallinum	Shining sumac	Shrub Tree																					
Rhus typhina	Staghorn Sumac	Shrub																					
Salix nigra	Black willow	Tree																					
Sambucus Canadensis	Common Elderberry	Shrub Tree																					
		Stem count	13	13	30	8	8	8	9	9	9	13	13	30	14	14	19	12	12	12	14	14	336
		Size (ares)		1	•		1	•		1	•		1	•		1	•		1			1	
		Size (ACRES)		0.0247			0.0247			0.0247			0.0247			0.0247			0.0247			0.0247	
		Species count	6	6	7	3	3	3	5	5	5	4	4	6	5	5	5	5	5	5	6	6	8
	S	tems per ACRE	526	526	1215	324	324	324	364	364	364	526	526	1215	567	567	769	486	486	486	567	567	13603

### Table 10d. Planted and Total Stems

Big Harris Creek Mitigation Site DMS Project No. 739

Monitoring Year 3 - 2020

											Curre	ent Plot D	ata (MY3	2020) - A	rea B								
			Veg	etation Plo	t 42	Veg	etation Plo	ot 43	Veg	etation Plo	t 44	Veg	etation Plo	t 45	Veg	etation Plo	t 46	Veg	etation Plo	t 47	Ve	getation Plo	t 48
Scientific Name	Common Name	Species Type	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	Т	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	Т
Acer negundo	Boxelder maple	Tree																					
Acer rubrum	Red maple	Tree			9	1	1	21	2	2	7	1	1	1	2	2	2	2	2	2	2	2	2
Betula nigra	River birch	Tree				4	4	4	2	2	2	2	2	2	1	1	1	1	1	1	1	1	1
Diospyros virginiana	American Persimmon	Tree												3									
Fagus	Beech	Tree																					
Fraxinus pennsylvanica	Green ash	Tree	5	5	5	4	4	4	2	2	2	2	2	2	6	6	6	3	3	3	3	3	3
Ilex opaca	American Holly	Shrub Tree																					
Juglans nigra	Black Walnut	Tree																					
Liquidambar styraiflua	Sweet Gum	Tree			28			90			90			10			10			23			
Liriodendron tulipifera	Tulip Poplar	Tree			37			90			90			6						10			50
Nyssa sylvatica	Blackgum	Tree							1	1	1	1	1	1	1	1	1				1	1	1
Pinus rigida	Pitch pine	Tree																					
Pinus Virginiana	Virginia Pine	Tree																					
Platanus occidentalis	American sycamore	Tree	3	3	3	2	2	2	4	4	24	5	5	5	4	4	4	6	6	6	3	3	3
Quercus sp.	Oak	Tree																					
Quercus alba	White Oak	Tree																					
Quercus falcata	Spanish Oak	Tree																					
Quercus nigra	Water Oak	Tree																					
Quercus pagoda	Cherrybark oak	Tree			4				1	1	1	1	1	1	1	1	1				2	2	2
Quercus phellos	Willow oak	Tree										1	1	1	1	1	1						
Quercus rubra	Red oak	Tree				1	1	1	3	3	3										2	2	2
Rhus copallinum	Shining sumac	Shrub Tree																					
Rhus typhina	Staghorn Sumac	Shrub																					
Salix nigra	Black willow	Tree															2						
Sambucus Canadensis	Common Elderberry	Shrub Tree																					
		Stem count	8	8	86	12	12	212	15	15	220	13	13	32	16	16	28	12	12	45	14	14	64
		Size (ares)		1			1	•		1			1	•		1	•		1	•		1	
		Size (ACRES)		0.0247			0.0247			0.0247			0.0247			0.0247			0.0247			0.0247	
		Species count	2	2	6	5	5	7	7	7	9	7	7	10	7	7	9	4	4	6	7	7	8
	S	tems per ACRE	324	324	3482	486	486	8,583	607	607	8,907	526	526	1,296	648	648	1,134	486	486	1,822	567	567	2,591

						(	Current P	lot Data (	MY3 2020	0) - Area I	3			
			Veg	etation Plo	t 49	Veg	etation Plo	t 50	Veg	etation Plo	t 51	Veg	etation Plo	t 52
Scientific Name	Common Name	Species Type	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T
Acer negundo	Boxelder maple	Tree												
Acer rubrum	Red maple	Tree	2	2	2						1			10
Betula nigra	River birch	Tree	3	3	3							2	2	2
Diospyros virginiana	American Persimmon	Tree						1	1	1	1			
Fagus	Beech	Tree												
Fraxinus pennsylvanica	Green ash	Tree	2	2	2	3	3	4	1	1	1	5	5	5
Ilex opaca	American Holly	Shrub Tree												
Juglans nigra	Black Walnut	Tree												
Liquidambar styraiflua	Sweet Gum	Tree									27			13
Liriodendron tulipifera	Tulip Poplar	Tree						11			10			10
Nyssa sylvatica	Blackgum	Tree	1	1	1									
Pinus rigida	Pitch pine	Tree												
Pinus Virginiana	Virginia Pine	Tree												
Platanus occidentalis	American sycamore	Tree	2	2	2							4	4	4
Quercus sp.	Oak	Tree												
Quercus alba	White Oak	Tree												
Quercus falcata	Spanish Oak	Tree												
Quercus nigra	Water Oak	Tree												
Quercus pagoda	Cherrybark oak	Tree	1	1	1	2	2	2				1	1	1
Quercus phellos	Willow oak	Tree												
Quercus rubra	Red oak	Tree	1	1	1							1	1	1
Rhus copallinum	Shining sumac	Shrub Tree												
Rhus typhina	Staghorn Sumac	Shrub												
Salix nigra	Black willow	Tree												
Sambucus Canadensis	Common Elderberry	Shrub Tree												
		Stem count	12	12	12	5	5	18	2	2	40	13	13	46
		Size (ares)		1			1			1			1	
		Size (ACRES)		0.0247			0.0247			0.0247			0.0247	
		Species count	7	7	7	2	2	4	2	2	5	5	5	8
		Stems per ACRE	486	486	486	202	202	729	81	81	1,619	526	526	1862

Exceeds requirements by 10%
Exceeds requirements, but by less than 10%
Fails to meet requirements, by less than 10%
Fails to meet requirements by more than 10% Volunteers included

PnoLS: Number of planted stems excluding live stakes P-All: Number of planted stems including live stakes

## Table 10e. Planted and Total Stems

Big Harris Creek Mitigation Site DMS Project No. 739 **Monitoring Year 3 - 2020** 

							Current P	lot Data	(MY3 202	0) - Area (	С									Annual	Summarie	es				
			Veg	etation Plo	ot 53	Veg	etation Plo	ot 54	Veg	getation Plo	t 55	Veg	etation Plo	t 56		MY3 (2020	)		MY2 (2019)		MY1 (9/	2018 thru :	11/2018)	MY0 (3	/2018 thru 5	/2018)
Scientific Name	Common Name	Species Type	PnoLS	P-all	T	PnoLS	P-all	Т	PnoLS	P-all	T	PnoLS	P-all	Т	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T	PnoLS	P-all	T
Acer negundo	Boxelder maple	Tree															3			6						
Acer rubrum	Red maple	Tree						1	3	3	3	2	2	2	95	95	200	108	108	307	143	143	432	171	171	171
Betula nigra	River birch	Tree	2	2	2	1	1	1	4	4	4				47	47	83	52	52	89	61	61	62	99	99	99
Diospyros virginiana	American Persimmon	Tree													1	1	38			50			11			
Fagus	Beech	Tree																					1			
Fraxinus pennsylvanica	Green ash	Tree	4	4	4	1	1	1	3	3	3	2	2	2	153	153	213	153	153	186	159	159	160	167	167	167
Ilex opaca	American Holly	Shrub Tree																					1			
Juglans nigra	Black Walnut	Tree																		1						
Liquidambar styraiflua	Sweet Gum	Tree						180			85			50			2332			2045			456			
Liriodendron tulipifera	Tulip Poplar	Tree			8									20			899			762			366			
Nyssa sylvatica	Blackgum	Tree				1	1	1				1	1	1	31	31	32	38	38	49	48	48	48	59	59	60
Pinus rigida	Pitch pine	Tree															65									
Pinus Virginiana	Virginia Pine	Tree																		23						
Platanus occidentalis	American sycamore	Tree	4	4	139	4	4	5	3	3	18	2	2	52	169	169	418	175	175	716	186	186	265	212	212	212
Quercus sp.	Oak	Tree	1	1	1										2	2	2	2	2	2	4	4	4	3	3	3
Quercus alba	White Oak	Tree																					2			
Quercus falcata	Spanish Oak	Tree																		1						
Quercus nigra	Water Oak	Tree																								
Quercus pagoda	Cherrybark oak	Tree	2	2	2	1	1	1	2	2	2	1	1	1	39	39	43	39	39	39	49	49	49	55	55	55
Quercus phellos	Willow oak	Tree				3	3	3				1	1	2	18	18	19	17	17	17	25	25	28	46	46	46
Quercus rubra	Red oak	Tree				1	1	1				1	1	1	35	35	35	37	37	43	51	51	51	57	57	57
Rhus copallinum	Shining sumac	Shrub Tree																		2						
Rhus typhina	Staghorn Sumac	Shrub																		3						
Salix nigra	Black willow	Tree															2									
Sambucus Canadensis	Common Elderberry	Shrub Tree																		1						
		Stem count	13	13	156	12	12	194	15	15	115	10	10	131	590	590	4384	621	621	4342	726	726	1936	869	869	870
		Size (ares)		1			1			1			1			56			56			56			56	
		Size (ACRES)		0.0247			0.0247			0.0247			0.0247			1.38			1.38			1.38			1.38	
		Species count	5	5	6	7	7	9	5	5	6	7	7	9	10	10	15	9	9	19	9	9	15	9	9	9
		Stems per ACRE	526	526	6316	486	486	7854	607	607	4656	405	405	5304	427	427	3169	449	449	3139	525	525	1399	628	628	629

Exceeds requirements by 10%
Exceeds requirements, but by less than 10%
Fails to meet requirements, by less than 10%
Fails to meet requirements by more than 10%
Volunteers included

PnoLS: Number of planted stems excluding live stakes P-All: Number of planted stems including live stakes T: Total stems

APPENDIX 4. Morphological Summary Data and Plot	:S

# Table 11a. Baseline Stream Data Summary

### Area A

Big Harris Creek Mitigation Site DMS Project No. 739 Monitoring Year 3 - 2020

Parameter G				Pre-Ke	storation Co	maition						esign											
Parameter 6		_													As-Built/Baseline								
	Gage	Carroll Creek Reach 1	Eaker Creek Reach 1	Royster Creek Reach 1	Scott Creek	UBHC Reach 2A	UBHC Reach 2B	UBHC Reach 4	Carroll Creek Reach 1	Royster Creek Reach 1	Scott Creek	UBHC Reach 2A	UBHC Reach 2B	UBHC Reach 4	Carroll Creek Reach 1	Eaker Creek Reach 1	Royster Creek Reach 1	Scott Creek	UBHC Reach 2A	UBHC Reach 2B	UBHC Reach		
		Min Max	Min Max	Min Max	Min Max	Min Max	Min Max	Min Max	Min Max	Min Max	Min Max	Min Max	Min Max	Min Max	Min Max	Min Max	Min Max	Min Max	Min Max	Min Max	Min Max		
Dimension and Substrate - Riffle			1	.	1	1	11111			1		1	1	1	1000	1	1	1	1000	1	1		
Bankfull Width (ft)		9.4 10.8	3.5 3.6	3.6 6.1	4.4 10.3	7.0 8.2	11.3 12.0	18.7 26.8	10.40	8.30	6.50	10.20	12.80	13.80	11.4	N/A	10.0	6.8	16.0	11.3	15.5 16.0		
Floodprone Width (ft)	<b>-</b>	13.1 14.2					-	22.0 34.6							82.0	N/A	46.7	67.1	108.7	170.3	118.0 190.0		
Bankfull Mean Depth	-	0.9 1.4	0.5 0.5	0.6	0.3 0.6	0.7 0.8	0.9 1.0	0.8 1.1	0.8	0.6	0.5	0.8	1.0	1.0	0.7	N/A	0.4	0.5	0.7	1.6	0.8 1.1		
Bankfull Max Depth		1.0 1.8	1.0 1.1	0.8 1.4	0.8 0.9		1.3 1.7	1.3 1.7	1.2	1.0	0.7	1.2	1.5	1.6	1.3	N/A	0.8	0.9	1.5	3.0	1.4 2.0		
Bankfull Cross-sectional Area (ft <sup>2</sup> )	-	11.4	1.9	3.7	2.9	5.6	11.3	20.4	8.2	5.3	3.1	7.9	12.5	14.4	7.9	N/A	3.6	3.6	11.6	17.7	13.1 17.6		
Width/Depth Ratio	, ⊢	6.6 12.5	6.6 6.9	6.1 10.2	7.4 30.8	9.1 11.5	11.4 12.7	17.6 30.3	13.2	13.0	13.6	13.2	13.1	13.2	16.4	N/A	27.6	12.7	22.0	7.3	14.5 18.3		
Entrenchment Ratio	-	1.2 1.5	1.9 2.0			1.2 1.4	1.3 1.5	1.1 1.8	2.2+	2.2+	1.4 2.2	2.2+	2.2+	2.2+	7.2	N/A	4.7	9.9	6.8	15.0	7.6 11.9		
Bank Height Ratio	-	3.4 5.0			3.8 10.6			1.6 2.9	1.0 1.2	1.0 1.2	1.0 1.2	1.0 1.2	1.0 1.2	1.0 1.2	1.0	N/A	1.0	1.0	1.0	1.0	1.0 1.0		
D <sub>50</sub> (mm)	-								N/A	N/A	N/A	N/A	N/A	N/A	51.00	N/A	43.50	51.60	44.20	83.80	46.20 85.60		
Profile			<u> </u>						,	,,,	,	1.4/.	1.47.	,	32.00	,	.5.50	32.00	20	00.00	10.20   03.00		
Riffle Length (ft)										T			T		14 65	10 19	7 42	22 47	11 40	8 39	19 56		
Riffle Slope (ft/ft)									0.016 0.050	0 0.033 0.0500	0.045 0.0530	0.016 0.0490	0.017 0.0500	0.017 0.0470									
Pool Length (ft)															18 50	4 13	7 71	6 138	10 59	10 47	33 73		
Pool Max Depth (ft)	N/A				0.9 1.2	2.2 2.2	1.9 1.9	2.9 3.2	1.3 2.4	1.1 2.0	1.0 1.7	1.2 2.3	1.5 2.9	1.6 3.1	1.9 2.8	1.3 2.1	1.6 2.5	1.9 5.2	1.9 3.3	2.6 3.4			
Pool Spacing (ft)					0.5 1.2	L.L   L.L	1.5	2.3 3.2	17 73	13 58	8 42	23 66	29 83	30 110	45 67	20 22	38 70	17 69	29 75	21 79	62 125		
Pool Volume (ft <sup>3</sup> )										20   30			23   33	50   110	.5   5/		00   70	1, 00	23 73		02 223		
Pattern														_			_	1					
Channel Beltwidth (ft)				T					31 47	25 37	7 26	26 51	28 64	41 69	26 45	N/A	9 18	25 45	13 31	20 35	19 67		
Radius of Curvature (ft)	_								19 47	15 37	16 29	18 41	23 51	25 62	15 29	46 62	21 41	11 28	18 26	30 34	27 60		
Rc:Bankfull Width (ft/ft)	N/A								1.8 4.5	1.8 4.5	2.5 4.5	1.8 4.0	1.8 4.0	1.8 4.5	1.3 2.5	N/A	2.1 4.1	1.6 4.1	1.1 1.6	2.7 3.0			
Meander Length (ft)									31 104	25 83	20 52	36 97	45 122	48 193	89 139	N/A	95 125	30 59	74 102	108 125			
Meander Width Ratio	-								3.0 4.5		3.0 8.0	3.5 9.5		3.5 14.0		N/A	0.9 1.8		0.8 1.9				
Wedner Wath Auto			1						3.0 1.3	3.0   1.3	3.0 0.0	3.3   3.3	3.3   3.3	3.3 11.0	2.2   3.3	,	0.5 1.0	3.7 0.0	0.0   1.3	1.0 3.1	1.2 1.2		
Ri%/Ru%/P%/G%/S%																							
SC%/Sa%/G%/C%/B%/Be%																							
		0.16/0.39/			SC/0.19/2.			SC/0.36/1.							0.28/2/10.2/5		SC/2/11/71.7/	0.21/24.23/39			0.3/6.69/29.8		
$D_{16}/D_{35}/D_{50}/D_{84}/D_{95}/D_{100}$		4.0/98.3/2			0/90.0/19	5.2/9.5/17/		0/129.8/61							9.6/	N/A	98.3/256	.8/	0.66/2.37/16.6	5/79.2/146.7/36	62 87/ 202.4/512		
Reach Shear Stress (Competency) lb/ft <sup>2</sup>	``,^.								0.94		1.37	0.61	1.30	1.39	0.75	N/A		1.19	0.64	1.18	0.63 0.86		
Max part size (mm) mobilized at bankfull																							
Stream Power (Capacity) W/m <sup>2</sup>																							
Additional Reach Parameters																							
Drainage Area (SM)		0.32	0.04	0.23	0.07	0.36	0.74	0.83	0.32	0.23	0.07	0.36	0.74	0.83	0.32	0.04	0.23	0.07	0.36	0.74	0.83		
Watershed Impervious Cover Estimate (%)	-	0.02	0.0 .	0.20	<10%	0.00	0.7	0.00	0.02	0.25		10%	1 0	0.00	0.02	0.0.	0.20	<10%	0.50	j 0., .			
Rosgen Classification	_	E4-G4c	A4	B4	A4	G4c	F4	F4	C4	B4	B4a	C4	C4	C4	C4	N/A	B/C4	B/C4	C4	C4	C4		
Bankfull Velocity (fps)	-	5.4	4.9	3.8	4.5	4.1	4.4	3.7	3.9	4.4	3.9	4.2	4.2	3.8	3.8	N/A	4.0	4.6	3.5	5.4	3.6 4.5		
Bankfull Discharge (cfs)	-	30	9.5	14	9	32	47	53	32	23	12	33	53	55	30.3	N/A	14.5	16.5	41.2	94.9	47.2 78.4		
O NEE rograssion (2 yr)	.								_	-						,	-						
Q-USGS extrapolation (1.2-yr)	N/A	18.0		26.0	6.6	24.8	44.0	51.0															
Q-Mannings					12 13	22 23		68															
Valley Slope (ft/ft)		0.0150	N/A	0.0325	0.0444	0.0152	0.0163	0.0129	0.0150	0.0325	0.0444	0.0152	0.0163	0.0129	0.0150	N/A	0.0325	0.0444	0.0152	0.0163	0.0129		
Channel Thalweg Length (ft)		553	135	438	630		90	1,203	595	459	662		934	1,039	590	135	459	644		930	1,296		
Sinuosity		1.16	1.01	1.01	1.08	1.22	1.22	1.28	1.15	1.10	1.05 1.10	1.18	1.15	1.10	1.2	N/A	1.1	1.1		1.1	1.4		
Bankfull/Channel Slope (ft/ft)	-	0.0180	0.0482	0.0153	0.0405	0.0163	0.0186	0.0118	0.0131	0.0295	0.0411	0.0130	0.0140	0.0105	0.0171	0.0555	0.0395	0.0382		0146	0.0126		

#### Table 11b. Baseline Stream Data Summary

Area B - Pre-Restoration Condition

Big Harris Creek Mitigation Site

DMS Project No. 739

Monitoring Year 3 - 2020

Area B																									
													Pre-Restora	tion Condition											
Parameter	Cara	TII: a44 (	Creek Reach 1	FILL AND C	reek UT1	Duideas Cu	eek Reach 1	UT1 to Brid	dana Cunnis	Lower Fle	etcher Creek	Lower Fle	tcher Creek	Upper Stick	Elliot Creek	Upper Stick	Elliott Creek	Upper Stick	k Elliott Creek	Upper Stick	Elliott Creek	Upper Stick	Elliott Creek	Upper Fle	tcher Creek
Parameter	Gage	Elliott	стеек кеасп 1	Elllott	reek UTI	bridges Cr	ек кеасп 1		ages Creek	Re	each 1		ach 2		ach 1		ach 5		ach 6	_	T2	1	IT3		ach 2
		Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Dimension and Substrate - Shallow	, I			1 .		1		-	•	1	16.4	1						T	1	1					
Bankfull Width (ft)	)		7.7		5.0	2.9	5.3	3. 4.			16.4 21.0		9.2		1.9 5.0		4.0	15.7	24.7		1.4		1.2		9.2
Floodprone Width (ft) Bankfull Mean Depth	<u> </u>		18.0 0.5		).4	6.0 0.4	17.0 1.0	0.			0.8		1.0		).4		1.2	19.0 0.7	58.0 1.2		7.0 ).7		5.0 ).8		9.0
Bankfull Mean Deptr	1		0.5		).2	0.4	1.0	0.		_	1.1		1.3		).6		1.7	1.5	1.7		).9		l.1		1.7
Bankfull Cross-sectional Area (ft²)	N/A		4.0		3.9		1.2	0.			12.4		9.1		l.9		8.4		18.4		2.9		3.6		.0.3
Width/Depth Ratio	1 .,,,		14.9		6.3	3.0	9.8	18			21.6		9.2		2.3		2.6	13.5	34.4		5.8		5.0		8.3
Entrenchment Ratio	2		2.3		l.1	2.2	4.7	1.		_	1.3		1.2		1.3		1.5	1.2	2.3		1.6		1.3		2.0
Bank Height Ratio	1		1.9		7.3	1.9	2.3	6.			5.1		2.3		0.7		1.7	1.4	3.5		1.0		1.1		3.2
D <sub>50</sub> (mm)	)					1				1				1				+							
Profile	· I			l																<u> </u>					
Riffle Length (ft)	)																								
Riffle Slope (ft/ft)	)		0.0179	0.0	0250	0.0	208	0.08	812	0.	.0204	0.	0198	0.0	0320	0.0	0150	0.	0175	0.0	)200			0.0270	0.0458
Pool Length (ft)	)																								
Pool Max Depth (ft)	/ N/A	1.0	1.4	0.5	0.5	1.2	1.5	0.5	0.5	1.1	1.4	1.3	1.7	1.3	2.0	1.7	2.1	0.8	1.0	1.0	1.2	1.3	1.4	7	2.2
Pool Spacing (ft)	)	15.0	100.0	22.5	27.9	22.1	51.2	3.8	4.1	65.0	80.0	6.0	80.0	14.1	68.1	15.0	90.0	15.0	90.0	29.5	49.3	21.5	21.5	77.0	259.0
Pool Volume (ft <sup>3</sup> )	)																								
Pattern																									
Channel Beltwidth (ft)	)	3	40	4	20	11	26	9	13	21	43	39	43	4	37	21	97	20	49	7	38	17	17	48	143
Radius of Curvature (ft)	)	7	74	5	23	6	25	6	25	53	98	100	130	2	23	11	76	15	69	12	26	21	33	10	90
Rc:Bankfull Width (ft/ft)	) N/A	0.9	9.6	1.4	6.9	2.0	4.8	1.7	7.5	3.2	6.0	10.9	14.1	0.5	4.6	0.8	5.0	0.9	2.8	2.8	6.0	5.0	7.9	1.1	9.8
Meander Length (ft)	)	54	166	45	56	44	102	44	102	249	336	318	336	28	136	72	134	142	304	59	99	43	43	200	295
Meander Width Ratio	)	0.3	5.1	0.7	3.6	3.8	8.9	3.8	8.9	4.2	4.7	4.2	4.7	5.8	27.8	1.4	6.4	0.8	2.0	1.5	8.7	4.0	4.0	5.2	15.5
Substrate, Bed and Transport Parameters																									
Ri%/Ru%/P%/G%/S%	ó																								
SC%/Sa%/G%/C%/B%/Be%	6																								
d16/d35/d50/d84/d95/d100	N/A								-					-											
Reach Shear Stress (Competency) lb/ft <sup>2</sup>	2 11/A					-			-					-						-					
Max part size (mm) mobilized at bankfull	I																								
Stream Power (Capacity) W/m <sup>2</sup>	2																								
Additional Reach Parameters																									
Drainage Area (SM)	)		0.13	C	.02	0	.07	0	01	(	0.41	(	).42		.05	0	.72	C	).76	0	.07	C	.10	0	).42
Watershed Impervious Cover Estimate (%)	)													10%											
Rosgen Classification	1	In	ncised C5		F4		ed E4	F5			F4		F4		F4		34c		d C4 / F4		<del>3</del> 4		G4		F4
Bankfull Velocity (fps)	)		4.2		5.2	1	.8	3.			4.8		4.1		1.8		2.8		2.9	1	1.2		1.2		3.6
Bankfull Discharge (cfs)	)		17		3		12	3			35		37		9		52		54		12		15		21
Q-NFF regression (2-yr)	N/A													<del>                                      </del>											
Q-USGS extrapolation (1.2-yr)	) '		11		2		7	1		_	144		162				43		45		7		9		21
Q-Mannings	5		15		9	1	12	2.			46		44				73		53	1	11		20	40	60
Valley Slope (ft/ft)	<u> </u>		0.0179		135		208	0.08			.0125		0198		0638		0143		0087		0208		0353		0160
Channel Thalweg Length (ft)	)		1,389		.41		45	5		_	574		167		52		909		,036	1	56		.07		,465
Sinuosity	(		1.30		.17		.06	1.3			1.10		03		.04		53		1.09		.22		.22		23
Bankfull/Channel Slope (ft/ft)	)		0.0138	0.0	0113	0.0	196	0.07	/00	0.	.0113	0.	0192	0.0	0613	0.0	0093	0.	0800	0.0	)200	0.0	0289	0.0	0130

### Table 11c. Baseline Stream Data Summary

### Area B - Design Parameters

Big Harris Creek Mitigation Site

DMS Project No. 739

Monitoring Year 3 - 2020

Area B																						
	Design																					
			=111						Lower Flet	cher Creek	Lower Fle	tcher Creek	Upper Stic	k Elliott Creek	Upper Stic	k Elliott Creek	Upper Stick	Elliott Creek	Upper Stick	Elliott Creek	Upper Flet	cher Creek
Parameter	Elliott Cre	ek Reach 1	Elliott	Creek UT1	Bridges Cre	ek Reach 1	UI1 to Br	ridges Creek	Read	ch 1	Rea	ach 2	Re	ach 5	Re	each 6	U	T2	U	г3	Rea	ch 2
	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Dimension and Substrate - Shallow		7.5	l	4.9		.9		4.9	1 44		-	2.4	T .	16.0		46.0	-	_	_	2	4.0	
Bankfull Width (ft)		7.5	10.8	_	9.7	.9 15.3	10.8		26.0	8		2.4				16.0	14.8	.7	7. 15.9			).5
Floodprone Width (ft)	16.5				_						27.3		22.5	35.3	35.3						50.0	100.0
Bankfull Mean Depth		).5		0.4		.5		0.4	0.			).9		1.1		1.1		.5	0.		0.	
Bankfull Max Depth	1.1	1.9 4.0	0.8	2.0	1.1	1.9 .7	0.8	2.0	1.7	3.0	1.8	3.1	2.3	4.0 18.4	2.3	4.0 18.4	1.0	1.8 .5	1.1	1.9	2.:	
Bankfull Cross-sectional Area (ft²)		4.0		12.0		3.0		12.0	14			4.0		14.0		14.0		3.0	13			2.2
Width/Depth Ratio Entrenchment Ratio		.2+		2.2+	1.4	2.2		2.2+	2.3			.2+	1.4	2.2		2.2+		2+	2.:		4.8	9.5
Bank Height Ratio		1.0		1.0		.0		1.0	1.			.2+ L.0		1.0		1.0		.0	1.		4.8	
D <sub>50</sub> (mm)																						
Profile																		<u></u>	-	·-		
			1		T		1						1		1		Τ					
Riffle Length (ft) Riffle Slope (ft/ft)	0.020	0.030	0.030	0.050	0.025	0.047	0.074	0.098	0.013	0.018	0.022	0.029	0.009	0.014	0.015	0.020	0.005	0.007	0.020	0.026	0.021	0.032
Pool Length (ft)					0.025				0.015				1		1		+		0.020			
Pool Length (ft) Pool Max Depth (ft)	1.1	1.9	0.8	1.4	1.1	1.9	0.8	1.4	1.7	3.0	1.8	3.1	2.3	4.0	2.3	4.0	1.0	1.8	1.1	1.9	2.:	
Pool Spacing (ft)	26	45	17	29	24	55	17	29	41	71	43	74	88	119	63	109	24	45	25	43	40	100
Pool Volume (ft <sup>3</sup> )	20	43	1/	23	24	33	-1/	23	41	/1	43	/4	00	119	03	109	24	43	23	43	40	100
Pattern																						
		1		1	ı		T	1								T	1					
Channel Beltwidth (ft)	19	60	17	39			17	39	41	95	43	99	61	81	62	78	24	54	25	58	25	95
Radius of Curvature (ft)	15 2.0	26	10	17			10 2.0	17	24	41	25	43	33	56 3.5	32	43 2.7	13	24	14 1.9	25 3.5	23	50
Rc:Bankfull Width (ft/ft)	52	3.5 90	2.0 34	3.5 59			34	3.5 59	2.0 83	3.5 142	2.0 87	3.5 149	2.1 139	192	2.0 166	191	1.9 47	3.6 81	50	3.5 87	100	4.8 200
Meander Length (ft)  Meander Width Ratio	2.5	8.0	3.5	8.0			3.5	8.0	3.5	8.0	3.5	8.0	3.8	5.0	3.8	4.8	3.5	8.0	3.5	8.0	2.4	9.0
Substrate, Bed and Transport Parameters	2.3	0.0	3.3	0.0			3.3	6.0	3.3	6.0	3.3	0.0	3.0	3.0	3.0	4.0	3.5	6.0	3.3	6.0	2.4	9.0
Ri%/Ru%/P%/G%/S%																	+					
SC%/Sa%/G%/C%/B%/Be% d16/d35/d50/d84/d95/d100																						
		.47			0.	C F			0.	73		.45		0.55		<u>l</u> 0.69						
Reach Shear Stress (Competency) lb/ft <sup>2</sup> Max part size (mm) mobilized at bankfull	U	.47			0.	03		 I	0.	/3	U	.43 		J.33		0.69	-	-	-	-	-	-
Stream Power (Capacity) W/m <sup>2</sup>																						
Additional Reach Parameters																						
		.13		0.02	0.	07		0.01	0.4	4.1	0	.42	1	0.72		0.76	1 0	07	0.:	10	0 :	29
Drainage Area (SM)  Watershed Impervious Cover Estimate (%)	- 0	.13		0.02	0.	07		J.U1	0.4	41		.42 <10%		J.72		0.76	0.	07	0.	10	0	29
Rosgen Classification		C5		C4	1 .	4		C4	С	4		C4	1	C4	1	C4	1 .	24	C	4		
Bankfull Velocity (fps)		1.3		3		.2		1.5	3.			3.4		2.8		2.9	3		3.		3.	
Bankfull Velocity (rps)  Bankfull Discharge (cfs)		+.3 17		6		2		3	3.			37		52		54		.4	1			.5
Q-NFF regression (2-yr)		1/		U	1	4		J	3	J		<i>31</i>		JŁ		J4		.4	1	J	3	U
Q-INFF regression (2-yr) Q-USGS extrapolation (1.2-yr)																						
Q-OSGS extrapolation (1.2-yr)  Q-Mannings																						
Valley Slope (ft/ft)	0.0	0174	0	0302	0.0	290	0	0580	0.00	ารด	0.0	0150	n	0110	n	.0115	0.0	045	0.0	150	0.0	158
Channel Thalweg Length (ft)		121		141		76		55	57			27		,507		1,069		54	11		1,4	
Sinuosity		.19		l.19	1.			L.20	1.0			.03		1.34		1.13		27	1.0		1,4	
Bankfull/Channel Slope (ft/ft)		0149		0255	0.0			.049	0.00			0088		0080		.0101		035	0.0		0.0128	0.0263
SC: Silt/Clay <0.062 mm diameter particles	0.0	J ± T J	ı	U_JJ	0.0	, <u>_</u> U	0.	.0-13	0.00	JJU	0.0	,,,,,	U.	0000	1 0	.0101	1 0.0	JJJ	0.0	100	0.0120	0.0203

#### Table 11d. Baseline Stream Data Summary

### Area B - As-Built/Baseline Parameters

Big Harris Creek Mitigation Site

DMS Project No. 739

Monitoring Year 3 - 2020

												As-Built	/Baseline													
Parameter	Elliott Cre	Elliott Creek Reach 1		Elliott Creek Reach 1		reek UT1	Bridges Creek Reach 1		UT1 to Br	ridges Creek		etcher Creek ach 1	Lower Fletcher Creek Reach 2		Upper Stick Elliot Creek Reach 1		Upper Stick Elliott Creek Reach 5		Upper Stick Elliott Creek Reach 6		Upper Stick Elliott Creek		Upper Stick Elliott Creek UT3		Upper Fletcher Creek Reach 2	
	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max		
mension and Substrate - Shallow																				•	•					
Bankfull Width (ft)	6.4	8.2		5.2		9.3		N/A		12.3		9.9		5.7	15.9	18.4	16.7	18.3		'.9		7.2	11.5	12.0		
Floodprone Width (ft)	19.0	19.6		4.0		3.6		N/A		26.4		8.4		7.2	169.2	178.4	148.5	192.7		5.0		3.8	72.0	99.5		
Bankfull Mean Depth	0.6	0.7	0	0.5	0	).4	1	N/A	(	0.8	(	0.6	(	).7	1.0	1.2	1.1	1.2	0	1.5	(	0.5	0.8	0.8		
Bankfull Max Depth	0.9	0.9	0	0.8	0	).7	1	N/A		1.1	(	0.8		).9	1.7	1.8	2.0	2.2	0	1.9	(	0.8	1.4	1.4		
Bankfull Cross-sectional Area (ft <sup>2</sup> )	4.1	5.6	2	2.5	3	3.3	1	N/A	9	9.7	(	5.3	4	1.7	18.9	19.2	19.1	22.4	3	.8	3	3.7	9.2	9.5		
Width/Depth Ratio	10.1	11.9		0.7		6.5		N/A		L5.7		5.4		9.6	13.3	17.8	14.6	14.9	10	6.5		.4.0	14.0	15.6		
Entrenchment Ratio	2.4	2.9	2	2.7	2	2.5	1	N/A		2.1		2.9	5	5.5	9.2	10.9	8.9	10.5	3	.2	8	8.8	6.0	8.6		
Bank Height Ratio	1.0	1.0	1	1.0	1	.0	1	N/A	:	1.0		1.0	1	.0	1.0	1.0	1.0	1.0	1	0	1	1.0	1.0	1.0		
D <sub>50</sub> (mm)	32	42	3	31	53	3.7	1	N/A	3	35.3	1	1.0	3	2.0	35.0	39.8	41.1	46.1	14	4.9	1	.4.4	39.1	54.8		
ofile																										
Riffle Length (ft)	7	64	11	21	11	32	6	6	11	55	14	36	6	18	39	74	13	80	14	37	18	19	16	69		
Riffle Slope (ft/ft)	0.0076	0.0712	0.0018	0.0429	0.0129	0.0576	0.0686	0.0862	0.0008	0.0466	0.0050	0.0396	0.0028	0.1323	0.0068	0.0218	0.0038	0.0653	0.0065	0.0167	0.0092	0.0257	0.0078	0.0631		
Pool Length (ft)	10.98	73.26	12.42	18.46	6.36	34.19	8.56	8.56	10.61	44	17.92	53.39	3.72	55.52	14.68	66.89	14.35	79.03	18.84	51.34	8.77	14.02	13.89	63.47		
Pool Max Depth (ft)	1.1	2.3	1.1	1.4	1.6	2.4	1.0	2.0	1.4	1.6	1.8	2.2	1.7	2.2	1.9	4.1	2.0	4.6	1.0	1.7	1.5	1.7	2.5	4.5		
Pool Spacing (ft)	20	132	18	45	29	49	11	11	36	92	42	90	22	102	48	128	43	127	62	62	26	34	45	162		
Pool Volume (ft <sup>3</sup> )					=														-	-						
attern									11 111111111111111111111111111111111111		<u> </u>	<u> </u>														
Channel Beltwidth (ft)	14	38	Ι ο	17	9	1 1 5	23	23	20	73	T	44	N/A	N/A	37	64	27	57	24	24	16	16	8	T 71		
	14 8	42	8			15			12					N/A N/A		48					9			71		
Radius of Curvature (ft) Rc:Bankfull Width (ft/ft)	1.3	5.1	15 2.9	20	10	19 2.0	19	19 N/A	1.0	50 4.1	53 5.4	79 8.0	N/A N/A	N/A N/A	25		24 1.4	39	20	17	1.3	12	23	50 4.2		
	46	156	48	3.8	1.1			-		138			· · · · · · · · · · · · · · · · · · ·		1.6 128	2.6	1.4	2.2 193	54	2.2 54		32	92	195		
Meander Length (ft) Meander Width Ratio		4.6	1.4	69 3.3	68 1.0	80	51	51 N/A	73	5.9	201 4.4	0.0	N/A N/A	N/A N/A	2.3	3.5	1.6		3.1	3.1	32 2.2	2.2	0.7	5.9		
	2.2	4.6	1.4	3.3	1.0	1.6	<u> </u>	N/A	1.6	5.9	4.4	0.0	N/A	N/A	2.3	3.5	1.6	3.1	3.1	3.1	2.2	2.2	0.7	5.9		
bstrate, Bed and Transport Parameters																										
Ri%/Ru%/P%/G%/S%																										
SC%/Sa%/G%/C%/B%/Be%																										
d16/d35/d50/d84/d95/d100		8/6/101.2/ .8/180	SC/1/5.9/4	7/101.2/180	SC/0.16/1/9	90/135.5/180	1	N/A	-	9/1.8/57.9/ .1/180	-	9/4.4/40.5/ .7/362		20.7/68.5/ 1/256	0.15/2.18, 103.6			'3.3/60.4/ 8/180	SC/0.14/0.2	2/26.1/48/64	SC/SC/0.2/2	20.5/35.9/ 180		/10.4/55.9/ 4/180		
Reach Shear Stress (Competency) lb/ft <sup>2</sup>	0	0.66	1.	.08	1.	.35	1	N/A	C	0.40	0	.71	3	.66	0.3	35	0.	41	0.	.44	0	).46	0	).55		
Max part size (mm) mobilized at bankfull																										
Stream Power (Capacity) W/m <sup>2</sup>																										
dditional Reach Parameters																										
Drainage Area (SM)	0	0.13	I 0.	.02	0.	.07		0.01		0.41	0	1.42	0	.05	0.7	72	0.	.76	0.	.07	0	0.10	0	0.29		
Watershed Impervious Cover Estimate (%)		-			1		1		·				10%									-	<u>.                                    </u>			
Rosgen Classification	C	C/E4	C/	/E4		25	1	N/A		C5		C4		E4	C	4	(	:4		25		C5		C4		
Bankfull Velocity (fps)		3.2		3.7		1.9		N/A		3.1		3.4		3.5	3.4	3.8	3.8	4.1		.4		2.1	3.3	3.6		
Bankfull Discharge (cfs)		13.3		9.2		).7		N/A		29.9		1.3		9.9	63.4	72.8	73.1	90.9		.0		7.7	30.2	34.1		
Q-NFF regression (2-yr)	_	-								-		-			-3			5.5								
Q-USGS extrapolation (1.2-yr)																										
Q-Mannings																										
Valley Slope (ft/ft)	0.0	0174	0.0	0302	0.0	)290	0.	0580	0.0	0089	0.0	0150		I/A	0.00	110	0.0	115	0.0	0045	0.0	0150	N	N/A		
Channel Thalweg Length (ft)		,121		.41		76		55		574		127		09	1,2	_		070		54		118		.407		
Sinuosity		1.1		l.1		0		1.0		1.1		1.0		0	1,2			1		4		1.3		1.2		
Siliuosity	•	4.4		0247		308	1	1.0	1		1	1.0		)837	1.	081		1093		101	_	0105		0125		

## Table 11e. Baseline Stream Data Summary

### Area C

Big Harris Creek Mitigation Site DMS Project No. 739

Monitoring Year 3 - 2020

## Area C

Area C																	
		Pre-Restoration Condition Design									As-Built/Baseline						
Parameter	Gage	_	Harris Creek h 1a/1b		Harris Creek ich 2	_	Harris Creek 1a/1b	Lower Big H		Lower Big F		_	Harris Creek ich 2				
	!	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max				
Dimension and Substrate - Shallow	ı	1															
Bankfull Width (ft)			25.2		5.2		5.0	27			.20		5.70				
Floodprone Width (ft)			20.0		0.0	75.0	115.0	100.0			158 1.9		00				
Bankfull Mean Depth			2.4		2.4	2.1		2					7				
Bankfull Max Depth			3.6		3.6		9	3			.0		8				
Bankfull Cross-sectional Area (ft <sup>2</sup> )	N/A		50.5	60.5			4.4	58		49		1	6.0				
Width/Depth Ratio		10.5			0.5		2.4	12		13			5.5				
Entrenchment Ratio			4.8		.8	2.9	4.4	3.7	7.4		.0		1.2				
Bank Height Ratio			2.0		0		0	1		1			0				
D <sub>50</sub> (mm)	<u> </u>	<u> </u>		<u> </u>						32	2.0	8	7.4				
Profile																	
Riffle Length (ft)	]					-			-	15	142	21	146				
Riffle Slope (ft/ft)	]	0.0133	0.0512	0.0063	0.0177		0.0054	0.0054	0.0086	0.0055	0.0792	0.0019	0.0651				
Pool Length (ft)	N/A									54.2 3.9	94.3	14.2	134.9				
Pool Max Depth (ft)			4.1		.2		.0		6.2		6.2	4.6	6.0				
Pool Spacing (ft)		200.0	250.0	410.0	480.0	185	240	150	250	116	218	37	291				
Pool Volume (ft <sup>3</sup> )																	
Pattern																	
Channel Beltwidth (ft)		75	120	85	125	53	112	110	145	58	105	80	117				
Radius of Curvature (ft)		70	165	120	190	60	80	75	90	60	80	65	90				
Rc:Bankfull Width (ft/ft)	N/A	2.8	6.5	4.8	7.5	2.3	3.1	2.8	3.3	2.3	3.1	2.4	3.4				
Meander Length (ft)		350	450	250	300	290	440	344	420	157	419	236	396				
Meander Width Ratio		3.0	4.8	3.4	5.0	2.0	4.3	4.1	5.4	2.2	4.0	3.0	4.4				
Substrate, Bed and Transport Parameters																	
Ri%/Ru%/P%/G%/S%																	
SC%/Sa%/G%/C%/B%/Be%	1																
d16/d35/d50/d84/d95/d100	N/A	1.9/16/29/	83/130/2048	1.9/16/29/8	33/130/2048					0.4/0.8/1.7/9	94/256/2048	0.2/0.3/5.6/	94/256/2048				
Reach Shear Stress (Competency) lb/ft <sup>2</sup>	N/A			-		-			-	-		-					
Max part size (mm) mobilized at bankfull																	
Stream Power (Capacity) W/m <sup>2</sup>																	
Additional Reach Parameters																	
Drainage Area (SM)		3.19	3.36	3.50	3.88	3.	.36	3.	88	3.	36	3.	.88				
Watershed Impervious Cover Estimate (%)	1			-1			<:	10%		*							
Rosgen Classification		E4	G4c	E4	G4c		С	(	Ĵ	C	<u>.</u> 5	(	C4				
Bankfull Velocity (fps)			2.9	3	3.2	3	.3	3	.4	3	.6	3	3.0				
Bankfull Discharge (cfs)		1	176	1	94	1	76	19	94	1	76	1	37				
Q-NFF regression (2-yr)	N/A																
Q-USGS extrapolation (1.2-yr)	IN/A	1	190	2	11												
Q-Mannings		182	255	205	350												
Valley Slope (ft/ft)			0053		053	0.0	053	0.0		0.0		0.0053					
Channel Thalweg Length (ft)	4		394		87	8	20	96	57		20	967					
Sinuosity			1.0		0		1	1		1			1				
Bankfull/Channel Slope (ft/ft)		0.0	0050	0.0	050	0.0	048	0.0	048	0.0	039	0.0032					

SC: Silt/Clay <0.062 mm diameter particles

(---): Data was not provided

N/A: Not Applicable

# Table 11f. Baseline Stream Data Summary

Big Harris Creek Mitigation Site DMS Project No.739

Monitoring Year 3 - 2020

											Reference Reac	h Data							
Parameter	Gage	Group Car	np	UT to	South	UT to Ca	ne Creek	Boyd Branch	Spence	er Creek	Box Creek	Hall	Creek	Meadow Fork	UT to Gap	UT to Kelly	UT to Sai	ndy Run	UT to Little Pine
raiametei	Gage	Tributary		Crow			ı		•						Branch	Branch		,	Trib 1
Dimension and Substrate - Shallow		Min I	Vlax	Min	Max	Min	Max	Min Max	Min	Max	Min Max	Min	Max	Min Max	Min Max	Min Max	Min	Max	Min Max
Bankfull Width (ft)		4.2	4.4	6.1	8.4	11.5	12.3	13.5	10.7	11.2	23.5	20.7	27.0	21.4	6.2	7.9	7.3	7.8	12.2
Floodprone Width (ft)			4.4 10.6	26.0	31.0		12.3 L.0	37.0	60.0	11.2	76.0	34.0	39.0		20.9	9.1	12.2	15.6	72.0
Bankfull Mean Depth			0.8	1.0	1.1	0.8	1.0	1.1	1.6	1.8	1.2	1.4	1.8	2.1	0.6	0.7	0.7	0.8	1.3
Bankfull Max Depth			1.2	1.0		1.2	1.6	1.9	2.1	2.6	1.9	3		3.1	1.0	1.1	1.1	1.4	1.8
Bankfull Cross-sectional Area (ft²)	N/A		3.6	6.4	8.7	8.9	12.2	15.4	17.8	19.7	28.9	1	5.9	44.0	3.8	5.7	5.7	6.2	16.3
Width/Depth Ratio	IN/A		55.0	5.8	8.0	12.3	14.4	11.8	5.8	7.1	19.1	11.6	19.7	10.4	10.1	10.9	6.6	9.8	9.1
Entrenchment Ratio			2.5	3.7	4.3	2.5	2.7	2.8	5.5	10.2+	3.3	1.4	1.6	>2.2	3.4	1.2	1.6	2.1	6.0
Bank Height Ratio			1.0	1.4	2.1			1.0		1.0	1.5	2.1	2.2	1.1	1.0	2.5	1.7	2.6	1.0
D50 (mm)		1.0	1.0	1.4	2.1			1.0	-	<u> </u>	1.5	2.1	2.2	1.1	1.0	2.5	1.7	2.0	1.0
D30 (IIIII)		L																	
Riffle Length (ft)		T										-							
Riffle Slope (ft/ft)			1218	0.0202	0.0664	0.0188	0.0704	0.015 0.028		013	0.0100 0.0770	0.008	0.02	0.2390	0.01 0.14		0.004		0.0600 0.0892
Pool Length (ft)			1210																
Pool Max Depth (ft)	N/A	1.8	2.8	1.3	3	1.8	2.3	2.6	3.3		4.4	2.7	3.5		15.0		1.3	1.5	2.2
Pool Spacing (ft)			58	28	63	27	73	260 345	71		29 88	35	108		3 4		9	55	26 81
Pool Volume (ft <sup>3</sup> )		- 1																	
Pattern																			
Channel Beltwidth (ft)		16	17	8	:1	1(	02	230.0	38	41	62 88	35	41			18 34	24	60	
Radius of Curvature (ft)			12	9	20	23	38	50 180	1.3	1.4	1 2	1	4			8 26	14	29	
Rc:Bankfull Width (ft/ft)	N/A												<u> </u>						
Meander Length (ft)	,	31	34	45	72	45	81	600 623	46	48	39 76	78	200			27 94	63	72	
Meander Width Ratio			3.8	9.6	13.3	8.3	8.9	17.0	3.4	3.6	2.6 3.7	1.5	1.7			2.3 4.3	3.3	7.6	
Substrate, Bed and Transport Parameters													ı					- 1	
Ri%/Ru%/P%/G%/S%																			
SC%/Sa%/G%/C%/B%/Be%																			
14.5 / 12.5 / 15.0 / 10.4 / 10.5 / 14.00		0.1/0.3/16/55		0.8/12.1/	19.7/49.5	0.6/12.2/2	27.8/74.5/		< 0.063	/3/8.8/4	44 /44 /22 /50 /70 /	<0.063/	1/13/70/	69/16/31/120/	0.4/8/19/102.3		0.062/1/	19/76/1	<0.063/2.4/22.6/1
d16/d35/d50/d84/d95/d100	N/A	0.1/0.3/16/55	0.6/	/75.	9/	128	3/		2/9	0/	41/11/22/50/78/	110	)/	230/	/256/		50/	′	20/256
Reach Shear Stress (Competency) lb/ft <sup>2</sup>	•																		
Max part size (mm) mobilized at bankfull																			
Stream Power (Capacity) W/m <sup>2</sup>																			
Additional Reach Parameters																			
Drainage Area (SM)		0.10		0.:	22	0	29	0.90	0	.96	2.13	4.	09	4.37	0.04	0.08	0.1	15	1.10
Watershed Impervious Cover Estimate (%)																			
Rosgen Classification		E5b		Е	4	Е	4	E4		E4	C4	В	4c	E4	B4a	A4	E4	4	E4b
Bankfull Velocity (fps)			3.6				.8	3.2	4.9	5.4	3.3		.3	5.1	5	6.2	3.		5.5
Bankfull Discharge (cfs)		12		3	0		10	51		97	94.9		59	224	18.7	23.2	19		85
Q-NFF regression (2-yr)												6							
Q-USGS extrapolation (1.2-yr)	N/A											-						-	
Q-Mannings												-						-	
Valley Length (ft)				_															
Channel Thalweg Length (ft)												-						-	
Sinuosity		1.60		2	20	1.4	40	1.40	1	.30	1.30	1.	04		1.12	1.19	1.6	50	1.10
Water Surface Slope (ft/ft) <sup>2</sup>																		-	
Bankfull Slope (ft/ft)												-							
CC CIL/CL0.0C2		•						1	•			1							

SC: Silt/Clay <0.062 mm diameter particles
(---): Data was not provided
N/A: Not Applicable

### Table 12a. Morphology and Hydraulic Summary (Dimensional Parameters - Cross-Section)

Big Harris Creek Mitigation Site DMS Project No. 739

Monitoring Year 3 - 2020

AREA A																														
		Cross-Sec	ction 1, UBH	IC R2A (Riff	le)			Cross-Sec	tion 2, UBH	C R2a (Pool	)			Cross-Sec	ction 3, UBH	IC R2B (Poo	I)			Cross-Sect	ion 4, UBH	C R2B (Riffle	e)			Cross-	Section 5, U	JBHC R4 (Poo	ol) <sup>2</sup>	
imension <sup>1</sup> and Substrate	Base (3/2018)	MY1 (11/2018)	MY2 (06/2019)	MY3 (06/2020)	MY4	MVE	Base (3/2018)	MY1 (11/2018)	MY2 (06/2019)	MY3 (06/2020)	MVA	MVE	Base (3/2018)	MY1 (11/2018)	MY2 (09/2019)	MY3 (10/2020)	MVA	MY5	Base (3/2018)	MY1 (11/2018)	MY2 (09/2019)	MY3 (10/2020)	MVA	MVE	Base (4/2018)	MY1 (10/2018)	MY2 (07/2019)	MY3 (06/2020)	MY4	MY5
Bankfull Elevation (ft)		929.0	929.2	929.5	IVI 14	IVITO	928.7	928.7	928.7	928.9	IVITA	IVITO	921.0	921.2	921.1		10114	IVITO	920.8	921.0	920.5	919.1	10114	IVITO	900.1	900.2	899.9	899.8	10114	IVITS
Low Bank Elevation (ft)	929.2	929.0	929.2	929.3	1		928.7	928.7	928.7	928.9			921.0	921.2	921.1	921.1 921.1			920.8	921.0	920.5	920.9			900.1	900.2	899.9	899.8		
Bankfull Width (ft)	16.0	10.4	13.4	10.4			13.5	12.2	13.3	11.4		1	12.0	16.1	15.2	15.4			11.3	18.2	13.8	18.9			17.0	19.2	11.9	10.9		
Floodprone Width (ft)	108.7	10.4	89.3	89.2	1		N/A	N/A	N/A	N/A		1	N/A	N/A	N/A	N/A			170.3	118.6	63.4	67.5			17.0 N/A	N/A	N/A	N/A		_
Bankfull Mean Depth (ft)	0.7	0.6	0.6	0.8	1		1.4	0.9	1.2	1.5			1.2	1.7	1.8	2.1			1.6	2.4	1.3	2.3			1.4	1.1	1.4	1.2		
Bankfull Mean Depth (π)  Bankfull Max Depth (ft)	1.5	1.4	1.9	2.0	<del>                                     </del>		3.1	1.7	2.8	2.9			1.2	4.0	3.7	4.3			3.0	4.2	2.4	4.0			2.7	2.7	2.7	2.3		
Bankfull Cross-Sectional Area (ft)	11.6	6.6	8.2	8.3	1		19.3	11.0	16.5	16.5		1	14.0	27.0	27.2	33.1			17.7	44.1	18.4	44.0			23.5	20.6	17.2	12.9		
Bankfull Width/Depth Ratio	22.0	16.5	21.7	13.1	1		N/A	N/A	N/A	N/A		1	N/A	N/A	N/A	33.1 N/A			7.3	7.5	10.4				23.5 N/A	20.6 N/A	N/A	N/A		
			+	+	<del>                                     </del>				<del>                                     </del>				· '									8.1						<del>                                     </del>		
Bankfull Entrenchment Ratio <sup>3</sup>	6.8	10.0	6.7	8.6			N/A	N/A	N/A	N/A			N/A	N/A	N/A	N/A			15.0	6.5	4.6	3.6			N/A	N/A	N/A	N/A		
Bankfull Bank Height Ratio	1.0	0.8	0.9	0.9			N/A	N/A	N/A	N/A			N/A	N/A	N/A	N/A			1.0	1.8	1.0	1.8			N/A	N/A	N/A	N/A		
		1	ection 6, UBI		e)				tion 7, UBH	_ `	)	1			ction 8, UBI					Cross-Section			fle)					yster Cr R1 (	(Pool)	
	Base	MY1	MY2	MY3			Base	MY1	MY2	MY3			Base	MY1	MY2	MY3			Base	MY1	MY2	MY3			Base	MY1	MY2	MY3		1 1
mension <sup>1</sup> and Substrate	(4/2018)	(10/2018)			MY4	MY5	(4/2018)	(10/2018)	(07/2019)	(06/2020)	MY4	MY5	(4/2018)		(07/2019)		MY4	MY5		(10/2018)		(06/2020)	MY4	MY5	, ,	(10/2018)	(06/2019)	(06/2020)	MY4	MY5
Bankfull Elevation (ft)	899.7	899.7	899.7	899.8			896.5	896.5	896.6	896.6			896.0	895.9	895.8	896.0			965.0	965.0	965.0	965.3			961.5	961.4	961.3	961.4		
Low Bank Elevation (ft)	899.7	899.7	899.7	899.7			896.5	896.5	896.6	896.6			896.0	895.9	895.8	896.0			965.0	965.0	965.0	964.9			961.5	961.4	961.3	961.4		
Bankfull Width (ft)	15.5	16.2	14.9	14.9			16.0	15.7	15.4	16.2			20.9	16.9	15.6	18.2			10.0	9.4	8.3	4.1			12.3	11.2	8.8	11.0		
Floodprone Width (ft)	118.0	110.8	119.2	121.7			190.0	167.4	137.2	137.3			N/A	N/A	N/A	N/A			46.7	46.1	39.5	39.6			N/A	N/A	N/A	N/A		
Bankfull Mean Depth (ft)	0.8	0.6	0.8	0.8			1.1	0.9	1.1	1.1			1.5	1.8	1.5	1.7			0.4	0.4	0.2	0.2			0.9	0.9	0.8	0.9		
Bankfull Max Depth (ft)	1.4	1.3	1.5	1.6			2.0	2.0	2.0	2.3			3.3	3.7	3.0	3.8			0.8	0.8	0.4	0.4			1.9	1.8	1.7	1.9		
Bankfull Cross-Sectional Area (ft)	13.1	10.5	12.0	12.1			17.6	14.7	17.7	17.1			31.6	31.0	22.8	30.9			3.6	3.7	1.8	1.0			11.0	9.7	7.4	9.5		
Bankfull Width/Depth Ratio	18.3	25.1	18.4	18.5			14.5	16.6	13.4	15.3			N/A	N/A	N/A	N/A			27.6	24.1	39.0	16.7			N/A	N/A	N/A	N/A		
Bankfull Entrenchment Ratio <sup>3</sup>	7.6	6.8	8.0	8.1			11.9	10.7	8.9	8.5			N/A	N/A	N/A	N/A			4.7	4.9	4.8	9.6			N/A	N/A	N/A	N/A		
Bankfull Bank Height Ratio	1.0	0.9	1.0	1.0			1.0	0.9	1.0	1.0			N/A	N/A	N/A	N/A			1.0	1.0	0.7	0.5			N/A	N/A	N/A	N/A		1
		Cross-Se	ection 11, Sc	ott Cr (Riffle	e)			Cross-Se	ction 12, Sco	ott Cr (Pool	)			Cross-Section	on 13, Carro	ll Cr R1 (Rif	fle)			Cross-Section	on 14, Carro	oll Cr R1 (Po	ol)		<u>_</u>					-
	Base	MY1	MY2	MY3			Base	MY1	MY2	MY3			Base	MY1	MY2	MY3			Base	MY1	MY2	MY3			ı					
Pimension <sup>1</sup> and Substrate	(4/2018)	(10/2018)	(08/2019)	(06/2020)	MY4	MY5		(10/2018)	(08/2019)	(06/2020)	MY4	MY5	(4/2018)	(10/2018)	(07/2019)	(06/2020)	MY4	MY5	(4/2018)	(10/2018)	(07/2019)	(06/2020)	MY4	MY5	i					
D 16 HEL 11 (61)					1 1		200.4			000.0			000.0			000 7				004.4										

Bankfull Elevation (ft)	894.8	894.7	894.8	893.5			890.1	890.2	890.0	889.8			862.2	862.2	862.2	862.7			861.6	861.4	861.9	861.9	
Low Bank Elevation (ft)	894.8	894.7	894.8	894.8			890.1	890.2	890.0	889.8			862.2	862.2	862.2	862.3			861.6	861.4	861.9	861.9	
Bankfull Width (ft)	6.8	8.7	13.6	13.6			13.7	13.9	12.5	11.4			11.4	11.3	8.6	7.0			12.7	10.2	11.5	8.7	
Floodprone Width (ft)	67.1	44.8	45.2	44.5			N/A	N/A	N/A	N/A			82.0	82.1	71.2	79.2			N/A	N/A	N/A	N/A	
Bankfull Mean Depth (ft)	0.5	0.6	1.3	1.2			1.1	0.9	1.1	1.0			0.7	0.6	0.6	0.7			1.1	0.9	0.8	1.0	
Bankfull Max Depth (ft)	0.9	1.2	2.2	2.1			2.1	1.7	2.1	1.9			1.3	1.2	1.1	1.2			2.0	1.8	1.9	2.0	
Bankfull Cross-Sectional Area (ft)	3.6	5.1	18.1	16.2			14.9	12.2	13.4	10.9			7.9	7.0	4.9	4.7			13.4	9.4	9.4	8.5	
Bankfull Width/Depth Ratio	12.7	15.0	10.2	11.4			N/A	N/A	N/A	N/A			16.4	18.2	15.0	10.3			N/A	N/A	N/A	N/A	
Bankfull Entrenchment Ratio <sup>3</sup>	9.9	5.1	3.3	3.3			N/A	N/A	N/A	N/A			7.2	7.3	8.3	11.3			N/A	N/A	N/A	N/A	
Bankfull Bank Height Ratio	1.0	1.2	2.6	2.5			N/A	N/A	N/A	N/A			1.0	0.9	0.8	0.7			N/A	N/A	N/A	N/A	
<sup>1</sup> MYO bankfull dimensions were calculated using a	a fixed bank	full elevation.	Beginning in	MY1 Bank He	eight Ratio	os are calo	culated based	on the As-built	(MY0) cross-se	ectional area	as descri	bed in the	Standard Me	asurement of t	he BHR Monit	oring Parame	ter docun	nent prov	rided by NCIR	T and NCDMS (	2018).		
<sup>2</sup> The bankfull elevation at cross-section 5 was set	too high in	the baseline r	eport. The ba	seline bankfu	ull elevati	on was up	dated in MY1																

<sup>&</sup>lt;sup>3</sup> Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins.

## Table 12b. Morphology and Hydraulic Summary (Dimensional Parameters - Cross-Section)

Big Harris Creek Mitigation Site DMS Project No. 739

Monitoring Year 3 - 2020

## AREA B

EA B																															
				SEC R1 (Riffle	e)		Cross-Sec	ction 16, US		)				EC R5 (Riffle	)			tion 18, USE		)			Section 19,		ool)				Section 20, U		fle)
nension <sup>1</sup> and Substrate	Base	MY1	MY2	MY3	BAYA BAYE	Base	MY1 (10/2018)	MY2 (06/2019)	MY3	MY4 MY5	Base (3/2018)	MY1 (10/2018)	MY2	MY3	MY4 MY5	Base	MY1	MY2	MY3	BAVA BAVE	Base	MY1	MY2	MY3	B 43/4	B 4VF	Base (3/2018)	MY1	MY2	MY3	543/4
Bankfull Elevation (ft)					MY4 MY5	<b>(3/2018)</b> 934.0	,,		( , , , , , , ,	IVIY4 IVIY5	,	,,			IVIY4 IVIY5	<b>(3/2018)</b> 930.9	(10/2018)		931.3	MY4 MY5	928.9	(10/2018)	928.8	( <b>03/2020</b> ) 928.9	MY4	IVIY5	(-,,	, ,	(06/2019)	(,,	MY4
	979.1	979.1	979.1	979.2			934.0	933.9	934.1		932.1	932.1	932.0	932.3			930.7	931.0				928.7					925.7	925.6	925.5	925.9	-
Low Bank Elevation (ft)  Bankfull Width (ft)	979.1	979.1	979.1	979.0		934.0	934.0	933.9	934.1		932.1	932.1	932.0	932.2		930.9	930.7	931.0	931.0		928.9	928.7	928.8	928.9			925.7	925.6	925.5 14.6	925.6	-
(	5.7	7.7	7.8	6.3		17.4 N/A	18.0 N/A	17.2 N/A	17.6 N/A		18.4	18.3 167.8	15.6	18.6		18.1	16.4	17.2 86.0	17.7 86.0		20.8	20.9	20.1 N/A	21.4			15.9	16.6	14.6	15.4 108.1	
Floodprone Width (ft)	37.2	37.0	35.8	35.8				N/A	,,,		169.2		93.6	93.6		172.1	166.3				N/A	N/A	,,,,	N/A			173.2	191.0	100.0		-
Bankfull Mean Depth (ft)	0.7	0.6	0.6	0.6		1.5	1.2	1.1	1.0		1.0	1.0	0.9	0.9		1.1	1.0	1.0	0.8		1.9	1.6	1.1	1.0			1.2	1.1	1.0	0.9	
Bankfull Max Depth (ft) Bankfull Cross-Sectional Area (ft)	0.9	0.9	1.0	1.0		2.3	2.1	1.7	1.7		1.7	1.7	1.6	1.7		1.7	1.5	1.8	1.9		3.5	3.9	2.4	2.6			1.8	1.8	2.0	1.,	
	4.7	4.8	4.7	3.6		26.3 N/A	22.0	18.5	17.6		19.2	18.4	14.0	17.5		19.1	16.1	17.5	14.8		39.3	34.3	21.5	21.8			18.9	18.2	13.9	14.5	
Bankfull Width/Depth Ratio	9.6	12.3	12.7	11.2			N/A	N/A	N/A		17.8	18.1	17.5	19.9		17.2	16.7	17.0	21.2		N/A	N/A	N/A	N/A			13.3	15.1	15.2	16.4	-
Bankfull Entrenchment Ratio <sup>2</sup>	5.5	4.8	4.6	5.7		N/A	N/A	N/A	N/A		9.2	9.2	6.0	5.0		9.5	10.2	5.0	4.9		N/A	N/A	N/A	N/A			10.9	11.5	7.4	7.0	
Bankfull Bank Height Ratio	1.0	1.0	1.0	0.9	ļ	N/A	N/A	N/A	N/A		1.0	1.0	0.8	0.9		1.0	0.9	0.9	0.9		N/A	N/A	N/A	N/A			1.0	1.0	0.8	0.9	
		Cross-Se	ction 21, U	SEC R6 (Poo	)		Cross-Sec	tion 22, US	EC R6 (Riffle	e)		Cross-Se	ction 23, US	EC R6 (Riffle	)		Cross-Sect	tion 24, Ellio	tt Cr (Riffle	)		Cross-S	Section 25, E	Elliott Cr (P	ool)			Cross-Se	ection 26, El	lliott Cr (Ri	ffle)
1	Base	MY1	MY2	MY3		Base	MY1	MY2	MY3		Base	MY1	MY2	MY3		Base	MY1	MY2	MY3		Base	MY1	MY2	MY3			Base	MY1	MY2	MY3	
nension <sup>1</sup> and Substrate					MY4 MY5		(10/2018)			MY4 MY5	(3/2018)				MY4 MY5	(4/2018)	(11/2018)			MY4 MY5			, , ,	(06/2020)	MY4	MY5			(06/2019)		MY4
Bankfull Elevation (ft)	919.8	919.8	919.9	919.8		919.4	919.3	919.4	919.4		917.5	917.6	917.5	917.3		972.1	972.2	972.2	972.2		970.5	970.5	970.6	970.7			970.1	970.1	970.1	970.2	
Low Bank Elevation (ft)	919.8	919.8	919.9	919.8		919.4	919.3	919.4	919.3		917.5	917.6	917.5	917.6		972.1	972.2	972.2	972.3		970.5	970.5	970.6	970.7			970.1	970.1	970.1	970.3	
Bankfull Width (ft)	21.8	22.3	21.9	21.6		18.3	16.3	19.8	18.2		16.7	16.2	16.3	17.1		6.4	7.1	7.9	7.3		7.6	8.9	10.6	9.7			8.2	8.6	8.8	8.5	
Floodprone Width (ft)	N/A	N/A	N/A	N/A		192.7	221.2	83.2	83.2		148.5	130.5	81.6	81.8		19.0	21.6	19.8	17.6		N/A	N/A	N/A	N/A			19.6	18.3	18.2	20.5	
Bankfull Mean Depth (ft)	2.1	1.7	1.9	1.7		1.2	1.2	1.2	1.2		1.1	1.2	1.2	1.3		0.6	0.6	0.5	0.6		1.5	0.9	1.2	1.0			0.7	0.6	0.6	0.8	
Bankfull Max Depth (ft)	5.2	3.8	4.2	3.7		2.2	2.6	2.5	2.7		2.0	2.2	2.5	2.9		0.9	1.0	0.9	1.1		1.9	1.5	2.0	1.5			0.9	0.9	1.1	1.3	
Bankfull Cross-Sectional Area (ft)	45.1	38.4	42.1	36.8		22.4	19.4	22.9	21.5		19.1	20.0	18.8	22.9		4.1	4.1	4.2	4.7		11.2	8.0	12.2	9.4			5.6	5.1	5.0	6.8	
Bankfull Width/Depth Ratio	N/A	N/A	N/A	N/A		14.9	13.7	17.1	15.4		14.6	13.1	14.1	12.7		10.1	12.3	14.9	11.3		N/A	N/A	N/A	N/A			11.9	14.5	15.6	10.6	
Bankfull Entrenchment Ratio <sup>2</sup>	N/A	N/A	N/A	N/A		10.5	13.6	4.2	4.6		8.9	8.1	5.0	4.8		2.9	3.0	2.5	2.4		N/A	N/A	N/A	N/A			2.4	2.1	2.1	2.4	
	N/A	N/A		N/A		1.0	0.9																				1.0				

<sup>1</sup> MYO bankfull dimensions were calculated using a fixed bankfull elevation. Beginning in MY1 Bank Height Ratios are calculated based on the As-built (MY0) cross-sectional area as described in the Standard Measurement of the BHR Monitoring Parameter document provided by NCIRT and NCDMS (2018).
2 Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins.

## Table 12c. Morphology and Hydraulic Summary (Dimensional Parameters - Cross-Section)

Big Harris Creek Mitigation Site DMS Project No. 739

Monitoring Year 3 - 2020

## AREA B

	(	Cross-Sectio	n 27, UT to	Elliott Cr (Ri	ffle)		(	Cross-Sect	ion 28, Brid	ges Cr (Ri	iffle)			Cross-Sect	ion 29, U	SEC UT2 (Ri	iffle)			Cross-Sect	tion 30, US	EC UT3 (Ri	ffle)³			Cross-Se	ction 31, L	JFC R2 (Riff	le)		Cross-Se	ection 32, l	JFC R2 (Poo	ol)	
	Base	MY1	MY2	MY3			Base	MY1	MY2	MY3			Base	MY1	MY2	MY3			Base	MY1	MY2	MY3			Base	MY1	MY2	MY3		Base		MY2	MY3		
Dimension <sup>1</sup> and Substrate	(4/2018)	(11/2018)	(06/2019)	(06/2020)	MY4	MY5	(4/2018)	(11/2018)	(06/2019)	(06/2020)	MY4	MY5	(3/2018)	(10/2018)	(06/2019)	(03/2020)	MY4	MY5	(3/2018)	(10/2018)	(06/2019)	(03/2020)	MY4	MY5	(10/2017)	(10/2018)	(08/2019)	(03/2020)	MY4 MY	(10/2017)	MY1	(08/2019)	(03/2020)	MY4	MY5
Bankfull Elevation (ft)	976.8	976.7	976.7	976.8			966.8	966.7	966.7	966.9			926.9	926.9	927.1	927.5			926.9	926.9	926.9	927.0			969.5	969.5	969.6	969.6		969.1	969.2	969.0	969.0		
Low Bank Elevation (ft)	976.8	976.7	976.7	976.7			966.8	966.7	966.7	966.7			926.9	926.9	927.1	927.4			926.9	926.9	926.9	926.9			969.5	969.5	969.6	969.6		969.1	969.2	969.0	969.0		
Bankfull Width (ft)	5.2	4.9	5.5	5.4			9.3	6.4	6.5	6.6			7.9	8.1	6.7	5.5			7.2	7.4	7.9	7.6			11.4	11.2	11.5	11.6		12.3	13.6	11.8	9.2		
Floodprone Width (ft)	14.0	14.2	13.3	14.3			23.6	21.1	20.4	20.1			25.0	26.0	23.0	43.5			63.8	62.8	45.3	45.2			91.8	91.7	77.7	77.8		N/A	N/A	N/A	N/A		
Bankfull Mean Depth (ft)	0.5	0.5	0.4	0.4			0.4	0.4	0.3	0.3			0.5	0.4	0.3	0.6			0.5	0.5	0.4	0.4			0.7	0.7	0.7	0.7		1.4	1.3	1.0	0.9		
Bankfull Max Depth (ft)	0.8	0.9	0.8	0.9			0.7	0.6	0.6	0.6			0.9	0.9	0.6	1.1			0.8	0.8	0.7	0.8			1.1	1.1	1.1	1.2		2.6	2.7	1.8	1.1		
Bankfull Cross-Sectional Area (ft <sup>2</sup> )	2.5	2.5	2.5	2.2			3.3	2.4	2.2	2.2			3.8	3.5	2.0	3.0			3.7	3.6	3.3	2.9			8.2	7.8	7.9	7.8		17.1	18.0	11.8	7.9		
Bankfull Width/Depth Ratio	10.7	9.7	12.4	13.2			26.5	17.2	19.3	19.8			16.5	18.6	22.5	9.9			14.0	15.5	18.6	19.4			15.7	16.0	16.8	17.2		N/A	N/A	N/A	N/A		
Bankfull Entrenchment Ratio <sup>5</sup>	2.7	2.9	2.4	2.6			2.5	3.3	3.1	3.0			3.2	3.2	3.4	8.0			8.8	8.4	5.8	6.0			8.1	8.2	6.7	6.7		N/A	N/A	N/A	N/A		
Bankfull Bank Height Ratio	1.0	1.0	1.0	0.9			1.0	0.8	0.8	0.8			1.0	1.0	0.7	1.0			1.0	1.0	0.9	0.9			1.0	1.0	1.0	1.0		N/A	N/A	N/A	N/A	1	
		Cross-S	ection 33, U	IFC R2 (Pool)				Cross-Se	ction 34, UF	C R2 (Riff	le)			Cross-Sec	tion 35, L	IFC R2 (Riff	le)³			Cross-Se	ection 36, l	JFC R2 (Po	ol)			Cross-Sec	ction 37, L	FC R1 (Riff	e)²		Cross-Se	ection 38, L	FC R1 (Pool	)3	
	Base	MY1	MY2	MY3			Base	MY1	MY2	MY3			Base	MY1	MY2	MY3			Base	MY1	MY2	MY3			Base	MY1	MY2	MY3		Base		MY2	MY3		
Dimension <sup>1</sup> and Substrate	(10/2017)	(10/2018)	(08/2019)	(03/2020)	MY4	MY5	(10/2017)	(10/2018)	(08/2019)	(03/2020)	MY4	MY5	(10/2017	(10/2018)	(08/2019)	(03/2020)	MY4	MY5	(10/2017)	(10/2018)	(08/2019)	(03/2020)	MY4	MY5	(3/2018)	(10/2018)	(06/2019)	(03/2020)	MY4 MY	(3/2018)	MY1	(06/2019)	(03/2020)	MY4	MY5
Bankfull Elevation (ft)	965.9	966.0	965.9	966.1			965.5	965.5	965.5	965.6			960.5	960.4	960.5	960.5			960.1	960.1	960.1	960.4			919.4	919.3	919.5	919.5		918.9	918.8	919.3	919.4		
Low Bank Elevation (ft)	965.9	966.0	965.9	966.1			965.5	965.5	965.5	965.6			960.5	960.4	960.5	960.5			960.1	960.1	960.1	960.4			919.4	919.3	919.5	919.4		918.9	918.8	919.3	919.4		
Bankfull Width (ft)	13.2	13.4	13.2	14.0			12.0	12.3	12.5	12.1			11.5	11.7	12.6	12.1			14.7	14.2	14.2	15.5			12.3	12.8	13.3	10.4		11.2	10.5	12.4	11.5		
Floodprone Width (ft)	N/A	N/A	N/A	N/A			72.0	69.1	70.6	69.8			99.5	96.4	85.5	85.7			N/A	N/A	N/A	N/A			26.4	25.3	27.3	26.9		N/A	N/A	N/A	N/A		
Bankfull Mean Depth (ft)	1.2	1.2	1.0	1.0			0.8	0.7	0.7	0.7			0.8	0.8	0.7	0.7			1.5	1.3	1.3	1.5			0.8	0.7	1.0	0.9		0.7	0.6	1.0	1.0		
Bankfull Max Depth (ft)	2.3	2.3	1.9	1.8			1.4	1.2	1.4	1.4			1.4	1.4	1.4	1.5			2.8	2.8	2.7	3.1			1.1	1.0	1.3	1.2		1.1	1.0	1.5	1.5		
Bankfull Cross-Sectional Area (ft <sup>2</sup> )	16.1	15.7	13.2	13.3			9.2	8.1	8.3	8.5			9.5	9.4	9.1	8.8			21.5	18.5	17.7	22.7			9.7	9.6	12.8	9.3		7.7	6.5	12.4	11.3		
Bankfull Width/Depth Ratio	N/A	N/A	N/A	N/A			15.6	18.7	18.9	17.1			14.0	14.7	17.3	16.7			N/A	N/A	N/A	N/A			15.7	17.1	13.8	11.7		N/A	N/A	N/A	N/A		
Bankfull Entrenchment Ratio⁵	N/A	N/A	N/A	N/A			6.0	5.6	5.6	5.8			8.6	8.2	6.8	7.1			N/A	N/A	N/A	N/A			2.1	2.0	2.1	2.6		N/A	N/A	N/A	N/A		
Bankfull Bank Height Ratio	N/A	N/A	N/A	N/A			1.0	0.9	1.0	1.0			1.0	1.0	1.0	1.0			N/A	N/A	N/A	N/A			1.0	1.0	1.2	1.0		N/A	N/A	N/A	N/A		1
	,		ction 39. LF	C R2 (Riffle)					ection 40, LF		ol)																								
	Paca						Pasa		MV2	MV2																									

Dalikiuli Dalik Heigili Natio	IN/A	IN/A	IV/A	IN/A			1.0	0.5	1.0	1.0		
		Cross-Se	ction 39, LF	C R2 (Riffle	e) <sup>4</sup>			Cross-Se	ction 40, L	.FC R2 (Poo	1)	
	Base	MY1	MY2	MY3			Base	MY1	MY2	MY3		
Dimension <sup>1</sup> and Substrate	(3/2018)	(10/2018)	(06/2019)	(03/2020)	MY4	MY5	(3/2018)	(10/2018)	(06/2019)	(03/2020)	MY4	MY5
Bankfull Elevation (ft)	915.9	915.9	915.9	916.0			916.0	915.9	915.9	915.9		
Low Bank Elevation (ft)	915.9	915.9	915.9	916.1			916.0	915.9	915.9	915.9		
Bankfull Width (ft)	9.9	9.8	9.1	10.1			11.5	10.9	10.4	10.0		
Floodprone Width (ft)	28.4	28.6	29.6	30.5			N/A	N/A	N/A	N/A		
Bankfull Mean Depth (ft)	0.6	0.5	0.6	0.8			1.0	0.9	1.2	1.2		
Bankfull Max Depth (ft)	0.8	0.9	1.2	1.1			1.5	1.3	1.8	1.6		
Bankfull Cross-Sectional Area (ft <sup>2</sup> )	6.3	4.6	5.9	7.6			11.8	9.6	12.1	11.9		
Bankfull Width/Depth Ratio	15.4	20.5	14.2	13.4			N/A	N/A	N/A	N/A		
Bankfull Entrenchment Ratio <sup>5</sup>	2.9	2.9	3.2	3.0			N/A	N/A	N/A	N/A		
Bankfull Bank Height Ratio	1.0	0.8	1.0	1.1			N/A	N/A	N/A	N/A		

## AREA C

		Cross-Sec	tion 41, LB	HC R1A (Po	ol)			Cross-Sect	ion 42, LBH	IC R1A (Rif	fle)³		(	Cross-Sectio	on 43, LBH0	C R1B/2 (Ri	ffle)²			Cross-Secti	on 44, LBH	IC R1B/2 (F	ool)	
	Base	MY1	MY2	MY3			Base	MY1	MY2	MY3			Base	MY1	MY2	MY3			Base	MY1	MY2	MY3		
Dimension <sup>1</sup> and Substrate	(9/2017)	(10/2018)	(08/2019)	(05/2020)	MY4	MY5	(9/2017)	(10/2018)	(08/2019)	(05/2020)	MY4	MY5	(9/2017)	(10/2018)	(08/2019)	(05/2020)	MY4	MY5	(9/2017)	(10/2018)	(08/2019)	(05/2020)	MY4	MY5
Bankfull Elevation (ft)	848.0	847.5	847.9	848.2			847.6	847.5	847.8	848.0			844.2	844.2	844.2	843.6			843.5	843.7	843.5	842.9		
Low Bank Elevation (ft)	848.0	847.5	847.9	848.2			847.6	847.5	847.8	848.3			844.2	844.2	844.2	844.2			843.5	843.7	843.5	842.9		
Bankfull Width (ft)	41.6	24.0	24.7	24.6			26.2	25.7	28.3	30.7			26.7	27.2	29.4	30.4			26.8	27.2	30.8	22.8		
Floodprone Width (ft)	N/A	N/A	N/A	N/A			158.0	155.7	77.9	78.0			299.6	171.0	84.9	84.9			N/A	N/A	N/A	N/A		
Bankfull Mean Depth (ft)	2.5	1.4	1.7	2.0			1.9	1.5	1.7	1.8			1.7	1.9	2.1	2.0			2.8	3.3	2.4	2.5		
Bankfull Max Depth (ft)	5.8	2.6	3.2	3.7			3.0	2.9	3.3	3.6			2.8	3.3	3.6	3.5			5.5	7.8	4.2	3.7		
Bankfull Cross-Sectional Area (ft <sup>2</sup> )	104.7	33.5	42.8	50.2			49.4	38.7	49.3	55.6			46.0	51.5	60.8	62.1			75.4	91.0	75.2	57.7		
Bankfull Width/Depth Ratio	N/A	N/A	N/A	N/A			13.9	17.1	16.2	16.9			15.5	14.3	14.2	14.9			N/A	N/A	N/A	N/A		
Bankfull Entrenchment Ratio <sup>5</sup>	N/A	N/A	N/A	N/A			6.0	6.1	2.8	2.5			11.2	6.3	2.9	2.8			N/A	N/A	N/A	N/A		
Bankfull Bank Height Ratio	N/A	N/A	N/A	N/A			1.0	0.9	1.0	1.1			1.0	1.1	1.2	1.2			N/A	N/A	N/A	N/A		

<sup>1</sup> MYO bankfull dimensions were calculated using a fixed bankfull elevation. Beginning in MY1 Bank Height Ratios are calculated based on the As-built (MY0) cross-sectional area as described in the Standard Measurement of the BHR Monitoring Parameter document provided by NCIRT and NCDMS (2018).

<sup>&</sup>lt;sup>2</sup> The floodprone width and entrenchment ratio at cross-section 37 and 43 were miscalculated during MY0. Both measurements were updated in MY1.

<sup>&</sup>lt;sup>3</sup> The bankfull (low bank) elevations were recorded incorrectly at cross-section 30, 35, 38, and 42 during MYO; therefore, subsequent cross-sectional data calculations were incorrect. MYO data was updated in MY1.

 $<sup>^4</sup>$  The Floodprone width for Cross-section 39 was incorrectly recorded MYO and was updated in MY1.

<sup>5</sup> Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins

Table 13a. Monitoring Data - Stream Reach Data Summary

UBHC R2A (STA. 129+81 - 136+66)

UBHC R2A (STA. 129+81 - 136+66)												
Parameter	As-Built/Ba	aseline 2018	MY1	2018	MY2	2019	MY	3 2020	MY4	2021	MY5	2022
	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Dimension and Substrate <sup>3</sup>												
Bankfull Width (ft)		6.0	10	).4	13	3.4	1	0.4				
Floodprone Width (ft)		8.7	104		89			9.2				
Bankfull Mean Depth		).7	0.	.6	0	.6		0.8				
Bankfull Max Depth		5	1.		1			2.0				
Bankfull Cross-Sectional Area (ft2)		1.6	6.		8			3.3				
Width/Depth Ratio		2.0	16		21			3.1				
Entrenchment Ratio <sup>1</sup>		5.8	1		6			3.6				
Bank Height Ratio <sup>2</sup>		0	0.		0			).9				
D50 (mm)	4	4.2	30	).6	52	4	!	9.9				
Profile												
Riffle Length (ft)		40										
Riffle Slope (ft/ft)		0.052										
Pool Length (ft)	10	59										
Pool Max Depth (ft)		3.3										
Pool Spacing (ft)		75										
Pool Volume (ft <sup>3</sup> )												
Pattern												
Channel Beltwidth (ft)		31										
Radius of Curvature (ft)	18	26										
Rc:Bankfull Width (ft/ft)		1.6										
Meander Wave Length (ft)		102										
Meander Width Ratio	0.8	1.9										
Additional Reach Parameters												
Rosgen Classification		C4										
Channel Thalweg Length (ft)		85										
Sinuosity (ft)	1.	.14							_			
Water Surface Slope (ft/ft) <sup>4</sup>							0.	011				
Bankfull Slope (ft/ft)		015										
Ri%/Ru%/P%/G%/S%												
SC%/Sa%/G%/C%/B%/Be%												
d16/d35/d50/d84/d95/d100		6.6/79.2/146.										
		362										
% of Reach with Eroding Banks		)%	3'	%	1	%		0%				

<sup>(---):</sup> Data was not provided

<sup>&</sup>lt;sup>1</sup> Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins.

<sup>&</sup>lt;sup>2</sup> Bank Height Ratio is the bank height divided by the max depth of the bankfull channel.

<sup>&</sup>lt;sup>3</sup> Starting in MY2, bankfull elevation is calculated using a fixed Abkf as described in the Standard Measurement of the BHR Monitoring Parameter provided by NCIRT and NCDMS (2018).

<sup>&</sup>lt;sup>4</sup>Water surface slopes are based on abbreviated longitudinal profiles of one meander length collected during MY3 after geomorphically significant events.

## Table 13b. Monitoring Data - Stream Reach Data Summary

Big Harris Creek Mitigation Site DMS Project No. 739 Monitoring Year 3 - 2020

UBHC R2B (STA. 136+66 - 139+15)

Min	MY1 2018	MY2 2019	MY3 2020	MY4 2021	MY5 2022
Bankfull Width (ft)	Min Max				
Floodprone Width (ft)					
Bankfull Max Depth   3.0	18.2	13.8	18.9		
Bankfull Max Depth   3.0	118.6	63.4	67.5		
Bankfull Cross-Sectional Area (ft2)	2.4	1.3	2.3		
Width/Depth Ratio	4.2	2.4	4.0		
Entrenchment Ratio	44.1	18.4	44.0		
Bank Height Ratio	7.5	10.4	8.1		
Profile	6.5	4.6	3.6		
Profile           Riffle Length (ft)         8         39           Riffle Slope (ft/ft)         0.022         0.063           Pool Length (ft)         10         47           Pool Max Depth (ft)         2.6         3.4           Pool Spacing (ft)         21         79           Pool Volume (ft³)         21         79           Pattern           Channel Beltwidth (ft)         20         35           Radius of Curvature (ft)         30         34           Rc:Bankfull Width (ft/ft)         2.7         3.0           Meander Wave Length (ft)         108         125           Meander Width Ratio         1.8         3.1           Additional Reach Parameters           Rosgen Classification         C4           Channel Thalweg Length (ft)         249           Sinuosity (ft)         1.14           Water Surface Slope (ft/ft)            Bankfull Slope (ft/ft)         0.015           Ri%/Ru%/P%/G%/S%            SC%/Sa%/G%/C%/B%/Be%            0.66/2.37/16.6/79.2/146.	1.8	1.0	1.8		
Riffle Length (ft)   8   39     Riffle Slope (ft/ft)   0.022   0.063     Pool Length (ft)   10   47     Pool Max Depth (ft)   2.6   3.4     Pool Spacing (ft)   21   79     Pool Volume (ft³)     Pattern	1.4	0.8	1.6		
Riffle Slope (ft/ft)       0.022       0.063         Pool Length (ft)       10       47         Pool Max Depth (ft)       2.6       3.4         Pool Spacing (ft)       21       79         Pool Volume (ft³)         Pattern         Channel Beltwidth (ft)       20       35         Radius of Curvature (ft)       30       34         Rc:Bankfull Width (ft/ft)       2.7       3.0         Meander Wave Length (ft)       108       125         Meander Width Ratio       1.8       3.1         Additional Reach Parameters         Rosgen Classification       C4         Channel Thalweg Length (ft)       249         Sinuosity (ft)       1.14         Water Surface Slope (ft/ft)          Bankfull Slope (ft/ft)       0.015         Ri%/Ru%/P%/G%/S%          SC%/Sa%/G%/C%/B%/Be%          0.66/2.37/16.6/79.2/146.					
Pool Length (ft)   10					
Pool Max Depth (ft)   2.6   3.4     Pool Spacing (ft)   21   79     Pool Volume (ft³)     Pattern					
Pool Spacing (ft)   21   79					
Pool Volume (ft³)  Pattern  Channel Beltwidth (ft) 20 35  Radius of Curvature (ft) 30 34  Rc:Bankfull Width (ft/ft) 2.7 3.0  Meander Wave Length (ft) 108 125  Meander Width Ratio 1.8 3.1  Additional Reach Parameters  Rosgen Classification C4  Channel Thalweg Length (ft) 249  Sinuosity (ft) 1.14  Water Surface Slope (ft/ft)  Bankfull Slope (ft/ft) 0.015  Ri%/Ru%/P%/G%/S%  SC%/Sa%/G%/C%/B%/Be%  SC%/Sa%/G%/C%/B%/Be% 0.66/2.37/16.6/79.2/146.					
Pattern           Channel Beltwidth (ft)         20         35           Radius of Curvature (ft)         30         34           Rc:Bankfull Width (ft/ft)         2.7         3.0           Meander Wave Length (ft)         108         125           Meander Width Ratio         1.8         3.1           Additional Reach Parameters         Rosgen Classification         C4           Channel Thalweg Length (ft)         249           Sinuosity (ft)         1.14           Water Surface Slope (ft/ft)            Bankfull Slope (ft/ft)         0.015           Ri%/Ru%/P%/G%/S%            SC%/Sa%/G%/C%/B%/Be%            416 (435 (435 (450 (480 (485 (430 (480 (440 (480 (480 (480 (480 (480 (48					
Channel Beltwidth (ft) 20 35  Radius of Curvature (ft) 30 34  Rc:Bankfull Width (ft/ft) 2.7 3.0  Meander Wave Length (ft) 108 125  Meander Width Ratio 1.8 3.1  Additional Reach Parameters  Rosgen Classification C4  Channel Thalweg Length (ft) 249  Sinuosity (ft) 1.14  Water Surface Slope (ft/ft)  Bankfull Slope (ft/ft) 0.015  Ri%/Ru%/P%/G%/S%  SC%/Sa%/G%/C%/B%/Be%  SC%/Sa%/G%/C%/B%/Be% 0.66/2.37/16.6/79.2/146.					
Radius of Curvature (ft)   30   34     Rc:Bankfull Width (ft/ft)   2.7   3.0     Meander Wave Length (ft)   108   125     Meander Width Ratio   1.8   3.1     Additional Reach Parameters   Rosgen Classification   C4     Channel Thalweg Length (ft)   249     Sinuosity (ft)   1.14     Water Surface Slope (ft/ft)       Bankfull Slope (ft/ft)   0.015     Ri%/Ru%/P%/G%/S%       SC%/Sa%/G%/C%/B%/Be%       0.66/2.37/16.6/79.2/146.					
Rc:Bankfull Width (ft/ft)   2.7   3.0     Meander Wave Length (ft)   108   125     Meander Width Ratio   1.8   3.1     Additional Reach Parameters     Rosgen Classification   C4     Channel Thalweg Length (ft)   249     Sinuosity (ft)   1.14     Water Surface Slope (ft/ft)       Bankfull Slope (ft/ft)   0.015     Ri%/Ru%/P%/G%/S%       SC%/Sa%/G%/C%/B%/Be%       416/435/450/450/450/64105 (4100   0.66/2.37/16.6/79.2/146.					
Meander Wave Length (ft)         108         125           Meander Width Ratio         1.8         3.1           Additional Reach Parameters           Rosgen Classification         C4           Channel Thalweg Length (ft)         249           Sinuosity (ft)         1.14           Water Surface Slope (ft/ft)            Bankfull Slope (ft/ft)         0.015           Ri%/Ru%/P%/G%/S%            SC%/Sa%/G%/C%/B%/Be%            416 (435 (435 (450 (484 (495 (4100)					
Meander Width Ratio         1.8         3.1           Additional Reach Parameters         Rosgen Classification         C4           Channel Thalweg Length (ft)         249           Sinuosity (ft)         1.14           Water Surface Slope (ft/ft)            Bankfull Slope (ft/ft)         0.015           Ri%/Ru%/P%/G%/S%            SC%/Sa%/G%/C%/B%/Be%            416 (435 (435 (435 (435 (435 (435 (435 (435					
Additional Reach Parameters  Rosgen Classification C4 Channel Thalweg Length (ft) 249 Sinuosity (ft) 1.14 Water Surface Slope (ft/ft) Bankfull Slope (ft/ft) 0.015 Ri%/Ru%/P%/G%/S% SC%/Sa%/G%/C%/B%/Be%  \$15 (135 (135 (135 (135 (135 (135 (135 (1					
Rosgen Classification C4 Channel Thalweg Length (ft) 249 Sinuosity (ft) 1.14 Water Surface Slope (ft/ft) Bankfull Slope (ft/ft) 0.015 Ri%/Ru%/P%/G%/S% SC%/Sa%/G%/C%/B%/Be% 0.66/2.37/16.6/79.2/146.					
Channel Thalweg Length (ft) 249  Sinuosity (ft) 1.14  Water Surface Slope (ft/ft)  Bankfull Slope (ft/ft) 0.015  Ri%/Ru%/P%/G%/S%  SC%/Sa%/G%/C%/B%/Be%  0.66/2.37/16.6/79.2/146.					
Sinuosity (ft) 1.14  Water Surface Slope (ft/ft)  Bankfull Slope (ft/ft) 0.015  Ri%/Ru%/P%/G%/S%  SC%/Sa%/G%/C%/B%/Be%  0.66/2.37/16.6/79.2/146.					
Water Surface Slope (ft/ft)  Bankfull Slope (ft/ft) 0.015  Ri%/Ru%/P%/G%/S%  SC%/Sa%/G%/C%/B%/Be%  0.66/2.37/16.6/79.2/146.					
Bankfull Slope (ft/ft) 0.015 Ri%/Ru%/P%/G%/S% SC%/Sa%/G%/C%/B%/Be% 0.66/2.37/16.6/79.2/146.					
Ri%/Ru%/P%/G%/S% SC%/Sa%/G%/C%/B%/Be% 0.66/2.37/16.6/79.2/146.					
SC%/Sa%/G%/C%/B%/Be% 0.66/2.37/16.6/79.2/146.					
0.66/2.37/16.6/79.2/146.					
0.10/032/020/084/095/01001					
7/362					
% of Reach with Eroding Banks 0%	14%	3%	7%		

<sup>(---):</sup> Data was not provided

<sup>&</sup>lt;sup>1</sup> Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins.

 $<sup>^{2}\,\</sup>mathrm{Bank}$  Height Ratio is the bank height divided by the max depth of the bankfull channel.

<sup>&</sup>lt;sup>3</sup> Starting in MY2, bankfull elevation is calculated using a fixed Abkf as described in the Standard Measurement of the BHR Monitoring Parameter provided by NCIRT and NCDMS (2018).

Table 13c. Monitoring Data - Stream Reach Data Summary

UBHC R4 (STA. 148+76 - 159+15)

UBHC R4 (STA. 148+76 - 159+15)												
Parameter	As-Built/Ba	seline 2018	MY1	2018	MY2	2019	MY3	2020	MY4	2021	MY5	2022
	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Dimension and Substrate <sup>3</sup>												
Bankfull Width (ft)	15.5	16.0	15.7	16.2	14.9	15.4	14.9	16.2				
Floodprone Width (ft)	118.0	190.0	110.8	167.4	119.2	137.2	121.7	137.3				
Bankfull Mean Depth	0.8	1.1	0.6	0.9	0.8	1.1	0.8	1.1				
Bankfull Max Depth	1.4	2.0	1.3	2.0	1.5	2.0	1.6	2.3				
Bankfull Cross-Sectional Area (ft2)	13.1	17.6	10.5	14.7	12.0	17.7	12.1	17.1				
Width/Depth Ratio	14.5	18.3	16.6	25.1	13.4	18.4	15.3	18.5				
Entrenchment Ratio <sup>1</sup>	7.6	11.9	6.8	10.7	8.0	8.9	8.1	8.5				
Bank Height Ratio <sup>2</sup>	1.0	1.0	0.9	0.9	1.0	1.0	1.0	1.0				
D50 (mm)	46.2	85.6	26.9	32	50.6	69.7	43.6	75.2				
Profile												
Riffle Length (ft)	19	56										
Riffle Slope (ft/ft)	0.012	0.052										
Pool Length (ft)	33	73										
Pool Max Depth (ft)	2.4	3.8										
Pool Spacing (ft)	62	125										
Pool Volume (ft <sup>3</sup> )												
Pattern												
Channel Beltwidth (ft)	19	67										
Radius of Curvature (ft)	27	60										
Rc:Bankfull Width (ft/ft)	1.7	3.8										
Meander Wave Length (ft)	122	178										
Meander Width Ratio	1.2	4.2										
Additional Reach Parameters												
Rosgen Classification	(	24										
Channel Thalweg Length (ft)	1,3	296										
Sinuosity (ft)	1.	36										
Water Surface Slope (ft/ft)	-											
Bankfull Slope (ft/ft)	0.0	013										
Ri%/Ru%/P%/G%/S%	-											
SC%/Sa%/G%/C%/B%/Be%	-											
d16/d35/d50/d84/d95/d100	0.3/6.69	/29.8/87/										
u10/u35/u50/u84/d95/d100	202.	4/512										
% of Reach with Eroding Banks	0	%	5	%	0	%	2	.%				

<sup>(---):</sup> Data was not provided

<sup>&</sup>lt;sup>1</sup> Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins.

 $<sup>^{2}\,\</sup>mathrm{Bank}$  Height Ratio is the bank height divided by the max depth of the bankfull channel.

<sup>&</sup>lt;sup>3</sup> Starting in MY2, bankfull elevation is calculated using a fixed Abkf as described in the Standard Measurement of the BHR Monitoring Parameter provided by NCIRT and NCDMS (2018).

Table 13d. Monitoring Data - Stream Reach Data Summary

Royster Creek R1 (STA. 802+54 - 807+13)

Parameter	As-Built/Ba	aseline 2018	MY1	2018	MY2	2019	MY3	2020	MY4	2021	MY!	5 2022
	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Dimension and Substrate <sup>3</sup>	•			<u>'</u>			<u>'</u>	•	•	•		
Bankfull Width (ft)	10	0.0	g	9.4	8	.3	4	.1				
Floodprone Width (ft)	4	6.7	4	6.1	39	).5	39	9.6				
Bankfull Mean Depth	C	).4	(	).4	0	.2	0	.2				
Bankfull Max Depth	C	0.8	(	0.8	0	.4	0	.4				
Bankfull Cross-Sectional Area (ft2)	3	3.6	3	3.7	1	.8	1	.0				
Width/Depth Ratio	2	7.6	2	4.1	39	0.0	16	5.7				
Entrenchment Ratio <sup>1</sup>	4	l.7	4	1.9	4	.8	9	.6				
Bank Height Ratio <sup>2</sup>	1	0	1	L.O	0	.7	0	.5				
D50 (mm)	4:	3.5	3	5.4	44	.4	1	.0				
Profile												
Riffle Length (ft)		42										
Riffle Slope (ft/ft)	0.007	0.057										
Pool Length (ft)	7	71										
Pool Max Depth (ft)		2.5										
Pool Spacing (ft)	38	70										
Pool Volume (ft <sup>3</sup> )												
Pattern												
Channel Beltwidth (ft)		18										
Radius of Curvature (ft)	21	41										
Rc:Bankfull Width (ft/ft)	2.1	4.1										
Meander Wave Length (ft)	95	125										
Meander Width Ratio	0.9	1.8										
Additional Reach Parameters												
Rosgen Classification		/C4										
Channel Thalweg Length (ft)	4	59										
Sinuosity (ft)		.05										
Water Surface Slope (ft/ft)	-											
Bankfull Slope (ft/ft)	0.0	040										
Ri%/Ru%/P%/G%/S%	-											
SC%/Sa%/G%/C%/B%/Be%	-											
d16/d35/d50/d84/d95/d100	SC/2/11/71	7/98.3/256										
% of Reach with Eroding Banks	C	)%	(	)%	0	%	C	%				
					1							

<sup>(---):</sup> Data was not provided

<sup>&</sup>lt;sup>1</sup> Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins.

 $<sup>^{2}\,\</sup>mathrm{Bank}$  Height Ratio is the bank height divided by the max depth of the bankfull channel.

<sup>&</sup>lt;sup>3</sup> Starting in MY2, bankfull elevation is calculated using a fixed Abkf as described in the Standard Measurement of the BHR Monitoring Parameter provided by NCIRT and NCDMS (2018).

Table 13e. Monitoring Data - Stream Reach Data Summary

Scott Creek (STA. 1210+12 - 1216+74)

Parameter	As-Built/Ba	seline 2018	MY1	2018	MY2	2019	MY3	2020	MY4	2021	MY5	2022
	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Dimension and Substrate <sup>3</sup>												
Bankfull Width (ft)	6	5.8	8	3.7	13	3.6	1	3.6				
Floodprone Width (ft)	6	7.1	4-	4.8	45	5.2	4	4.5				
Bankfull Mean Depth	C	).5	C	).6	1	.3	1	2				
Bankfull Max Depth	C	).9	1	L.2	2	.2	2	1				
Bankfull Cross-Sectional Area (ft2)	3	3.6	53	5.1	18	3.1	1	6.2				
Width/Depth Ratio	1	2.7	1.	5.0	10	).2	1	1.4				
Entrenchment Ratio <sup>1</sup>	g	).9	5	5.1	3	.3	3	3.3				
Bank Height Ratio <sup>2</sup>	1	0	1	1.2	2	.6	2	1.5				
D50 (mm)	5	1.6	3	3.3	49	9.5	3	8.7				
Profile												
Riffle Length (ft)	22	47										
Riffle Slope (ft/ft)	0.016	0.042										
Pool Length (ft)	6	138										
Pool Max Depth (ft)	1.9	5.2										
Pool Spacing (ft)	17	69										
Pool Volume (ft <sup>3</sup> )												
Pattern												
Channel Beltwidth (ft)	25	45										
Radius of Curvature (ft)	11	28										
Rc:Bankfull Width (ft/ft)	1.6	4.1										
Meander Wave Length (ft)	30	59										
Meander Width Ratio	3.7	6.6										
Additional Reach Parameters												
Rosgen Classification		/C4										
Channel Thalweg Length (ft)	6	44										
Sinuosity (ft)	1.	.10										
Water Surface Slope (ft/ft) <sup>4</sup>							0.	041				
Bankfull Slope (ft/ft)	0.0	038										
Ri%/Ru%/P%/G%/S%	-											
SC%/Sa%/G%/C%/B%/Be%	-											
d16/d35/d50/d84/d95/d100		.23/39.8/ 50.7/512										
% of Reach with Eroding Banks		)%	4	1%	2	%	1	.%				
					1		II.		1		II.	

<sup>(---):</sup> Data was not provided

<sup>&</sup>lt;sup>1</sup> Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins.

<sup>&</sup>lt;sup>2</sup> Bank Height Ratio is the bank height divided by the max depth of the bankfull channel.

<sup>&</sup>lt;sup>3</sup> Starting in MY2, bankfull elevation is calculated using a fixed Abkf as described in the Standard Measurement of the BHR Monitoring Parameter provided by NCIRT and NCDMS (2018).

<sup>&</sup>lt;sup>4</sup>Water surface slopes are based on abbreviated longitudinal profiles of one meander length collected during MY3 after geomorphically significant events.

Table 13f. Monitoring Data - Stream Reach Data Summary

### Carroll Creek (STA. 1301+68 - 1307+63)

Parameter	As-Built/Ba	aseline 2018			MY2	2019	MY3	2020	MY4	2021	MY5	2022
	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Dimension and Substrate <sup>3</sup>												
Bankfull Width (ft)	1	1.4	11	L.3	8.	6	7	.0				
Floodprone Width (ft)	8	2.0	82	2.1	71	.2	7:	9.2				
Bankfull Mean Depth	C	).7	0	.6	0.6		C	.7				
Bankfull Max Depth	1	3	1	.2	1.1		1	.2				
Bankfull Cross-Sectional Area (ft2)	7	'.9	7.	.0	4.9		4	.7				
Width/Depth Ratio	1	6.4	18	18.2		.0	10.3					
Entrenchment Ratio <sup>1</sup>	7	'.2	7.	.3	8.3		1:	L.3				
Bank Height Ratio <sup>2</sup>	1	0	0	.9	0.	8	C	.7				
D50 (mm)	Ξ,	51	41	L.3	42.6		36.0					
Profile												
Riffle Length (ft)	14	65										
Riffle Slope (ft/ft)	0.008	0.036										
Pool Length (ft)	18	50										
Pool Max Depth (ft)	1.9	2.8										
Pool Spacing (ft)	45	67										
Pool Volume (ft <sup>3</sup> )												
Pattern												
Channel Beltwidth (ft)	26	45										
Radius of Curvature (ft)	15	29										
Rc:Bankfull Width (ft/ft)	1.3	2.5										
Meander Wave Length (ft)	89	139										
Meander Width Ratio	2.2	3.9										
Additional Reach Parameters												
Rosgen Classification	(	C4										
Channel Thalweg Length (ft)	5	90										
Sinuosity (ft)	1	.15										
Water Surface Slope (ft/ft)												
Bankfull Slope (ft/ft)	0.	017										
Ri%/Ru%/P%/G%/S%												
SC%/Sa%/G%/C%/B%/Be%												
44.6./43.6./46.4./10.6./14.00	0.28/2/1	.0.2/59.6/										
d16/d35/d50/d84/d95/d100	101.	2/180										
% of Reach with Eroding Banks	(	)%	0	%	09	%	C	%				
(): Data was not provided							•		•			

<sup>(---):</sup> Data was not provided

<sup>&</sup>lt;sup>1</sup> Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins.

 $<sup>^{2}\,\</sup>mathrm{Bank}$  Height Ratio is the bank height divided by the max depth of the bankfull channel.

<sup>&</sup>lt;sup>3</sup> Starting in MY2, bankfull elevation is calculated using a fixed Abkf as described in the Standard Measurement of the BHR Monitoring Parameter provided by NCIRT and NCDMS (2018).

## Table 13g. Monitoring Data - Stream Reach Data Summary

Big Harris Creek Mitigation Site DMS Project No. 739 Monitoring Year 3 - 2020

USEC R1	(STA.	1002+89 -	1006+98)	

Bankfull Width (ft)   6.7   7.7   7.8   6.3	Parameter	As-Built/Ba	aseline 2018			MY2	2019	MY3	2020	MY4	2021	MY5	2022
Bankfull Width (ft)   6.7   7.7   7.8   6.3		Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Bankfull Width (ft)   6.7   7.7   7.8   6.3	Dimension and Substrate <sup>3</sup>												
Bankfull Mean Depth		6	5.7	7	.7	7.	8	6	.3				
Bankfull Max Depth 0.9 0.9 1.0 1.0 1.0 Bankfull Consectional Area (f2) 4.7 4.8 4.7 3.6 Bankfull Consectional Area (f2) 4.7 4.8 4.7 3.6 Bankfull Consectional Area (f2) 4.7 4.8 4.7 3.6 Bank Height Ratio' 5.5 4.8 4.6 5.7 Bank Height Ratio' 1.0 1.0 1.0 0.9 Bank Height Ratio' 1.0 1.0 1.0 0.9 Bank Height Ratio' 1.0 1.0 1.0 0.9 Bank Height Ratio' 1.0 32.0 36.5 33.6 64.0 Bank Height Ratio' 1.0 1.0 1.0 0.9 Bank Height Ratio' 1.0 1.0 1.0 0.9 Bank Height Ratio' 1.0 1.0 1.0 0.9 Bank Height Ratio 1.0 1.0 1.0 1.0 1.0 1.0 Bank Height Ratio 1.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0	Floodprone Width (ft)	3	7.2	37	7.0	35	.8	3!	5.8				
Bankfull Cross-Sectional Area (ft2)	Bankfull Mean Depth	C	).7	0	.6	0.			.6				
Width/Depth Ratio   9.6   12.3   12.7   11.2	Bankfull Max Depth	C	).9	0	.9	1.0		1	.0				
Entrenchment Ratio 5.5 4.8 4.6 5.7	Bankfull Cross-Sectional Area (ft2)	4	l.7	4	.8			3	.6				
Bank Height Ratio	Width/Depth Ratio	S	0.6	12.3		12.7		11.2					
Profile  Riffle Length (ft) 6 18 Riffle Slope (ft/ft) 0.003 0.132 Pool Length (ft) 4 56 Pool Max Depth (ft) 1.7 2.2 Pool Spacing (ft) 22 102 Pool Volume (ft³)  Pattern  Channel Beltwidth (ft) Radius of Curvature (ft) Re:Bankfull Width (ft/ft) Meander Wave Length (ft) Meander Width Ratio Meander Width Ratio Meander Width Ratio Sogen Classification E4 Channel Thalweg Length (ft) 409 Sinuosity (ft) 1.00 Water Surface Slope (ft/ft²) Bankfull Slope (ft/ft²) Bankfull Slope (ft/ft²) SCS/Sa%/G%/C%/B%/Be% SCS/Sa%/G%/C%/B&/G%/Be%/G%/C%/B&/G%/Be%/G%/Be%/G%/Be%/G%/Be%/G%/G%/Be%/G%/Be%/G%/G%/G%/Be%/G%/G%/G%/G%/G%/G%/G%/G%/G%/G%/G%/G%/G%	Entrenchment Ratio <sup>1</sup>	5	5.5	4	.8	4.6		5	.7				
Profile  Riffle Length (ft) 6 18 Riffle Slope (ft/ft) 0.003 0.132 Pool Length (ft) 4 56 Pool Max Depth (ft) 1.7 2.2 Pool Spacing (ft) 22 102 Pool Volume (ft) Pattern  Channel Beltwidth (ft) Radius of Curvature (ft) Meander Width Ratio Meander Width Ratio Meander Width Ratio Meander Width Ratio Mander Width Ratio Mander Bespecial Classification E4 Channel Thalweg Length (ft) 409 Sinuosity (ft) 1.00 Water Surface Slope (ft/ft) Bankfull Slope (ft/ft) Bankfull Slope (ft/ft) 0.084 Ri%/Ru%/P%/G%/5% SCS/Sa%/G%/C%/B%/Be% SCS/Sa%/G%/C%/Sa%/G%/C%/B%/Be% SCS/Sa%/G%/C%/B%/Be% SCS/Sa%/G%/C%/B%/Be% SCS/Sa%/G%/C%/B&/Sa%/G%/SA%/Be% SCS/Sa%/G%/C%/SA%/Be% SCS/Sa%/G%/SA%/G%/SA%/Be% SCS/Sa%/G%/SA%/G%/SA%/BA	Bank Height Ratio <sup>2</sup>	1	0	1	.0	1.	0	0	.9				
Riffle Length (ft) 6 18 Riffle Slope (ft/ft) 0.003 0.132 Pool Length (ft) 4 56 Pool Max Depth (ft) 1.7 2.2 Pool Spacing (ft) 22 102 Pool Volume (ft <sup>3</sup> )  Pattern  Channel Beltwidth (ft) Radius of Curvature (ft) Re:Bankfull Width (ft/ft) Meander Wave Length (ft) Meander Width Ratio  Additional Reach Parameters  Rosgen Classification E4 Channel Thalweg Length (ft) 409 Sinuosity (ft) 409 Sinuosity (ft) 0.084 Ri%/Ru%/P%/G%/5% SC%/Sa%/G%/C%/B%/8e% SC%/Sa%/G%/C%/B%/Be% SC%/Sa%/G%/C%/B%/Be% SC%/Sa%/G%/C%/B%/Be% SC%/Sa%/G%/C%/B%/B6% SC%/Sa%/G%/C%/B%/Be% SC%/Sa%/G%/C%/B%/Be%/G%/SA%/C%/B%/Be%/G%/SA%/C%/SA%/G%/SA%/C%/SA%/G%/SA%/C%/B%/G%/SA%/G%/G%/SA%/G%/SA%/G%/SA%/G%/SA%/G%/G%/SA%/G%/SA%/G%/SA%/G%/G%/SA%/G%/SA%/G%/SA%/G	D50 (mm)	3	2.0	36	6.5	33	.6	64	1.0				
Riffle Slope (ft/ft) 0.003 0.132 Pool Length (ft) 4 556 Pool Max Depth (ft) 1.7 2.2 Pool Spacing (ft) 22 102 Pool Volume (ft²)  Pattern  Channel Beltwidth (ft) Radius of Curvature (ft) Rc:Bankfull Width (ft/ft) Meander Wave Length (ft) Meander Width Ratio Additional Reach Parameters  Rosgen Classification E4 Channel Thalweg Length (ft) 409 Sinuosity (ft) 1.00  Water Surface Slope (ft/ft) Bankfull Slope (ft/ft) 0.084 Ri%/Ru%/P%/G%/S% SC%/Sa%/G%/C%/B%/Be% GSC3.15/20.7(68.5/ 137/256	Profile												
Pool Length (ft)   4   56     Pool Max Depth (ft)   1.7   2.2     Pool Spacing (ft)   22   102     Pool Volume (ft <sup>3</sup> )   Poll Volu	Riffle Length (ft)	6	18										
Pool Max Depth (ft) 1.7 2.2 Pool Spacing (ft) 22 102 Pool Volume (ft³)  Pattern  Channel Beltwidth (ft) Radius of Curvature (ft) Re:Bankfull Width (ft/ft) Meander Wave Length (ft) Meander Width Ratio Meander Width Ratio Additional Reach Parameters  Rosgen Classification E4 Channel Thalweg Length (ft) 409 Sinuosity (ft) 1.00 Water Surface Slope (ft/ft) Bankfull Slope (ft/ft) 0.084 Ri%/Rv%/P%/G%/S% SC%/Sa%/G%/C%/B%/Be% SC%/Sa%/G%/C%/B%/Be%  SC3.15/20.7/68.5/ 137/256	Riffle Slope (ft/ft)	0.003	0.132										
Pool Spacing (ft) 22 102 Pool Volume (ft <sup>3</sup> )  Pattern  Channel Beltwidth (ft) Radius of Curvature (ft) Rc:Bankfull Width (ft/ft) Meander Wave Length (ft) Meander Wave Length (ft) Meander Width Ratio Additional Reach Parameters  Rosgen Classification E4 Channel Thalweg Length (ft) 409 Sinuosity (ft) 1.00  Water Surface Slope (ft/ft) Bankfull Slope (ft/ft) 0.084 Ri%/Rv%/P%/G%/S% SC%/Sa%/G%/C%/B%/Be% SC%/Sa%/G%/C%/B%/Be% SC%/Sa%/G%/C%/B%/Be% SC/3.15/20.7/68.5/ 137/256	Pool Length (ft)	4	56										
Pattern  Channel Beltwidth (ft) Radius of Curvature (ft) Re:Bankfull Width (ft/ft) Meander Wave Length (ft) Meander Width Ratio Meander Width Ratio Additional Reach Parameters  Rosgen Classification E4 Channel Thalweg Length (ft) 409 Sinuosity (ft) 1.00 Water Surface Slope (ft/ft) Bankfull Slope (ft/ft) 0.084 Ri%/Ru%/P%/G%/S% SC%/Sa%/G%/C%/B%/Be% SC%/Sa%/G%/C%/B%/Be% SC%/Sa%/G%/C%/B%/Be% SC/3.15/20.7/68.5/ 137/256	Pool Max Depth (ft)	1.7	2.2										
Pattern  Channel Beltwidth (ft)	Pool Spacing (ft)	22	102										
Pattern  Channel Beltwidth (ft)	Pool Volume (ft <sup>3</sup> )												
Radius of Curvature (ft) Rc:Bankfull Width (ft/ft) Meander Wave Length (ft) Meander Width Ratio Meander Width Ratio  Additional Reach Parameters  Rosgen Classification E4 Channel Thalweg Length (ft) 409 Sinuosity (ft) 1.00  Water Surface Slope (ft/ft) Bankfull Slope (ft/ft) 0.084 Ri%/Ru%/P%/G%/S% SC%/Sa%/G%/C%/B%/Be% SC%/Sa%/G%/C%/B%/Be%  SC%/Sa%/G%/C%/B%/Be%  d16/d35/d50/d84/d95/d100  SC/3.15/20.7/68.5/ 137/256	Pattern												
Rc:Bankfull Width (ft/ft) Meander Wave Length (ft) Meander Width Ratio Meander Width Ratio  Additional Reach Parameters  Rosgen Classification E4 Channel Thalweg Length (ft) 409 Sinuosity (ft) 1.00  Water Surface Slope (ft/ft) 0.015  Bankfull Slope (ft/ft) 0.084  Ri%/Ru%/P%/G%/S% SC%/Sa%/G%/C%/B%/Be% SC%/Sa%/G%/C%/B%/Be% SC%/Sa%/G%/C%/B%/Be%  d16/d35/d50/d84/d95/d100  SC/3.15/20.7/68.5/ 137/256	Channel Beltwidth (ft)												
Meander Wave Length (ft)         Meander Width Ratio         Additional Reach Parameters       Rosgen Classification     E4        Channel Thalweg Length (ft)     409       Sinuosity (ft)     1.00       Water Surface Slope (ft/ft) <sup>4</sup> 0.015       Bankfull Slope (ft/ft)     0.084       Ri%/Ru%/P%/G%/S%         SC%/Sa%/G%/C%/B%/Be%         416/d35/d50/d84/d95/d100     SC/3.15/20.7/68.5/ 137/256	Radius of Curvature (ft)												
Meander Width Ratio	Rc:Bankfull Width (ft/ft)												
Additional Reach Parameters  Rosgen Classification	Meander Wave Length (ft)												
Rosgen Classification   E4	Meander Width Ratio												
Channel Thalweg Length (ft) 409  Sinuosity (ft) 1.00  Water Surface Slope (ft/ft) <sup>4</sup> Bankfull Slope (ft/ft) 0.084  Ri%/Ru%/P%/G%/S%  SC%/Sa%/G%/C%/B%/Be%  d16/d35/d50/d84/d95/d100  Channel Thalweg Length (ft) 409  0.015  0.015  SC%/Sa%/G%/C%/B%/Be%  SC%/Sa%/G%/C%/B%/Be%  SC/3.15/20.7/68.5/ 137/256	Additional Reach Parameters												
Sinuosity (ft) 1.00  Water Surface Slope (ft/ft) <sup>4</sup> Bankfull Slope (ft/ft) 0.084  Ri%/Ru%/P%/G%/S%  SC%/Sa%/G%/C%/B%/Be%  d16/d35/d50/d84/d95/d100 SC/3.15/20.7/68.5/ 137/256	Rosgen Classification	E	4										
Water Surface Slope (ft/ft) Bankfull Slope (ft/ft) 0.084 Ri%/Ru%/P%/G%/S% SC%/Sa%/G%/C%/B%/Be% d16/d35/d50/d84/d95/d100 SC/3.15/20.7/68.5/ 137/256	Channel Thalweg Length (ft)	4	09										
Bankfull Slope (ft/ft) 0.084  Ri%/Ru%/P%/G%/S%  SC%/Sa%/G%/C%/B%/Be%  d16/d35/d50/d84/d95/d100 SC/3.15/20.7/68.5/ 137/256	Sinuosity (ft)	1.	.00										
Bankfull Slope (ft/ft) 0.084  Ri%/Ru%/P%/G%/S%  SC%/Sa%/G%/C%/B%/Be%  d16/d35/d50/d84/d95/d100 SC/3.15/20.7/68.5/ 137/256	Water Surface Slope (ft/ft) <sup>4</sup>	-						0.0	)15				
SC%/Sa%/G%/C%/B%/Be% d16/d35/d50/d84/d95/d100 SC/3.15/20.7/68.5/ 137/256		0.0	084										
d16/d35/d50/d84/d95/d100 SC/3.15/20.7/68.5/ 137/256	Ri%/Ru%/P%/G%/S%	-											
d16/d35/d50/d84/d95/d100 137/256	SC%/Sa%/G%/C%/B%/Be%												
137/230	44.6./43.6./46.4./10.6./14.0.0	SC/3.15/2	20.7/68.5/										
% of Reach with Eroding Banks 0% 8% 4% 7%	a16/a35/a50/a84/d95/d100	137	/256										
	% of Reach with Eroding Banks	C	)%	8	%	49	%	7	%				

<sup>(---):</sup> Data was not provided

<sup>&</sup>lt;sup>1</sup> Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins.

 $<sup>^{2}\,\</sup>mathrm{Bank}$  Height Ratio is the bank height divided by the max depth of the bankfull channel.

<sup>&</sup>lt;sup>3</sup> Starting in MY2, bankfull elevation is calculated using a fixed Abkf as described in the Standard Measurement of the BHR Monitoring Parameter provided by NCIRT and NCDMS (2018).

<sup>&</sup>lt;sup>4</sup>Water surface slopes are based on abbreviated longitudinal profiles of one meander length collected during MY3 after geomorphically significant events.

## Table 13h. Monitoring Data - Stream Reach Data Summary

Big Harris Creek Mitigation Site DMS Project No. 739 **Monitoring Year 3 - 2020** 

USEC R5 (STA. 1043+77 - 1058+84)

USEC R5 (STA. 1043+77 - 1058+84)												
Parameter	As-Built/B	aseline 2018	MY1	2018	MY2	2019	MY3	2020	MY4	2021	MY5	2022
	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Dimension and Substrate <sup>3</sup>												
Bankfull Width (ft)	15.9	18.4	16.4	18.3	14.6	17.2	15.4	18.6				
Floodprone Width (ft)	169.2	173.2	166.3	191.0	86.0	108.0	86.0	108.1				
Bankfull Mean Depth	1.0	1.2	1.0	1.1	0.9	1.0	0.8	0.9				
Bankfull Max Depth	1.7	1.8	1.5	1.8	1.6	1.8	1.7	1.9				
Bankfull Cross-Sectional Area (ft2)	18.9	19.2	16.1	18.4	13.9	17.5	14.5	17.5				
Width/Depth Ratio	13.3	17.8	15.1	18.1	15.2	17.5	16.4	21.2				
Entrenchment Ratio <sup>1</sup>	9.2	10.9	9.2	11.5	5.0	7.4	4.9	7.0				
Bank Height Ratio <sup>2</sup>	1.0	1.0	0.8	1.0	0.8	0.9	0.9	0.9				
D50 (mm)	35.0	39.8	32.0	35.3	30.4	43.1	24.7	56.9				
Profile												
Riffle Length (ft)	39	74										
Riffle Slope (ft/ft)	0.007	0.022										
Pool Length (ft)	15	67										
Pool Max Depth (ft)	1.9	4.1										
Pool Spacing (ft)	48	128										
Pool Volume (ft <sup>3</sup> )												
Pattern												
Channel Beltwidth (ft)	37	64										
Radius of Curvature (ft)	25	48										
Rc:Bankfull Width (ft/ft)	1.6	2.6										
Meander Wave Length (ft)	128	200										
Meander Width Ratio	2.3	3.5										
Additional Reach Parameters												
Rosgen Classification		C4										
Channel Thalweg Length (ft)	1,	228										
Sinuosity (ft)	1	.23										
Water Surface Slope (ft/ft)												
Bankfull Slope (ft/ft)	0.	008										
Ri%/Ru%/P%/G%/S%												
SC%/Sa%/G%/C%/B%/Be%												
41 C (42 F /4 F O /4 O A /4 O F /4 A O O	0.15/2.18	3/23.6/64/										
d16/d35/d50/d84/d95/d100	103	.6/10										
% of Reach with Eroding Banks	(	0%	1	L%	0	%	C	1%				

<sup>(---):</sup> Data was not provided

<sup>&</sup>lt;sup>1</sup> Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins.

 $<sup>^{2}\,\</sup>mathrm{Bank}$  Height Ratio is the bank height divided by the max depth of the bankfull channel.

<sup>&</sup>lt;sup>3</sup> Starting in MY2, bankfull elevation is calculated using a fixed Abkf as described in the Standard Measurement of the BHR Monitoring Parameter provided by NCIRT and NCDMS (2018).

Table 13i. Monitoring Data - Stream Reach Data Summary

USEC R6 (STA. 1059+14 - 1069+83)

USEC R6 (STA. 1059+14 - 1069+83)				****		****						
Parameter		aseline 2018		2018		2019		2020		2021		2022
_	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Dimension and Substrate <sup>3</sup>												
Bankfull Width (ft)		18.3	16.2	16.3	16.3	19.8	17.1	18.2				
Floodprone Width (ft)	148.5	192.7	130.5	221.2	81.6	83.2	81.8	83.2				
Bankfull Mean Depth		1.2	1.2	1.2	1.2	1.2	1.2	1.3				
Bankfull Max Depth		2.2	2.2	2.6	2.5	2.5	2.7	2.9				
Bankfull Cross-Sectional Area (ft)	19.1	22.4	19.4	20.0	18.8	22.9	21.5	22.9				
Width/Depth Ratio		14.9	13.1	13.7	14.1	17.1	12.7	15.4				
Entrenchment Ratio <sup>1</sup>	8.9	10.5	8.1	13.6	4.2	5.0	4.6	4.8				
Bank Height Ratio <sup>2</sup>	1.0	1.0	0.9	1.0	1.0	1.0	1.0	1.1				
D50 (mm)	41.1	46.1	26.9	34	27.3	50.9	42.9	44.2				
Profile												
Riffle Length (ft)	13	80										
Riffle Slope (ft/ft)	0.004	0.065										
Pool Length (ft)	14	79										
Pool Max Depth (ft)		4.6										
Pool Spacing (ft)	43	127										
Pool Volume (ft <sup>3</sup> )												
Pattern												
Channel Beltwidth (ft)	27	57										
Radius of Curvature (ft)	24	39										
Rc:Bankfull Width (ft/ft)	1.4	2.2										
Meander Wave Length (ft)	160	193										
Meander Width Ratio	1.6	3.1										
Additional Reach Parameters												
Rosgen Classification	(	C4										
Channel Thalweg Length (ft)	1,	070										
Sinuosity (ft)	1.	.13										
Water Surface Slope (ft/ft)	-											
Bankfull Slope (ft/ft)	0.0	009										
Ri%/Ru%/P%/G%/S%	-											
SC%/Sa%/G%/C%/B%/Be%	-											
	SC/0.61/	3.3/60.4/										
d16/d35/d50/d84/d95/d100	113.	8/180										
% of Reach with Eroding Banks	C	)%	4	%	1	%	(	)%				

<sup>(---):</sup> Data was not provided

<sup>&</sup>lt;sup>1</sup> Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins.

 $<sup>^{2}\,\</sup>mathrm{Bank}$  Height Ratio is the bank height divided by the max depth of the bankfull channel.

<sup>&</sup>lt;sup>3</sup> Starting in MY2, bankfull elevation is calculated using a fixed Abkf as described in the Standard Measurement of the BHR Monitoring Parameter provided by NCIRT and NCDMS (2018).

Table 13j. Monitoring Data - Stream Reach Data Summary

Elliott Creek (STA. 1400+85 - 1412+06)

Elliott Creek (STA. 1400+85 - 1412+06)												
Parameter	As-Built/Ba	aseline 2018	MY1	2018	MY2	2019	MY3	2020	MY4	2021	MY5	2022
	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Dimension and Substrate <sup>3</sup>												
Bankfull Width (ft)	6.4	8.2	7.1	8.6	7.9	8.8	7.3	8.5				
Floodprone Width (ft)	19.0	19.6	18.3	21.6	18.2	19.8	17.6	20.5				
Bankfull Mean Depth	0.6	0.7	0.6	0.6	0.5	0.6	0.6	0.8				
Bankfull Max Depth	0.9	0.9	0.9	1.0	0.9	1.1	1.1	1.3				
Bankfull Cross-Sectional Area (ft)	4.1	5.6	4.1	5.1	4.2	5.0	4.7	6.8				
Width/Depth Ratio	10.1	11.9	12.3	14.5	14.9	15.6	10.6	11.3				
Entrenchment Ratio <sup>1</sup>	2.4	2.9	2.1	3.0	2.1	2.5	2.4	2.4				
Bank Height Ratio <sup>2</sup>	1.0	1.0	1.0	1.0	0.9	1.0	1.1	1.2				
D50 (mm)	32.0	41.7	23.9	49.1	46.9	75.9	11.0	14.1				
Profile												
Riffle Length (ft)	7	64										
Riffle Slope (ft/ft)	0.008	0.071										
Pool Length (ft)	11	73										
Pool Max Depth (ft)	1.1	2.3										
Pool Spacing (ft)		132										
Pool Volume (ft <sup>3</sup> )												
Pattern												
Channel Beltwidth (ft)	14	38										
Radius of Curvature (ft)	8	42										
Rc:Bankfull Width (ft/ft)	1.3	5.1										
Meander Wave Length (ft)	46	156										
Meander Width Ratio	2.2	4.6										
Additional Reach Parameters												
Rosgen Classification		/E4										
Channel Thalweg Length (ft)		121										
Sinuosity (ft)	1	.13										
Water Surface Slope (ft/ft) <sup>4</sup>							0.0	007				
Bankfull Slope (ft/ft)	0.	015										
Ri%/Ru%/P%/G%/S%	•											
SC%/Sa%/G%/C%/B%/Be%	•											
d16/d35/d50/d84/d95/d100		8/6/101.2/ 8/180										
% of Reach with Eroding Banks		)%	2	2%	0	%	2	!%				

<sup>(---):</sup> Data was not provided

<sup>&</sup>lt;sup>1</sup> Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins.

 $<sup>^{2}\,\</sup>mathrm{Bank}$  Height Ratio is the bank height divided by the max depth of the bankfull channel.

<sup>&</sup>lt;sup>3</sup> Starting in MY2, bankfull elevation is calculated using a fixed Abkf as described in the Standard Measurement of the BHR Monitoring Parameter provided by NCIRT and NCDMS (2018).

<sup>&</sup>lt;sup>4</sup>Water surface slopes are based on abbreviated longitudinal profiles of one meander length collected during MY3 after geomorphically significant events.

Table 13k. Monitoring Data - Stream Reach Data Summary

#### Elliott Creek UT1 (STA. 1415+87 - 1417+28)

Parameter	As-Built/Ba	aseline 2018	MY1	2018	MY2	2019	MY3	2020	MY4	2021	MY5	2022
	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Dimension and Substrate <sup>3</sup>												
Bankfull Width (ft)	5	5.2	4.	.9	5	5	5	.4				
Floodprone Width (ft)	1	4.0	14	.2	13	.3		1.3				
Bankfull Mean Depth	C	).5	0.	.5	0	4	C	.4				
Bankfull Max Depth	C	0.8	0.	.9	0.8		C	.9				
Bankfull Cross-Sectional Area (ft)		1.5	2.		2.5			.2				
Width/Depth Ratio	10	0.7	9.	.7	12	.4	13.2					
Entrenchment Ratio <sup>1</sup>	2	2.7	2.	.9	2.4		2.6					
Bank Height Ratio <sup>2</sup>	1	0	1.	.0	1	0	C	.9				
D50 (mm)	3	1.0	36	5.8	26.4		3.1					
Profile												
Riffle Length (ft)		21										
Riffle Slope (ft/ft)	0.002	0.043										
Pool Length (ft)	12	18										
Pool Max Depth (ft)		1.4										
Pool Spacing (ft)	18	45										
Pool Volume (ft <sup>3</sup> )												
Pattern												
Channel Beltwidth (ft)		17										
Radius of Curvature (ft)		20										
Rc:Bankfull Width (ft/ft)		3.8										
Meander Wave Length (ft)		69										
Meander Width Ratio	1.4	3.3										
Additional Reach Parameters												
Rosgen Classification		/E4										
Channel Thalweg Length (ft)		41										
Sinuosity (ft)		.07										
Water Surface Slope (ft/ft) <sup>4</sup>							0.0	025				
Bankfull Slope (ft/ft)		025										
Ri%/Ru%/P%/G%/S%	-											
SC%/Sa%/G%/C%/B%/Be%	-											
d16/d35/d50/d84/d95/d100	SC/1/5.9/4	7/101.2/180										
% of Reach with Eroding Banks	C	)%	09	%	0	%	C	%				
/ \ Data was not provided			070		0,0		0,0		•			

<sup>(---):</sup> Data was not provided

<sup>&</sup>lt;sup>1</sup> Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins.

<sup>&</sup>lt;sup>2</sup> Bank Height Ratio is the bank height divided by the max depth of the bankfull channel.

<sup>&</sup>lt;sup>3</sup> Starting in MY2, bankfull elevation is calculated using a fixed Abkf as described in the Standard Measurement of the BHR Monitoring Parameter provided by NCIRT and NCDMS (2018).

<sup>&</sup>lt;sup>4</sup>Water surface slopes are based on abbreviated longitudinal profiles of one meander length collected during MY3 after geomorphically significant events.

Table 13I. Monitoring Data - Stream Reach Data Summary

Bridges Creek R1 (STA. 1500+91 - 1504+67)

Parameter	As-Built/Ba	seline 2018	MY1	2018	MY2	2019	MY3	2020	MY4	2021	MY5	2022
	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Dimension and Substrate <sup>3</sup>												
Bankfull Width (ft)	9	.3	6	.4	6	.5	6	5.6				
Floodprone Width (ft)	2:	3.6	21	l.1	20	).4	20	0.1				
Bankfull Mean Depth	0	0.4	0	.4	0	.3	C	).3				
Bankfull Max Depth	0	1.7	0	.6	0	.6	C	0.6				
Bankfull Cross-Sectional Area (ft)	3	.3	2	.4	2.2		2	2				
Width/Depth Ratio	20	6.5	17	7.2	19	9.3	19	9.8				
Entrenchment Ratio <sup>1</sup>	2	5	3	.3	3	.1	3	3.0				
Bank Height Ratio <sup>2</sup>	1	0	0	.8	0	.8	C	).8				
D50 (mm)	53	3.7	29	9.0	44	1.2	1	3.9				
Profile												
Riffle Length (ft)		32										
Riffle Slope (ft/ft)	0.013	0.058										
Pool Length (ft)	6	34										
Pool Max Depth (ft)	1.6	2.4										
Pool Spacing (ft)	29	49										
Pool Volume (ft <sup>3</sup> )												
Pattern												
Channel Beltwidth (ft)	9	15										
Radius of Curvature (ft)	10	19										
Rc:Bankfull Width (ft/ft)	1.1	2.0										
Meander Wave Length (ft)	68	80										
Meander Width Ratio	1.0	1.6										
Additional Reach Parameters												
Rosgen Classification		C5										
Channel Thalweg Length (ft)		76										
Sinuosity (ft)	1.	.00							_			
Water Surface Slope (ft/ft) <sup>4</sup>							0.0	023				
Bankfull Slope (ft/ft)	0.0	031										
Ri%/Ru%/P%/G%/S%	-											
SC%/Sa%/G%/C%/B%/Be%	-											
d16/d35/d50/d84/d95/d100	SC/0.16/1/9	0/135.5/180										
% of Reach with Eroding Banks	C	1%	0	%	0	%	C	)%				

<sup>(---):</sup> Data was not provided

<sup>&</sup>lt;sup>1</sup> Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins.

<sup>&</sup>lt;sup>2</sup> Bank Height Ratio is the bank height divided by the max depth of the bankfull channel.

<sup>&</sup>lt;sup>3</sup> Starting in MY2, bankfull elevation is calculated using a fixed Abkf as described in the Standard Measurement of the BHR Monitoring Parameter provided by NCIRT and NCDMS (2018).

<sup>&</sup>lt;sup>4</sup>Water surface slopes are based on abbreviated longitudinal profiles of one meander length collected during MY3 after geomorphically significant events.

## Table 13m. Monitoring Data - Stream Reach Data Summary

Big Harris Creek Mitigation Site DMS Project No. 739 **Monitoring Year 3 - 2020** 

USEC UT2 (STA. 1080+00 - 1081+54)

USEC UT2 (STA. 1080+00 - 1081+54)												
Parameter	As-Built/B	aseline 2018	MY1 2	018	MY2	2019	MY3	2020	MY4	2021	MY5	2022
	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Dimension and Substrate <sup>3</sup>												
Bankfull Width (ft)	7	7.9	8.1	_	6.	7	5	.5				
Floodprone Width (ft)	2	5.0	26.0	0	23	.0	4:	3.5				,
Bankfull Mean Depth	(	).5	0.4		0.	3	C	.6				
Bankfull Max Depth	(	).9	0.9	)	0.	6	1	.1				
Bankfull Cross-Sectional Area (ft)	3	3.8	3.5	)	2.	0	3	.0				
Width/Depth Ratio	1	6.5	18.6	6	22	.5	9	.9				
Entrenchment Ratio <sup>1</sup>	3	3.2	3.2	2	3.	4	8	.0				
Bank Height Ratio <sup>2</sup>	1	1.0	1.0	)	0.	7		1				
D50 (mm)	1	4.9	0.5	)	1.	3	C	.7				
Profile												
Riffle Length (ft)	14	37										
Riffle Slope (ft/ft)	0.007	0.017										
Pool Length (ft)	19	51										
Pool Max Depth (ft)	1.0	1.7										
Pool Spacing (ft)	62	62										
Pool Volume (ft <sup>3</sup> )												
Pattern												
Channel Beltwidth (ft)	24	24										
Radius of Curvature (ft)	20	17										
Rc:Bankfull Width (ft/ft)	2.5	2.2										
Meander Wave Length (ft)	54	54										
Meander Width Ratio	3.1	3.1										
Additional Reach Parameters												
Rosgen Classification	(	C5										
Channel Thalweg Length (ft)	1	54										
Sinuosity (ft)		.41										
Water Surface Slope (ft/ft)												
Bankfull Slope (ft/ft)	0.	010										
Ri%/Ru%/P%/G%/S%												
SC%/Sa%/G%/C%/B%/Be%												
d16/d35/d50/d84/d95/d100												
% of Reach with Eroding Banks	(	)%	0%		09	%	C	%				

<sup>(---):</sup> Data was not provided

<sup>&</sup>lt;sup>1</sup> Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins.

 $<sup>^{2}\,\</sup>mathrm{Bank}$  Height Ratio is the bank height divided by the max depth of the bankfull channel.

<sup>&</sup>lt;sup>3</sup> Starting in MY2, bankfull elevation is calculated using a fixed Abkf as described in the Standard Measurement of the BHR Monitoring Parameter provided by NCIRT and NCDMS (2018).

## Table 13n. Monitoring Data - Stream Reach Data Summary

Big Harris Creek Mitigation Site DMS Project No. 739 **Monitoring Year 3 - 2020** 

USEC UT3 (STA. 1082+00 - 1083+18)

USEC UT3 (STA. 1082+00 - 1083+18)							
Parameter	As-Built/Ba	aseline 2018	MY1 2018	MY2 2019	MY3 2020	MY4 2021	MY5 2022
	Min	Max	Min Max	Min Max	Min Max	Min Max	Min Max
Dimension and Substrate <sup>3</sup>							
Bankfull Width (ft)	7	7.2	7.4	7.9	7.6		
Floodprone Width (ft)		3.8	62.8	45.3	45.2		
Bankfull Mean Depth	C	).5	0.5	0.4	0.4		
Bankfull Max Depth		).8	0.8	0.7	0.8		
Bankfull Cross-Sectional Area (ft)	3	3.7	3.6	3.3	2.9		
Width/Depth Ratio		4.0	15.5	18.6	19.4		
Entrenchment Ratio <sup>1</sup>	8	3.8	8.4	5.8	6.0		
Bank Height Ratio <sup>2</sup>		1.0	1.0	0.9	0.9		
D50 (mm)	1	4.4	18.9	S/C	19.6		
Profile							
Riffle Length (ft)		19					
Riffle Slope (ft/ft)		0.026					
Pool Length (ft)		14					
Pool Max Depth (ft)		1.7					
Pool Spacing (ft)		34					
Pool Volume (ft <sup>3</sup> )							
Pattern	,						
Channel Beltwidth (ft)		16					
Radius of Curvature (ft)		12					
Rc:Bankfull Width (ft/ft)		1.0					
Meander Wave Length (ft)		32					
Meander Width Ratio	1.3	1.3					
Additional Reach Parameters	1						
Rosgen Classification		C5					
Channel Thalweg Length (ft)		18					
Sinuosity (ft)		.28					
Water Surface Slope (ft/ft)							
Bankfull Slope (ft/ft)		011					
Ri%/Ru%/P%/G%/S%							
SC%/Sa%/G%/C%/B%/Be%							
d16/d35/d50/d84/d95/d100							
% of Reach with Eroding Banks	(	0%	0%	0%	0%		

<sup>(---):</sup> Data was not provide

<sup>&</sup>lt;sup>1</sup> Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins.

 $<sup>^{2}\,\</sup>mathrm{Bank}$  Height Ratio is the bank height divided by the max depth of the bankfull channel.

<sup>&</sup>lt;sup>3</sup> Starting in MY2, bankfull elevation is calculated using a fixed Abkf as described in the Standard Measurement of the BHR Monitoring Parameter provided by NCIRT and NCDMS (2018).

## Table 13o. Monitoring Data - Stream Reach Data Summary

Big Harris Creek Mitigation Site DMS Project No. 739 **Monitoring Year 3 - 2020** 

UFC R2 (STA. 1616+02 - 1630+09)

UFC R2 (STA. 1616+02 - 1630+09)												
Parameter	As-Built/B	aseline 2018	MY1	2018	MY2	2019	MY3	2020	MY4	2021	MY5	2022
	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Dimension and Substrate <sup>3</sup>												
Bankfull Width (ft)	11.4	12.0	11.2	12.3	11.5	12.6	11.6	12.1				
Floodprone Width (ft)	72.0	99.5	69.1	96.4	70.2	85.5	69.8	85.7				
Bankfull Mean Depth	0.7	0.8	0.7	0.8	0.7	0.7	0.7	0.7				
Bankfull Max Depth	1.1	1.4	1.1	1.4	1.1	1.4	1.2	1.5				
Bankfull Cross-Sectional Area (ft)	8.2	9.5	7.8	9.4	7.9	9.1	7.8	8.8				
Width/Depth Ratio	14.0	15.7	14.7	18.7	16.8	18.9	16.7	17.2				
Entrenchment Ratio <sup>1</sup>	6.0	8.6	5.6	8.2	5.6	6.8	5.8	7.1				
Bank Height Ratio <sup>2</sup>	1.0	1.0	0.9	1.0	1.0	1.0	1.0	1.0				
D50 (mm)	39.1	54.8	33.4	39.5	39.5	58.3	37.1	67.0				
Profile												
Riffle Length (ft)	16	69										
Riffle Slope (ft/ft)	0.008	0.063										
Pool Length (ft)	14	63										
Pool Max Depth (ft)	2.5	4.5										
Pool Spacing (ft)	45	162										
Pool Volume (ft <sup>3</sup> )												
Pattern												
Channel Beltwidth (ft)	8	71										
Radius of Curvature (ft)	23	50										
Rc:Bankfull Width (ft/ft)	2.0	3.8										
Meander Wave Length (ft)	92	195										
Meander Width Ratio	0.7	5.4										
Additional Reach Parameters												
Rosgen Classification	(	C4										
Channel Thalweg Length (ft)	1,	407										
Sinuosity (ft)	1	.20										
Water Surface Slope (ft/ft)												
Bankfull Slope (ft/ft)	0.	013										
Ri%/Ru%/P%/G%/S%												
SC%/Sa%/G%/C%/B%/Be%												
41 C (42 F /4 F O /4 O A /4 O F /4 A O O	SC/0.63/	10.4/55.9/										
d16/d35/d50/d84/d95/d100	104	/180										
% of Reach with Eroding Banks	(	)%	1	L%	0	%	C	)%				

<sup>(---):</sup> Data was not provided

<sup>&</sup>lt;sup>1</sup> Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins.

 $<sup>^{2}\,\</sup>mathrm{Bank}$  Height Ratio is the bank height divided by the max depth of the bankfull channel.

<sup>&</sup>lt;sup>3</sup> Starting in MY2, bankfull elevation is calculated using a fixed Abkf as described in the Standard Measurement of the BHR Monitoring Parameter provided by NCIRT and NCDMS (2018).

## Table 13p. Monitoring Data - Stream Reach Data Summary

Big Harris Creek Mitigation Site DMS Project No. 739 **Monitoring Year 3 - 2020** 

LFC R1 (STA. 1641+28 - 1647+02)

LFC R1 (STA. 1641+28 - 1647+02)												
Parameter	As-Built/Ba	seline 2018	MY1 2	018	MY2	2019	MY3	2020	MY4	2021	MY5	2022
	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Dimension and Substrate <sup>3</sup>												
Bankfull Width (ft)		2.3	12.8	8	13	.3	10	0.4				
Floodprone Width (ft)		5.4	25.3	3	27	.3	26	5.9				
Bankfull Mean Depth	C	.8	0.7		1.	0	0	.9				
Bankfull Max Depth		1	1.0		1.		1	.2				
Bankfull Cross-Sectional Area (ft)		.7	9.6		12		9	.3				
Width/Depth Ratio		5.7	17.3		13			1.7				
Entrenchment Ratio <sup>1</sup>		.1	2.0		2.		2	.6				
Bank Height Ratio <sup>2</sup>		0	1.0	1	1.			1				
D50 (mm)	3.	5.3	10.4	4	50	.6	32	2.7				
Profile												
Riffle Length (ft)		55										
Riffle Slope (ft/ft)		0.047										
Pool Length (ft)		44										
Pool Max Depth (ft)		1.6										
Pool Spacing (ft)		92										
Pool Volume (ft <sup>3</sup> )												
Pattern												
Channel Beltwidth (ft)	20	73										
Radius of Curvature (ft)	12	50										
Rc:Bankfull Width (ft/ft)	1.0	4.1										
Meander Wave Length (ft)		138										
Meander Width Ratio	1.6	5.9										
Additional Reach Parameters												
Rosgen Classification		25										
Channel Thalweg Length (ft)		74										
Sinuosity (ft)		.07										
Water Surface Slope (ft/ft)												
Bankfull Slope (ft/ft)		009										
Ri%/Ru%/P%/G%/S%												
SC%/Sa%/G%/C%/B%/Be%		/4.0/57.0/										
d16/d35/d50/d84/d95/d100	110.	/1.8/57.9/ 1/180										
% of Reach with Eroding Banks		)%	0%	1	09	6	0	%				

<sup>(---):</sup> Data was not provided

<sup>&</sup>lt;sup>1</sup> Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins.

 $<sup>^{2}\,\</sup>mathrm{Bank}$  Height Ratio is the bank height divided by the max depth of the bankfull channel.

<sup>&</sup>lt;sup>3</sup> Starting in MY2, bankfull elevation is calculated using a fixed Abkf as described in the Standard Measurement of the BHR Monitoring Parameter provided by NCIRT and NCDMS (2018).

## Table 13q. Monitoring Data - Stream Reach Data Summary

Big Harris Creek Mitigation Site DMS Project No. 739 **Monitoring Year 3 - 2020** 

LFC R2 (STA. 1647+33 - 1651+60)

Parameter	As-Built/Baseline 2018		MY1	2018	MY2 2019		MY3 2020		MY4 2021		MY5 2022	
	Min	Max	Min Max		Min Max		Min Max		Min Max		Min Max	
Dimension and Substrate <sup>3</sup>												
Bankfull Width (ft)	9	9.9		9.8		9.1		10.1				
Floodprone Width (ft)		8.4	28.6		29.6		30.5					
Bankfull Mean Depth	C	).6	0.5		0.6		0.8					
Bankfull Max Depth	(	).8	0.9		1.2		1.1					
Bankfull Cross-Sectional Area (ft)	6	5.3	4.6		5.9		7.6					
Width/Depth Ratio	1	5.4	20.5		14.2		13.4					
Entrenchment Ratio <sup>1</sup>	2	2.9	2	.9	3.2		3.0					
Bank Height Ratio <sup>2</sup>	1	1.0	0	.8	1.	0	1.1					
D50 (mm)	1	1.0	8	.4	43.9		40.2					
Profile												
Riffle Length (ft)		36										
Riffle Slope (ft/ft)	0.005	0.040										
Pool Length (ft)	18	53										
Pool Max Depth (ft)	1.8	2.2										
Pool Spacing (ft)	42	90										
Pool Volume (ft <sup>3</sup> )												
Pattern												
Channel Beltwidth (ft)	4	14										
Radius of Curvature (ft)	53	79										
Rc:Bankfull Width (ft/ft)	5.4	8.0										
Meander Wave Length (ft)	201	201										
Meander Width Ratio	4.4	0.0										
Additional Reach Parameters												
Rosgen Classification		C4										
Channel Thalweg Length (ft)		27										
Sinuosity (ft)		.00										
Water Surface Slope (ft/ft)	-											
Bankfull Slope (ft/ft)		016										
Ri%/Ru%/P%/G%/S%												
SC%/Sa%/G%/C%/B%/Be%												
d16/d35/d50/d84/d95/d100	0.27/0.69/4.4/40.5/ 128.7/362											
% of Reach with Eroding Banks	(	)%	4	%	2'	%	0	%				

<sup>(---):</sup> Data was not provided

<sup>&</sup>lt;sup>1</sup> Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins.

 $<sup>^{2}\,\</sup>mathrm{Bank}$  Height Ratio is the bank height divided by the max depth of the bankfull channel.

<sup>&</sup>lt;sup>3</sup> Starting in MY2, bankfull elevation is calculated using a fixed Abkf as described in the Standard Measurement of the BHR Monitoring Parameter provided by NCIRT and NCDMS (2018).

Table 13r. Monitoring Data - Stream Reach Data Summary

Big Harris Creek Mitigation Site

DMS Project No. 739

Monitoring Year 3 - 2020

LBHC R1a (STA. 300+13 - 305+13)

Parameter	As-Built/Baseline 2018		MY1	2018	MY2	MY2 2019		MY3 2020		MY4 2021		MY5 2022	
	Min	Max	Min Max		Min	Max	Min	Max	Min	Max	Min	Max	
Dimension and Substrate <sup>3</sup>													
Bankfull Width (ft)	2	6.2	25.7		28.3		30.7						
Floodprone Width (ft)	1!	58.0	155.7		77	77.9		78.0					
Bankfull Mean Depth		1.9	1.5		1.7		1.8						
Bankfull Max Depth	***	3.0	2.9		3.3		3.6						
Bankfull Cross-Sectional Area (ft)	4	9.4	38.7		49	49.3		55.6					
Width/Depth Ratio	1	3.9	17.1		16.2		16.9						
Entrenchment Ratio <sup>1</sup>	(	5.0	6	.1	2.	2.8		.5					
Bank Height Ratio <sup>2</sup>		1.0	0	.9	1.	.0	1	1.1					
D50 (mm)	3	2.0	20	0.3	51	51.2		9.6					
Profile													
Riffle Length (ft)	15	142											
Riffle Slope (ft/ft)	0.005	0.079											
Pool Length (ft)	54	94											
Pool Max Depth (ft)	3.9	6.2											
Pool Spacing (ft)	116	218											
Pool Volume (ft <sup>3</sup> )													
Pattern													
Channel Beltwidth (ft)	58	105											
Radius of Curvature (ft)	60	80											
Rc:Bankfull Width (ft/ft)	2.0	2.6											
Meander Wave Length (ft)	157	419											
Meander Width Ratio	1.9	3.5											
Additional Reach Parameters													
Rosgen Classification		C5											
Channel Thalweg Length (ft)	5	500											
Sinuosity (ft)	1	10											
Water Surface Slope (ft/ft)													
Bankfull Slope (ft/ft)	0.	004											
Ri%/Ru%/P%/G%/S%													
SC%/Sa%/G%/C%/B%/Be%													
d16/d35/d50/d84/d95/d100	0.4/0.8/1.7/94/256/2048												
% of Reach with Eroding Banks	(	0%	0	1%	0'	%	C	%					

<sup>(---):</sup> Data was not provided

<sup>&</sup>lt;sup>1</sup> Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins.

 $<sup>^{\</sup>rm 2}$  Bank Height Ratio is the bank height divided by the max depth of the bankfull channel.

<sup>&</sup>lt;sup>3</sup> Starting in MY2, bankfull elevation is calculated using a fixed Abkf as described in the Standard Measurement of the BHR Monitoring Parameter provided by NCIRT and NCDMS (2018).

Table 13s. Monitoring Data - Stream Reach Data Summary

Big Harris Creek Mitigation Site DMS Project No. 739

Monitoring Year 3 - 2020

#### LBHC R1b/2 (STA. 305+13 - 318+00)

Dimension and Substrate*   Bankfull Width (ft)   26.7   27.2   29.4   30.4	Parameter	As-Built/E	aseline 2018	MY1	2018	MY2	MY2 2019		MY3 2020		MY4 2021		MY5 2022	
Bankfull Width (ft)   26.7   27.2   29.4   30.4     Floodprine Width (ft)   299.6   171.0   84.9   84.9     Bankfull Mean Depth   1.7   1.9   2.1   2.0     Bankfull Max Depth   2.8   3.3   3.6   3.5     Bankfull Cross-Sectional Area (ft)   46.0   55.5   60.8   62.1     Width/Depth Ratio   15.5   14.3   14.2   14.9     Entrenchment Ratio   11.2   6.3   2.9   2.8     Bank Height Ratio   1.0   1.1   1.2   1.2     DS0 (mm)   87.4   47.7   61.5   85.4      Profile   Riffle Length (ft)   21   146     Riffle Slope (ft/ft)   0.002   0.065     Pool Length (ft)   14   135     Pool Max Depth (ft)   4.6   6.0     Pool Spacing (ft)   37   291     Pattern   Channel Beltwidth (ft)   80   117     Radius of Curvature (ft)   65   90     R.B.Bankfull Width (ft/ft)   2.4   3.4     Meander Wave Length (ft)   2.4   3.4     Meander Wave Length (ft)   2.26   396     Meander Width Ratio   3.0   4.4     Additional Reach Parameters   Rosgen Classification   C4     Channel Thalwey Length (ft)   1.09     Water Surface Stope (ft/ft)       Bankfull Slope (ft/ft)       Bankfull Slope (ft/ft)       Slov/SaW/GW/CW/BW/BeW       SCW/SaW/GW/CW/BW/BeW		Min	Max	Min Max		Min	Max	Min	Max	Min	Max	Min	Max	
Floodprone Width (ff)   299.6	Dimension and Substrate <sup>3</sup>													
Bankfull Mean Depth	Bankfull Width (ft)		26.7		27.2		29.4		30.4					
Bankfull Max Depth   2.8   3.3   3.6   3.5	Floodprone Width (ft)	2	99.6	171.0		84.9		84.9						
Bankfull Cross-Sectional Area (ft)	Bankfull Mean Depth			1.9				2.0						
Width/Depth Ratio   15.5   14.3   14.2   14.9	Bankfull Max Depth		2.8	3.3		3	3.6		3.5					
Entrenchment Ratio <sup>†</sup> Bank Height Ratio   1.0   1.1   1.2   1.2   1.2   1.2   1.2   1.5	Bankfull Cross-Sectional Area (ft)	4	16.0	51.5		60.8		62.1						
Bank Height Ratio   1.0	Width/Depth Ratio	1	15.5	14	1.3	14	14.2		1.9					
D50 (mm)   87.4   47.7   61.5   85.4	Entrenchment Ratio <sup>1</sup>	1	11.2	6.	.3	2	2.9		2.8					
Profile  Riffle Length (ft) 21 146  Riffle Slope (ft/ft) 0.002 0.065  Pool Length (ft) 14 135  Pool Max Depth (ft) 4.6 6.0  Pool Spacing (ft) 37 291  Pool Volume (ft³)  Pattern  Channel Beltwidth (ft) 80 117  Radius of Curvature (ft) 65 90  Riseankfull Width (ft/ft) 2.4 3.4  Meander Wave Length (ft) 236 396  Meander Width Ratio 3.0 4.4  Additional Reach Parameters  Rosgen Classification C4  Channel Thalweg Length (ft) 1,287  Sinuosity (ft) 1.09  Water Surface Slope (ft/ft)  Bankfull Slope (ft/ft)  Bankfull Slope (ft/ft) 0.003  Ri%/Ru%/P%/G%/S%  S%/Sa%/G%/C%/B%/Be%  d16/d35/d50/d84/d95/d100  0.2/0.3/5.6/94/256/2048	Bank Height Ratio <sup>2</sup>		1.0	1.	.1	1	.2	1.2						
Riffle Length (ft) 21 146 Riffle Slope (ft/ft) 0.002 0.065 Pool Length (ft) 14 135 Pool Max Depth (ft) 4.6 6.0 Pool Spacing (ft) 37 291 Pool Volume (ft <sup>2</sup> ) Pattern  Channel Beltwidth (ft) 80 117 Radius of Curvature (ft) 65 90 Re:Bankfull Width (ft/ft) 2.4 3.4 Meander Wave Length (ft) 236 396 Meander Width Ratio 3.0 4.4  Additional Reach Parameters  Rosgen Classification C4 Channel Thalweg Length (ft) 1.287 Sinuosity (ft) 1.09 Water Surface Slope (ft/ft <sup>4</sup> ) Bankfull Slope (ft/ft <sup>4</sup> ) 0.003 Ri%/Ru%/P%/G%/S% SCS%/Sa%/G%/C%/B%/Be% d16/d35/d50/d84/d95/d100 0.2/0.3/5.6/94/256/2048	D50 (mm)	8	37.4	47	<sup>7</sup> .7	6:	61.5		85.4					
Riffle Slope (ft/ft)   0.002   0.065     Pool Length (ft)   14   135     Pool Max Depth (ft)   4.6   6.0     Pool Spacing (ft)   37   291     Pool Volume (ft <sup>3</sup> )     Pattern	Profile													
Pool Length (ft)	Riffle Length (ft)	21	146											
Pool Max Depth (ft)   4.6   6.0			0.065											
Pool Spacing (ft)   37   291			135											
Pattern	Pool Max Depth (ft)	4.6	6.0											
Pattern  Channel Beltwidth (ft) 80 117  Radius of Curvature (ft) 65 90  Rc:Bankfull Width (ft/ft) 2.4 3.4  Meander Wave Length (ft) 236 396  Meander Width Ratio 3.0 4.4  Additional Reach Parameters  Rosgen Classification C4  Channel Thalweg Length (ft) 1,287  Sinuosity (ft) 1.09  Water Surface Slope (ft/ft)  Bankfull Slope (ft/ft) 0.003  Ri%/Ru%/P%/G%/S%  SC%/Sa%/G%/C%/B%/Be%  d16/d35/d50/d84/d95/d100 0.2/0.3/5.6/94/256/2048		37	291											
Channel Beltwidth (ft) 80 117 Radius of Curvature (ft) 65 90 Rc:Bankfull Width (ft/ft) 2.4 3.4 Meander Wave Length (ft) 236 396 Meander Width Ratio 3.0 4.4  Additional Reach Parameters  Rosgen Classification C4 Channel Thalweg Length (ft) 1,287 Sinuosity (ft) 1.09 Water Surface Slope (ft/ft) Bankfull Slope (ft/ft) 0.003 Ri:%/Ru%/P%/G%/S% SC%/Sa%/G%/C%/B%/Be% d16/d35/d50/d84/d95/d100 0.2/0.3/5.6/94/256/2048	Pool Volume (ft <sup>3</sup> )													
Radius of Curvature (ft) 65 90  Rc:Bankfull Width (ft/ft) 2.4 3.4  Meander Wave Length (ft) 236 396  Meander Width Ratio 3.0 4.4  Additional Reach Parameters  Rosgen Classification C4  Channel Thalweg Length (ft) 1,287  Sinuosity (ft) 1.09  Water Surface Slope (ft/ft) 0.003  Ri%/Ru%/P%/G%/S%  SC%/Sa%/G%/C%/B%/Be%  d16/d35/d50/d84/d95/d100 0.2/0.3/5.6/94/256/2048														
Rc:Bankfull Width (ft/ft) 2.4 3.4  Meander Wave Length (ft) 236 396  Meander Width Ratio 3.0 4.4  Additional Reach Parameters  Rosgen Classification C4 Channel Thalweg Length (ft) 1,287  Sinuosity (ft) 1.09  Water Surface Slope (ft/ft) Bankfull Slope (ft/ft) 0.003  Ri%/Rw%/P%/G%/S% SC%/Sa%/G%/C%/B%/Be% d16/d35/d50/d84/d95/d100 0.2/0.3/5.6/94/256/2048	Channel Beltwidth (ft)	80	117											
Meander Wave Length (ft)     236     396       Meander Width Ratio     3.0     4.4       Additional Reach Parameters       Rosgen Classification     C4       Channel Thalweg Length (ft)     1,287       Sinuosity (ft)     1.09       Water Surface Slope (ft/ft) <sup>4</sup> Bankfull Slope (ft/ft)     0.003       Ri%/Ru%/P%/G%/S%        SC%/Sa%/G%/C%/B%/Be%        d16/d35/d50/d84/d95/d100     0.2/0.3/5.6/94/256/2048	. ,		90											
Meander Width Ratio       3.0       4.4         Additional Reach Parameters         Rosgen Classification       C4         Channel Thalweg Length (ft)       1,287         Sinuosity (ft)       1.09         Water Surface Slope (ft/ft) <sup>4</sup> Bankfull Slope (ft/ft)       0.003         Ri%/Ru%/P%/G%/S%          SC%/Sa%/G%/C%/B%/Be%          d16/d35/d50/d84/d95/d100       0.2/0.3/5.6/94/256/2048			3.4											
Additional Reach Parameters  Rosgen Classification C4 Channel Thalweg Length (ft) 1,287 Sinuosity (ft) 1.09 Water Surface Slope (ft/ft) <sup>4</sup> Bankfull Slope (ft/ft) 0.003 Ri%/Ru%/P%/G%/S% SC%/Sa%/G%/C%/B%/Be% d16/d35/d50/d84/d95/d100 0.2/0.3/5.6/94/256/2048	_ : :													
Rosgen Classification C4 Channel Thalweg Length (ft) 1,287 Sinuosity (ft) 1.09 Water Surface Slope (ft/ft) Bankfull Slope (ft/ft) 0.003 Ri%/Ru%/P%/G%/S% SC%/Sa%/G%/C%/B%/Be% d16/d35/d50/d84/d95/d100 0.2/0.3/5.6/94/256/2048		3.0	4.4											
Channel Thalweg Length (ft) 1,287  Sinuosity (ft) 1.09  Water Surface Slope (ft/ft) <sup>4</sup> Bankfull Slope (ft/ft) 0.003  Ri%/Ru%/P%/G%/S%  SC%/Sa%/G%/C%/B%/Be%  d16/d35/d50/d84/d95/d100 0.2/0.3/5.6/94/256/2048	Additional Reach Parameters													
Sinuosity (ft) 1.09  Water Surface Slope (ft/ft) <sup>4</sup> Bankfull Slope (ft/ft) 0.003  Ri%/Ru%/P%/G%/S%  SC%/Sa%/G%/C%/B%/Be%  d16/d35/d50/d84/d95/d100 0.2/0.3/5.6/94/256/2048														
Water Surface Slope (ft/ft) <sup>4</sup> Bankfull Slope (ft/ft)       0.003         Ri%/Ru%/P%/G%/S%          SC%/Sa%/G%/C%/B%/Be%          d16/d35/d50/d84/d95/d100       0.2/0.3/5.6/94/256/2048														
Bankfull Slope (ft/ft) 0.003  Ri%/Ru%/P%/G%/S%  SC%/Sa%/G%/C%/B%/Be%  d16/d35/d50/d84/d95/d100 0.2/0.3/5.6/94/256/2048	Sinuosity (ft)	1	1.09							_				
Ri%/Ru%/P%/G%/S% SC%/Sa%/G%/C%/B%/Be% d16/d35/d50/d84/d95/d100 0.2/0.3/5.6/94/256/2048								0.0	007					
SC%/Sa%/G%/C%/B%/Be% d16/d35/d50/d84/d95/d100 0.2/0.3/5.6/94/256/2048			.003											
d16/d35/d50/d84/d95/d100 0.2/0.3/5.6/94/256/2048														
	SC%/Sa%/G%/C%/B%/Be%													
% of Reach with Froding Banks 0% 11% 6% 6%	d16/d35/d50/d84/d95/d100	0.2/0.3/5.6	/94/256/2048											
// Or readin with Erouning Buring   0/0   11/0   0/0   0/0	% of Reach with Eroding Banks		0%	11	L%	6	%	6	%					

<sup>(---):</sup> Data was not provided

<sup>&</sup>lt;sup>1</sup> Entrenchment Ratio (ER) is the flood prone width divided by the bankfull width. ER in MY2 and forward will be based on the width between monumented cross-section pins. ER in MY0 and MY1 are based on surveyed widths beyond cross-section pins.


 $<sup>^{\</sup>rm 2}$  Bank Height Ratio is the bank height divided by the max depth of the bankfull channel.

<sup>&</sup>lt;sup>3</sup> Starting in MY2, bankfull elevation is calculated using a fixed Abkf as described in the Standard Measurement of the BHR Monitoring Parameter provided by NCIRT and NCDMS (2018).

<sup>&</sup>lt;sup>4</sup>Water surface slopes are based on abbreviated longitudinal profiles of one meander length collected during MY3 after geomorphically significant events.

Big Harris Creek Mitigation Site - Area A NCDMS Project No. 739 Monitoring Year 3 - 2020

### UBHC Reach 2A: Cross-Section 1



## **Bankfull Dimensions**

x-section area (ft.sq.)

10.4 width (ft)

mean depth (ft) 0.8

2.0 max depth (ft)

wetted perimeter (ft) 11.7

hydraulic radius (ft) 0.7

13.1 width-depth ratio

89.2 W flood prone area (ft)

entrenchment ratio 8.6

0.9 low bank height ratio


Survey Date: 06/2020



View Downstream

Big Harris Creek Mitigation Site - Area A NCDMS Project No. 739 Monitoring Year 3 - 2020

### UBHC Reach 2A: Cross-Section 2



# Bankfull Dimensions

- x-section area (ft.sq.) 16.5
- width (ft) 11.4
- 1.5 mean depth (ft)
- 2.9 max depth (ft)
- 13.4
- wetted perimeter (ft) hydraulic radius (ft) 1.2
- 7.9 width-depth ratio


Survey Date: 06/2020



View Downstream

Big Harris Creek Mitigation Site - Area A NCDMS Project No. 739 Monitoring Year 3 - 2020

### **UBHC Reach 2B: Cross-Section 3**



## **Bankfull Dimensions**

- 33.1 x-section area (ft.sq.)
- 15.4 width (ft)
- 2.1 mean depth (ft)
- 4.3 max depth (ft)
- 19.0 wetted perimeter (ft)
- 1.7 hydraulic radius (ft)
- 7.2 width-depth ratio


Survey Date: 10/2020



View Downstream

Big Harris Creek Mitigation Site - Area A NCDMS Project No. 739 Monitoring Year 3 - 2020

### UBHC Reach 2B: Cross-Section 4



## **Bankfull Dimensions**

- 44.0 x-section area (ft.sq.)
- 18.9 width (ft)
- 2.3 mean depth (ft)
- 4.0 max depth (ft)
- 23.6 wetted perimeter (ft)
- 1.9 hydraulic radius (ft)
- 8.1 width-depth ratio
- 67.5 W flood prone area (ft)
- 07.5 W 1100d profile area (11
- 3.6 entrenchment ratio
- 1.8 low bank height ratio


Survey Date: 10/2020



View Downstream

Big Harris Creek Mitigation Site - Area A NCDMS Project No. 739 Monitoring Year 3 - 2020

### **UBHC Reach 4: Cross-Section 5**



## **Bankfull Dimensions**

- x-section area (ft.sq.) 12.9
- 10.9 width (ft)
- 1.2 mean depth (ft)
- 2.3 max depth (ft)
- wetted perimeter (ft) hydraulic radius (ft) 12.4
- 1.0
- 9.3 width-depth ratio


Survey Date: 06/2020



View Downstream

Big Harris Creek Mitigation Site - Area A NCDMS Project No. 739 Monitoring Year 3 - 2020

### **UBHC Reach 4: Cross-Section 6**



## **Bankfull Dimensions**

- L2.1 x-section area (ft.sq.)
- 14.9 width (ft)
- 0.8 mean depth (ft)
- 1.6 max depth (ft)
- 15.4 wetted perimeter (ft)
- 0.8 hydraulic radius (ft)
- 18.5 width-depth ratio
- 121.7 W flood prone area (ft)
- 8.1 entrenchment ratio
- 1.0 low bank height ratio


Survey Date: 06/2020



View Downstream

Big Harris Creek Mitigation Site - Area A NCDMS Project No. 739 Monitoring Year 3 - 2020

### **UBHC Reach 4: Cross-Section 7**



## **Bankfull Dimensions**

- 17.1 x-section area (ft.sq.)
- 16.2 width (ft)
- 1.1 mean depth (ft)
- 2.3 max depth (ft)
- 18.2 wetted perimeter (ft)
- 0.9 hydraulic radius (ft)
- 15.3 width-depth ratio
- 137.3 W flood prone area (ft)
- 8.5 entrenchment ratio
- 1.0 low bank height ratio


Survey Date: 06/2020



View Downstream

Big Harris Creek Mitigation Site - Area A NCDMS Project No. 739 Monitoring Year 3 - 2020

### **UBHC Reach 4: Cross-Section 8**



## **Bankfull Dimensions**

- x-section area (ft.sq.) 30.9
- 18.2 width (ft)
- 1.7 mean depth (ft)
- 3.8 max depth (ft)
- wetted perimeter (ft) hydraulic radius (ft) 21.9
- 1.4
- 10.7 width-depth ratio


Survey Date: 06/2020



View Downstream

Big Harris Creek Mitigation Site - Area A NCDMS Project No. 739 Monitoring Year 3 - 2020

## Royster Creek Reach 1: Cross-Section 9



## **Bankfull Dimensions**

- x-section area (ft.sq.)
- 4.1 width (ft)
- 0.2 mean depth (ft)
- 0.4 max depth (ft)
- wetted perimeter (ft) 4.3
- hydraulic radius (ft) 0.2
- 16.7 width-depth ratio
- 39.6 W flood prone area (ft)
- entrenchment ratio 9.6
- 0.5 low bank height ratio


Survey Date: 06/2020



View Downstream

Big Harris Creek Mitigation Site - Area A NCDMS Project No. 739 Monitoring Year 3 - 2020

## Royster Creek Reach 1: Cross-Section 10



## **Bankfull Dimensions**

- x-section area (ft.sq.)
- 11.0 width (ft)
- 0.9 mean depth (ft)
- 1.9 max depth (ft)
- wetted perimeter (ft) hydraulic radius (ft) 12.6
- 0.8
- 12.7 width-depth ratio


Survey Date: 06/2020



View Downstream

Big Harris Creek Mitigation Site - Area A NCDMS Project No. 739 Monitoring Year 3 - 2020

### Scott Creek: Cross-Section 11



## Bankfull Dimensions

- 16.2 x-section area (ft.sq.)
- 13.6 width (ft)
- 1.2 mean depth (ft)
- 2.1 max depth (ft)
- 14.5 wetted perimeter (ft)
- 1.1 hydraulic radius (ft)
- 11.4 width-depth ratio
- 44.5 W flood prone area (ft)
- 3.3 entrenchment ratio
- 2.5 low bank height ratio


Survey Date: 06/2020



View Downstream

Big Harris Creek Mitigation Site - Area A NCDMS Project No. 739 Monitoring Year 3 - 2020

### Scott Creek: Cross-Section 12



## **Bankfull Dimensions**

- 10.9 x-section area (ft.sq.)
- 11.4 width (ft)
- 1.0 mean depth (ft)
- 1.9 max depth (ft)
- 12.2 wetted perimeter (ft)
- 0.9 hydraulic radius (ft)
- 11.9 width-depth ratio


Survey Date: 06/2020



View Downstream

Big Harris Creek Mitigation Site - Area A NCDMS Project No. 739 Monitoring Year 3 - 2020

### Carroll Creek Reach 1: Cross-Section 13



## **Bankfull Dimensions**

- x-section area (ft.sq.)
- 7.0 width (ft)
- 0.7 mean depth (ft)
- 1.2 max depth (ft)
- wetted perimeter (ft) 7.7
- hydraulic radius (ft) 0.6
- 10.3 width-depth ratio
- 79.2 W flood prone area (ft)
- entrenchment ratio 11.3
- 0.7 low bank height ratio


Survey Date: 06/2020



View Downstream

Big Harris Creek Mitigation Site - Area A NCDMS Project No. 739 Monitoring Year 3 - 2020

### Carroll Creek Reach 1: Cross-Section 14



# Bankfull Dimensions

- x-section area (ft.sq.)
- width (ft) 8.7
- 1.0 mean depth (ft)
- 2.0 max depth (ft)
- wetted perimeter (ft) hydraulic radius (ft) 11.1
- 8.0
- 8.9 width-depth ratio


Survey Date: 06/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 Monitoring Year 3 - 2020

### USEC Reach 1: Cross-Section 15



### **Bankfull Dimensions**

- 3.6 x-section area (ft.sq.)
- 6.3 width (ft)
- 0.6 mean depth (ft)
- 1.0 max depth (ft)
- 6.9 wetted perimeter (ft)
- 0.5 hydraulic radius (ft)
- 11.2 width-depth ratio
- 35.8 W flood prone area (ft)
- 5.7 entrenchment ratio
- 0.9 low bank height ratio


Survey Date: 06/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 **Monitoring Year 3 - 2020** 

### USEC Reach 5: Cross-Section 16



### **Bankfull Dimensions**

- 17.6 x-section area (ft.sq.)
- 17.6 width (ft)
- 1.0 mean depth (ft)
- 1.7 max depth (ft)
- 18.3 wetted perimeter (ft)
- 1.0 hydraulic radius (ft)
- 17.7 width-depth ratio


Survey Date: 04/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 Monitoring Year 3 - 2020

### USEC Reach 5: Cross-Section 17



### **Bankfull Dimensions**

17.5 x-section area (ft.sq.)

18.6 width (ft)

0.9 mean depth (ft)

1.7 max depth (ft)

19.5 wetted perimeter (ft)

0.9 hydraulic radius (ft)

19.9 width-depth ratio

93.6 W flood prone area (ft)

5.0 entrenchment ratio

0.9 low bank height ratio


Survey Date: 04/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 Monitoring Year 3 - 2020

### USEC Reach 5: Cross-Section 18



### **Bankfull Dimensions**

14.8 x-section area (ft.sq.)

17.7 width (ft)

0.8 mean depth (ft)

1.9 max depth (ft)

18.5 wetted perimeter (ft)

0.8 hydraulic radius (ft)

21.2 width-depth ratio

86.0 W flood prone area (ft)

4.9 entrenchment ratio

0.9 low bank height ratio


Survey Date: 04/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 Monitoring Year 3 - 2020

### USEC Reach 5: Cross-Section 19



### **Bankfull Dimensions**

- x-section area (ft.sq.)
- 21.4 width (ft)
- 1.0 mean depth (ft)
- 2.6 max depth (ft)
- wetted perimeter (ft) hydraulic radius (ft) 23.1
- 0.9
- 21.0 width-depth ratio


Survey Date: 03/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 Monitoring Year 3 - 2020

### USEC Reach 5: Cross-Section 20



### **Bankfull Dimensions**

14.5 x-section area (ft.sq.)

15.4 width (ft)

0.9 mean depth (ft)

1.7 max depth (ft)

wetted perimeter (ft) 16.2

hydraulic radius (ft) 0.9

16.4 width-depth ratio

108.1 W flood prone area (ft)

7.0 entrenchment ratio

0.9 low bank height ratio


Survey Date: 03/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 Monitoring Year 3 - 2020

### USEC Reach 6: Cross-Section 21



# Bankfull Dimensions

- x-section area (ft.sq.)
- 21.6 width (ft)
- 1.7 mean depth (ft)
- 3.7 max depth (ft)
- wetted perimeter (ft) hydraulic radius (ft) 24.2
- 1.5
- 12.7 width-depth ratio


Survey Date: 03/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 Monitoring Year 3 - 2020

### USEC Reach 6: Cross-Section 22



### **Bankfull Dimensions**

- 21.5 x-section area (ft.sq.)
- 18.2 width (ft)
- 1.2 mean depth (ft)
- 2.7 max depth (ft)
- 20.0 wetted perimeter (ft)
- 1.1 hydraulic radius (ft)
- 15.4 width-depth ratio
- 83.2 W flood prone area (ft)
- 4.6 entrenchment ratio
- 1.0 low bank height ratio


Survey Date: 03/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 Monitoring Year 3 - 2020

### USEC Reach 6: Cross-Section 23



### **Bankfull Dimensions**

- x-section area (ft.sq.)
- 17.1 width (ft)
- 1.3 mean depth (ft)
- 2.9 max depth (ft)
- wetted perimeter (ft) 18.7
- hydraulic radius (ft) 1.2
- 12.7 width-depth ratio
- 81.8 W flood prone area (ft)
- entrenchment ratio 4.8
- low bank height ratio 1.1

Survey Date: 03/2020




View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739

Monitoring Year 3 - 2020

### Elliott Creek: Cross-Section 24



### **Bankfull Dimensions**

- 4.7 x-section area (ft.sq.)
- 7.3 width (ft)
- 0.6 mean depth (ft)
- 1.1 max depth (ft)
- 7.9 wetted perimeter (ft)
- 0.6 hydraulic radius (ft)
- 11.3 width-depth ratio
- 17.6 W flood prone area (ft)
- 2.4 entrenchment ratio
- 1.2 low bank height ratio


Survey Date: 06/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 **Monitoring Year 3 - 2020** 

### Elliott Creek: Cross-Section 25



### **Bankfull Dimensions**

- 9.4 x-section area (ft.sq.)
- 9.7 width (ft)
- 1.0 mean depth (ft)
- 1.5 max depth (ft)
- 10.7 wetted perimeter (ft)
- 0.9 hydraulic radius (ft)
- 9.9 width-depth ratio


Survey Date: 06/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 Monitoring Year 3 - 2020

### Elliott Creek: Cross-Section 26



### **Bankfull Dimensions**

- 6.8 x-section area (ft.sq.)
- 8.5 width (ft)
- mean depth (ft) 0.8
- 1.3 max depth (ft)
- wetted perimeter (ft) 9.1
- hydraulic radius (ft) 0.7
- 10.6 width-depth ratio
- 20.5 W flood prone area (ft)
- entrenchment ratio 2.4
- 1.1 low bank height ratio


Survey Date: 06/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 Monitoring Year 3 - 2020

### UT1 to Elliott Creek: Cross-Section 27



### **Bankfull Dimensions**

- 2.2 x-section area (ft.sq.)
- 5.4 width (ft)
- 0.4 mean depth (ft)
- 0.9 max depth (ft)
- 5.8 wetted perimeter (ft)
- 0.4 hydraulic radius (ft)
- 13.2 width-depth ratio
- 14.3 W flood prone area (ft)
- 2.6 entrenchment ratio
- 0.9 low bank height ratio


Survey Date: 06/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 Monitoring Year 3 - 2020

## **Bridges Creek: Cross-Section 28**



### **Bankfull Dimensions**

- 2.2 x-section area (ft.sq.)
- 6.6 width (ft)
- 0.3 mean depth (ft)
- 0.6 max depth (ft)
- 6.8 wetted perimeter (ft)
- 0.3 hydraulic radius (ft)
- 19.8 width-depth ratio
- 20.1 W flood prone area (ft)
- 3.0 entrenchment ratio
- 0.8 low bank height ratio


Survey Date: 06/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 Monitoring Year 3 - 2020

### USEC UT2: Cross-Section 29



### **Bankfull Dimensions**

- x-section area (ft.sq.)
- 5.5 width (ft)
- mean depth (ft) 0.6
- 1.1 max depth (ft)
- wetted perimeter (ft) 7.1
- hydraulic radius (ft) 0.4
- 9.9 width-depth ratio
- 43.5 W flood prone area (ft)
- entrenchment ratio 8.0
- 1.0 low bank height ratio


Survey Date: 03/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 Monitoring Year 3 - 2020

### USEC Reach UT3: Cross-Section 30



### **Bankfull Dimensions**

- 2.9 x-section area (ft.sq.)
- 7.6 width (ft)
- 0.4 mean depth (ft)
- 0.8 max depth (ft)
- 7.8 wetted perimeter (ft)
- 0.4 hydraulic radius (ft)
- 19.4 width-depth ratio
- 45.2 W flood prone area (ft)
- 6.0 entrenchment ratio
- 0.9 low bank height ratio


Survey Date: 03/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 Monitoring Year 3 - 2020

### UFC Reach 2: Cross-Section 31



### **Bankfull Dimensions**

- 7.8 x-section area (ft.sq.)
- 11.6 width (ft)
- 0.7 mean depth (ft)
- 1.2 max depth (ft)
- 12.0 wetted perimeter (ft)
- 0.7 hydraulic radius (ft)
- 17.2 width-depth ratio
- 77.8 W flood prone area (ft)
- 6.7 entrenchment ratio
- 1.0 low bank height ratio


Survey Date: 03/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 **Monitoring Year 3 - 2020** 

### UFC Reach 2: Cross-Section 32



### **Bankfull Dimensions**

- 7.9 x-section area (ft.sq.)
- 9.2 width (ft)
- 0.9 mean depth (ft)
- 1.1 max depth (ft)
- 10.0 wetted perimeter (ft)
- 0.8 hydraulic radius (ft)
- 10.7 width-depth ratio


Survey Date: 03/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 Monitoring Year 3 - 2020

### UFC Reach 2: Cross-Section 33



### **Bankfull Dimensions**

- x-section area (ft.sq.) 13.3
- 14.0 width (ft)
- mean depth (ft) 1.0
- 1.8 max depth (ft)
- wetted perimeter (ft) hydraulic radius (ft) 15.1
- 0.9
- 14.7 width-depth ratio


Survey Date: 03/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 Monitoring Year 3 - 2020

### UFC Reach 2: Cross-Section 34



### **Bankfull Dimensions**

- 8.5 x-section area (ft.sq.)
- 12.1 width (ft)
- 0.7 mean depth (ft)
- 1.4 max depth (ft)
- 12.6 wetted perimeter (ft)
- 0.7 hydraulic radius (ft)
- 17.1 width-depth ratio
- 69.8 W flood prone area (ft)
- 03.8 W Hood profit area (it
- 5.8 entrenchment ratio
- 1.0 low bank height ratio


Survey Date: 03/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 Monitoring Year 3 - 2020

### UFC Reach 2: Cross-Section 35



### **Bankfull Dimensions**

- 8.8 x-section area (ft.sq.)
- 12.1 width (ft)
- 0.7 mean depth (ft)
- 1.5 max depth (ft)
- 12.8 wetted perimeter (ft)
- 0.7 hydraulic radius (ft)
- 16.7 width-depth ratio
- 85.7 W flood prone area (ft)
- 7.1 entrenchment ratio
- 1.0 low bank height ratio


Survey Date: 03/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 **Monitoring Year 3 - 2020** 

### UFC Reach 2: Cross-Section 36



### **Bankfull Dimensions**

- 22.7 x-section area (ft.sq.)
- 15.5 width (ft)
- 1.5 mean depth (ft)
- 3.1 max depth (ft)
- 17.7 wetted perimeter (ft)
- 1.3 hydraulic radius (ft)
- 10.6 width-depth ratio


Survey Date: 03/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 Monitoring Year 3 - 2020

### LFC Reach 1: Cross-Section 37



### **Bankfull Dimensions**

- 9.3 x-section area (ft.sq.)
- 10.4 width (ft)
- 0.9 mean depth (ft)
- 1.2 max depth (ft)
- 11.3 wetted perimeter (ft)
- 0.8 hydraulic radius (ft)
- 11.7 width-depth ratio
- 26.9 W flood prone area (ft)
- 2.6 entrenchment ratio
- 1.0 low bank height ratio


Survey Date: 03/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 Monitoring Year 3 - 2020

### LFC Reach 1: Cross-Section 38



### **Bankfull Dimensions**

- x-section area (ft.sq.)
- width (ft) 11.5
- 1.0 mean depth (ft)
- 1.5 max depth (ft)
- wetted perimeter (ft) hydraulic radius (ft) 12.5
- 0.9
- 11.6 width-depth ratio


Survey Date: 03/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 **Monitoring Year 3 - 2020** 

### LFC Reach 2: Cross-Section 39



### **Bankfull Dimensions**

- 7.6 x-section area (ft.sq.)
- 10.1 width (ft)
- 0.8 mean depth (ft)
- 1.1 max depth (ft)
- 10.7 wetted perimeter (ft)
- 0.7 hydraulic radius (ft)
- 13.4 width-depth ratio
- 30.5 W flood prone area (ft)
- 3.0 entrenchment ratio
- 1.1 low bank height ratio


Survey Date: 03/2020



View Downstream

Big Harris Creek Mitigation Site - Area B NCDMS Project No. 739 Monitoring Year 3 - 2020

### LFC Reach 2: Cross-Section 40



### **Bankfull Dimensions**

- 11.9 x-section area (ft.sq.)
- 10.0 width (ft)
- 1.2 mean depth (ft)
- 1.6 max depth (ft)
- wetted perimeter (ft) hydraulic radius (ft) 11.5
- 1.0
- 8.4 width-depth ratio


Survey Date: 03/2020



View Downstream

Big Harris Creek Mitigation Site - Area C NCDMS Project No. 739 Monitoring Year 3 - 2020

### LBHC Reach 1A: Cross-Section 41



### **Bankfull Dimensions**

- x-section area (ft.sq.)
- 24.6 width (ft)
- mean depth (ft) 2.0
- 3.7 max depth (ft)
- wetted perimeter (ft) hydraulic radius (ft) 27.6
- 1.8
- 12.1 width-depth ratio


Survey Date: 05/2020



View Downstream

Big Harris Creek Mitigation Site - Area C NCDMS Project No. 739 Monitoring Year 3 - 2020

### LBHC Reach 1A: Cross-Section 42



### **Bankfull Dimensions**

5.0	x-section area	

- 30.7 width (ft)
- 1.8 mean depth (ft)
- 3.6 max depth (ft)
- 32.5 wetted perimeter (ft)
- 1.7 hydraulic radius (ft)
- 16.9 width-depth ratio
- 78.0 W flood prone area (ft)
- 2.5 entrenchment ratio
- 1.1 low bank height ratio

Survey Date: 05/2020




View Downstream

Big Harris Creek Mitigation Site - Area C NCDMS Project No. 739

Monitoring Year 3 - 2020

### LBHC Reach 1B/2: Cross-Section 43



### Bankfull Dimensions

62.1 x-section area (ft.sq.)

30.4 width (ft)

2.0 mean depth (ft)

3.5 max depth (ft)

33.3 wetted perimeter (ft)

1.9 hydraulic radius (ft)

14.9 width-depth ratio

84.9 W flood prone area (ft)

2.8 entrenchment ratio

1.2 low bank height ratio


Survey Date: 05/2020



View Downstream

Big Harris Creek Mitigation Site - Area C NCDMS Project No. 739 Monitoring Year 3 - 2020

## LBHC Reach 1B/2: Cross-Section 44



### **Bankfull Dimensions**

- 57.7 x-section area (ft.sq.)
- 22.8 width (ft)
- 2.5 mean depth (ft)
- 3.7 max depth (ft)
- 25.8 wetted perimeter (ft)
- 2.2 hydraulic radius (ft)
- 9.0 width-depth ratio

Survey Date: 05/2020




View Downstream


Big Harris Creek Mitigation Site - Area A DMS Project No. 739 Monitoring Year 3 - 2020

UBHC Reaches 2A & 2B, Reachwide

		Diame	ter (mm)	Pa	rticle Co	unt	Reach S	ummary
Particle Class							Class	Percent
		min	max	Riffle	Pool	Total	Percentage	Cumulative
SILT/CLAY	Silt/Clay	0.000	0.062	1		1	1	1
	Very fine	0.062	0.125		1	1	1	2
	Fine	0.125	0.250		1	1	1	3
SANO	Medium	0.25	0.50		3	3	3	6
Sr.	Coarse	0.5	1.0		6	6	6	12
	Very Coarse	1.0	2.0		7	7	7	19
	Very Fine	2.0	2.8	3	7	10	10	29
	Very Fine	2.8	4.0	6	8	14	14	43
	Fine	4.0	5.6	8	3	11	11	54
	Fine	5.6	8.0	9	4	13	13	67
JEL	Medium	8.0	11.0	3		3	3	70
GRAVEL	Medium	11.0	16.0	7	5	12	12	82
ŭ	Coarse	16.0	22.6	9	1	10	10	92
	Coarse	22.6	32	1	1	2	2	94
	Very Coarse	32	45	1	2	3	3	97
	Very Coarse	45	64	1		1	1	98
	Small	64	90		1	1	1	99
ale	Small	90	128					99
COBBLE	Large	128	180	1		1	1	100
ŭ	Large	180	256					100
	Small	256	362					100
ROULDER	Small	362	512					100
COULT	Medium	512	1024					100
•	Large/Very Large	1024	2048					100
BEDROCK	Bedrock	2048	>2048					100
			Total	50	50	100	100	100

Reachwide				
Channel materials (mm)				
D <sub>16</sub> =	1.5			
D <sub>35</sub> =	3.3			
D <sub>50</sub> =	5.0			
D <sub>84</sub> =	17.1			
D <sub>95</sub> =	35.9			
D <sub>100</sub> =	180.0			





Big Harris Creek Mitigation Site - Area A


DMS Project No. 739


Monitoring Year 3 - 2020

UBHC Reach 2A, Cross-Section 1

Particle Class		Diameter (mm)		Riffle 100-	Summary		
				Count	Class	Percent	
		min	max	Count	Percentage	Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062			0	
	Very fine	0.062	0.125			0	
_	Fine	0.125	0.250	1	1	1	
SAND	Medium	0.25	0.50	4	4	5	
51	Coarse	0.5	1.0	5	5	10	
	Very Coarse	1.0	2.0			10	
	Very Fine	2.0	2.8	3	3	13	
	Very Fine	2.8	4.0	4	4	17	
	Fine	4.0	5.6	7	7	24	
	Fine	5.6	8.0	12	12	36	
JEL	Medium	8.0	11.0	21	21	57	
GRAVEL	Medium	11.0	16.0	18	18	75	
Ü	Coarse	16.0	22.6	10	10	85	
	Coarse	22.6	32	6	6	91	
	Very Coarse	32	45	5	5	96	
	Very Coarse	45	64	2	2	98	
	Small	64	90	1	1	99	
ale	Small	90	128			99	
CORRIE	Large	128	180			99	
•	Large	180	256			99	
	Small	256	362	1	1	100	
BOULDER	Small	362	512			100	
COULL	Medium	512	1024			100	
8.	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
	•	•	Total	100	100	100	

Cross-Section 1							
Cha	Channel materials (mm)						
D <sub>16</sub> =	3.7						
D <sub>35</sub> =	7.8						
D <sub>50</sub> =	9.9						
D <sub>84</sub> =	21.8						
D <sub>95</sub> =	42.0						
D <sub>100</sub> =	362.0						





Big Harris Creek Mitigation Site - Area A


DMS Project No. 739


Monitoring Year 3 - 2020

UBHC Reach 2B, Cross-Section 4

		Diame	ter (mm)	Riffle 100-	Sum	mary
Par	Particle Class		max	Count	Class Percentage	Percent Cumulative
SILT/CLAY	Silt/Clay	0.000	0.062	6	6	6
	Very fine	0.062	0.125	2	2	8
	Fine	0.125	0.250	3	3	11
SAND	Medium	0.25	0.50	16	16	27
יל	Coarse	0.5	1.0	18	18	45
	Very Coarse	1.0	2.0	7	7	52
	Very Fine	2.0	2.8			52
	Very Fine	2.8	4.0	1	1	53
	Fine	4.0	5.6	1	1	54
	Fine	5.6	8.0	4	4	58
JEL	Medium	8.0	11.0	5	5	63
GRAVEL	Medium	11.0	16.0	6	6	69
-	Coarse	16.0	22.6	2	2	71
	Coarse	22.6	32	6	6	77
	Very Coarse	32	45	4	4	81
	Very Coarse	45	64	3	3	84
	Small	64	90	4	4	88
COBBLE	Small	90	128	5	5	93
CORY	Large	128	180	6	6	99
-	Large	180	256	1	1	100
	Small	256	362			100
, OER	Small	362	512			100
BOULDER	Medium	512	1024			100
>	Large/Very Large	1024	2048			100
BEDROCK	Bedrock	2048	>2048			100
			Total	100	100	100

	Cross-Section 4						
Cha	Channel materials (mm)						
D <sub>16</sub> =	0.3						
D <sub>35</sub> =	0.7						
D <sub>50</sub> =	1.6						
D <sub>84</sub> =	64.0						
D <sub>95</sub> =	143.4						
D <sub>100</sub> =	256.0						







Big Harris Creek Mitigation Site - Area A DMS Project No. 739 Monitoring Year 3 - 2020

UBHC Reach 4, Reachwide

Particle Class		Diame	ter (mm)	Pa	rticle Co	unt	Reach S	ummary
							Class	Percent
		min	max	Riffle	Pool	Total	Percentage	Cumulative
SILT/CLAY	Silt/Clay	0.000	0.062					0
	Very fine	0.062	0.125					0
_	Fine	0.125	0.250	1	2	3	3	3
SAND	Medium	0.25	0.50		10	10	10	13
2,	Coarse	0.5	1.0	1	6	7	7	20
	Very Coarse	1.0	2.0		7	7	7	27
	Very Fine	2.0	2.8	1	2	3	3	30
	Very Fine	2.8	4.0		3	3	3	33
	Fine	4.0	5.6		2	2	2	35
	Fine	5.6	8.0		2	2	2	37
JEL	Medium	8.0	11.0		2	2	2	39
GRAVEL	Medium	11.0	16.0	2		2	2	41
Ü	Coarse	16.0	22.6	3	2	5	5	46
	Coarse	22.6	32	3	2	5	5	51
	Very Coarse	32	45	6	2	8	8	59
	Very Coarse	45	64	5	2	7	7	66
	Small	64	90	8	2	10	10	76
COBBLE	Small	90	128	7	4	11	11	87
OBL	Large	128	180	8		8	8	95
Ŭ	Large	180	256	2		2	2	97
	Small	256	362	1		1	1	98
BOULDER	Small	362	512					98
COULT	Medium	512	1024					98
•	Large/Very Large	1024	2048					98
BEDROCK	Bedrock	2048	>2048	2		2	2	100
	·		Total	50	50	100	100	100

Reachwide				
Channel materials (mm)				
D <sub>16</sub> =	0.7			
D <sub>35</sub> =	5.6			
D <sub>50</sub> =	29.8			
D <sub>84</sub> =	116.3			
D <sub>95</sub> =	180.0			
D <sub>100</sub> =	>2048			





Big Harris Creek Mitigation Site - Area A


DMS Project No. 739


Monitoring Year 3 - 2020

UBHC Reach 4, Cross-Section 6

Particle Class		Diameter (mm)		Riffle 100-	Summary		
				Count	Class	Percent	
		min	max	Count	Percentage	Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062			0	
	Very fine	0.062	0.125			0	
	Fine	0.125	0.250	2	2	2	
SAND	Medium	0.25	0.50	2	2	4	
51	Coarse	0.5	1.0	3	3	7	
	Very Coarse	1.0	2.0	2	2	9	
	Very Fine	2.0	2.8	1	1	10	
	Very Fine	2.8	4.0	1	1	11	
	Fine	4.0	5.6	2	2	13	
	Fine	5.6	8.0	2	2	15	
JEL	Medium	8.0	11.0	2	2	17	
GRAVEL	Medium	11.0	16.0	3	3	20	
Ŭ	Coarse	16.0	22.6	10	10	30	
	Coarse	22.6	32	10	10	40	
	Very Coarse	32	45	11	11	51	
	Very Coarse	45	64	9	9	60	
	Small	64	90	11	11	71	
COBBLE	Small	90	128	16	16	87	
COBP.	Large	128	180	6	6	93	
•	Large	180	256	7	7	100	
	Small	256	362			100	
OFR	Small	362	512			100	
BOULDER	Medium	512	1024			100	
	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
	•	•	Total	100	100	100	

Cross-Section 6					
Channel materials (mm)					
D <sub>16</sub> =	9.4				
D <sub>35</sub> =	26.9				
D <sub>50</sub> =	43.6				
D <sub>84</sub> =	119.8				
D <sub>95</sub> =	199.1				
D <sub>100</sub> =	256.0				





Big Harris Creek Mitigation Site - Area A


DMS Project No. 739


Monitoring Year 3 - 2020

UBHC Reach 4, Cross-Section 7

Particle Class		Diame	ter (mm)	Riffle 100-	Summary		
				Count	Class	Percent	
		min	max	Count	Percentage	Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062			0	
	Very fine	0.062	0.125			0	
	Fine	0.125	0.250	1	1	1	
SAND	Medium	0.25	0.50	3	3	4	
51	Coarse	0.5	1.0	1	1	5	
	Very Coarse	1.0	2.0	2	2	7	
	Very Fine	2.0	2.8			7	
	Very Fine	2.8	4.0			7	
	Fine	4.0	5.6	3	3	10	
	Fine	5.6	8.0			10	
.161	Medium	8.0	11.0	1	1	11	
GRAVEL	Medium	11.0	16.0	2	2	13	
·	Coarse	16.0	22.6	4	4	17	
	Coarse	22.6	32	9	9	26	
	Very Coarse	32	45	4	4	30	
	Very Coarse	45	64	11	11	41	
	Small	64	90	19	19	60	
COBBLE	Small	90	128	17	17	77	
COBE	Large	128	180	14	14	91	
•	Large	180	256	2	2	93	
	Small	256	362	1	1	94	
OER	Small	362	512	5	5	99	
ROULDER	Medium	512	1024	1	1	100	
	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
	•	•	Total	100	100	100	

Cross-Section 7						
Channel materials (mm)						
D <sub>16</sub> =	20.7					
D <sub>35</sub> =	52.8					
D <sub>50</sub> =	75.2					
D <sub>84</sub> =	151.8					
D <sub>95</sub> =	388.0					
D <sub>100</sub> =	1024.0					







Big Harris Creek Mitigation Site - Area A DMS Project No. 739 Monitoring Year 3 - 2020

Royster Creek Reach 1, Reachwide

		Diame	ter (mm)	Pa	rticle Co	unt	Reach Summary	
Par	ticle Class						Class	Percent
		min	max	Riffle	Pool	Total	Percentage	Cumulative
SILT/CLAY	Silt/Clay	0.000	0.062	4	14	18	18	18
	Very fine	0.062	0.125	4	2	6	6	24
	Fine	0.125	0.250	1	1	2	2	26
SAND	Medium	0.25	0.50		1	1	1	27
Sr.	Coarse	0.5	1.0	2	8	10	10	37
	Very Coarse	1.0	2.0		6	6	6	43
	Very Fine	2.0	2.8					43
	Very Fine	2.8	4.0					43
	Fine	4.0	5.6		2	2	2	45
	Fine	5.6	8.0		3	3	3	48
JEL	Medium	8.0	11.0	2	1	3	3	51
GRAVEL	Medium	11.0	16.0	2	1	3	3	54
Ŭ	Coarse	16.0	22.6	1	1	2	2	56
	Coarse	22.6	32	2		2	2	58
	Very Coarse	32	45	7	2	9	9	67
	Very Coarse	45	64	7	2	9	9	76
	Small	64	90	6	1	7	7	83
COBBLE	Small	90	128	3	4	7	7	90
OBL	Large	128	180	2		2	2	92
ŭ	Large	180	256	4	1	5	5	97
	Small	256	362	2		2	2	99
. DER	Small	362	512	1		1	1	100
BOULDER	Medium	512	1024					100
ν-	Large/Very Large	1024	2048					100
BEDROCK	Bedrock	2048	>2048					100
	•	•	Total	50	50	100	100	100

Reachwide					
Channel materials (mm)					
D <sub>16</sub> =	Silt/Clay				
D <sub>35</sub> =	0.9				
D <sub>50</sub> =	9.9				
D <sub>84</sub> =	94.6				
D <sub>95</sub> =	222.4				
D <sub>100</sub> =	512.0				





Big Harris Creek Mitigation Site - Area A


DMS Project No. 739


Monitoring Year 3 - 2020

Royster Creek Reach 1, Cross-Section 9

		Diame	ter (mm)	Riffle 100-	Summary		
Pai	rticle Class			Count	Class	Percent	
		min	max	Count	Percentage	Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062	1	1	1	
	Very fine	0.062	0.125	21	21	22	
_	Fine	0.125	0.250	12	12	34	
SAND	Medium	0.25	0.50	6	6	40	
51	Coarse	0.5	1.0	10	10	50	
	Very Coarse	1.0	2.0	15	15	65	
	Very Fine	2.0	2.8			65	
	Very Fine	2.8	4.0	3	3	68	
	Fine	4.0	5.6	6	6	74	
GRAVEL	Fine	5.6	8.0	6	6	80	
	Medium	8.0	11.0	12	12	92	
	Medium	11.0	16.0	4	4	96	
	Coarse	16.0	22.6	3	3	99	
	Coarse	22.6	32			99	
	Very Coarse	32	45	1	1	100	
	Very Coarse	45	64			100	
	Small	64	90			100	
ale.	Small	90	128			100	
COBBLE	Large	128	180			100	
Ü	Large	180	256			100	
	Small	256	362			100	
BOULDER	Small	362	512			100	
	Medium	512	1024			100	
	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
	****		Total	100	100	100	

Cross-Section 9						
Channel materials (mm)						
D <sub>16</sub> =	0.1					
D <sub>35</sub> =	0.3					
D <sub>50</sub> =	1.0					
D <sub>84</sub> =	8.9					
D <sub>95</sub> =	14.6					
D <sub>100</sub> =	45.0					







Big Harris Creek Mitigation Site - Area A DMS Project No. 739 Monitoring Year 3 - 2020

Scott Creek, Reachwide

		Diame	ter (mm)	Pa	rticle Co	unt	Reach Summary	
Particle Class		min	max	Riffle	Pool	Total	Class Percentage	Percent Cumulative
SILT/CLAY	Silt/Clay	0.000	0.062	2	4	6	6	6
	Very fine	0.062	0.125	1	9	10	10	16
	Fine	0.125	0.250	2	3	5	5	21
SAND	Medium	0.25	0.50		1	1	1	22
SA	Coarse	0.5	1.0	1	4	5	5	27
	Very Coarse	1.0	2.0		2	2	2	29
	Very Fine	2.0	2.8					29
	Very Fine	2.8	4.0	1	1	2	2	31
	Fine	4.0	5.6		1	1	1	32
	Fine	5.6	8.0	1	2	3	3	35
.161	Medium	8.0	11.0	1		1	1	36
GRAVEL	Medium	11.0	16.0					36
· ·	Coarse	16.0	22.6	1	1	2	2	38
	Coarse	22.6	32	5	3	8	8	46
	Very Coarse	32	45	3	2	5	5	51
	Very Coarse	45	64	7	2	9	9	60
	Small	64	90	7	3	10	10	70
COBBLE	Small	90	128	9	4	13	13	83
COBL	Large	128	180	4	5	9	9	92
ŭ	Large	180	256	2	2	4	4	96
	Small	256	362	2	1	3	3	99
BOULDER	Small	362	512	1		1	1	100
	Medium	512	1024					100
	Large/Very Large	1024	2048					100
BEDROCK	Bedrock	2048	>2048					100
	•		Total	50	50	100	100	100

Reachwide					
Channel materials (mm)					
D <sub>16</sub> =	0.1				
D <sub>35</sub> =	8.0				
D <sub>50</sub> =	42.0				
D <sub>84</sub> =	132.9				
D <sub>95</sub> =	234.4				
D <sub>100</sub> =	512.0				





Big Harris Creek Mitigation Site - Area A


DMS Project No. 739


Monitoring Year 3 - 2020

Scott Creek, Cross-Section 11

		Diame	ter (mm)	Riffle 100-	Summary		
Pai	rticle Class			Count	Class	Percent	
		min	max		Percentage	Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062	3	3	3	
	Very fine	0.062	0.125	1	1	4	
	Fine	0.125	0.250	7	7	11	
SANO	Medium	0.25	0.50	6	6	17	
'ל	Coarse	0.5	1.0	3	3	20	
	Very Coarse	1.0	2.0	2	2	22	
	Very Fine	2.0	2.8	3	3	25	
	Very Fine	2.8	4.0	1	1	26	
	Fine	4.0	5.6	1	1	27	
	Fine	5.6	8.0	4	4	31	
JEL	Medium	8.0	11.0	1	1	32	
GRAVEL	Medium	11.0	16.0	1	1	33	
Ŭ	Coarse	16.0	22.6	4	4	37	
	Coarse	22.6	32	8	8	45	
	Very Coarse	32	45	9	9	54	
	Very Coarse	45	64	18	18	72	
	Small	64	90	8	8	80	
COBBLE	Small	90	128	11	11	91	
OBU	Large	128	180	6	6	97	
·	Large	180	256	3	3	100	
	Small	256	362			100	
OER	Small	362	512			100	
BOULDER	Medium	512	1024			100	
ν,	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
	•	•	Total	100	100	100	

Cross-Section 11					
Channel materials (mm)					
D <sub>16</sub> =	0.4				
D <sub>35</sub> =	19.0				
D <sub>50</sub> =	38.7				
D <sub>84</sub> =	102.3				
D <sub>95</sub> =	160.7				
D <sub>100</sub> =	256.0				







Big Harris Creek Mitigation Site - Area A DMS Project No. 739 Monitoring Year 3 - 2020

Carroll Creek, Reachwide

		Diame	ter (mm)	Pa	rticle Co	unt	Reach Summary	
Par	ticle Class						Class	Percent
		min	max	Riffle	Pool	Total	Percentage	Cumulative
SILT/CLAY	Silt/Clay	0.000	0.062		1	1	1	1
	Very fine	0.062	0.125		8	8	8	9
	Fine	0.125	0.250		11	11	11	20
SAND	Medium	0.25	0.50		3	3	3	23
71	Coarse	0.5	1.0	2	6	8	8	31
	Very Coarse	1.0	2.0		1	1	1	32
	Very Fine	2.0	2.8	1	1	2	2	34
	Very Fine	2.8	4.0	1	3	4	4	38
	Fine	4.0	5.6	1	1	2	2	40
	Fine	5.6	8.0	1		1	1	41
JEL	Medium	8.0	11.0	2		2	2	43
GRAVEL	Medium	11.0	16.0	6	1	7	7	50
	Coarse	16.0	22.6	2	1	3	3	53
	Coarse	22.6	32	6	5	11	11	64
	Very Coarse	32	45	2	4	6	6	70
	Very Coarse	45	64	11	2	13	13	83
	Small	64	90	6	1	7	7	90
CORRIE	Small	90	128	4	1	5	5	95
OBU	Large	128	180	3		3	3	98
Ŭ	Large	180	256	2		2	2	100
	Small	256	362					100
OER	Small	362	512					100
BOULDER	Medium	512	1024					100
<b>V</b>	Large/Very Large	1024	2048					100
BEDROCK	Bedrock	2048	>2048					100
			Total	50	50	100	100	100

Reachwide					
Channel materials (mm)					
D <sub>16</sub> =	0.2				
D <sub>35</sub> =	3.1				
D <sub>50</sub> =	16.0				
D <sub>84</sub> =	67.2				
D <sub>95</sub> =	128.0				
D <sub>100</sub> =	256.0				





Big Harris Creek Mitigation Site - Area A


DMS Project No. 739


Monitoring Year 3 - 2020

Carroll Creek, Cross-Section 13

		Diame	ter (mm)	Riffle 100-	Summary		
Pai	rticle Class			Count	Class	Percent	
		min	max	Count	Percentage	Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062			0	
	Very fine	0.062	0.125			0	
	Fine	0.125	0.250	1	1	1	
SANO	Medium	0.25	0.50	2	2	3	
51	Coarse	0.5	1.0	5	5	8	
	Very Coarse	1.0	2.0	2	2	10	
	Very Fine	2.0	2.8	3	3	13	
	Very Fine	2.8	4.0	1	1	14	
	Fine	4.0	5.6	2	2	16	
	Fine	5.6	8.0	2	2	18	
,EL	Medium	8.0	11.0	2	2	20	
GRAVEL	Medium	11.0	16.0	6	6	26	
	Coarse	16.0	22.6	5	5	31	
	Coarse	22.6	32	10	10	41	
	Very Coarse	32	45	26	26	67	
	Very Coarse	45	64	14	14	81	
	Small	64	90	10	10	91	
COBBLE	Small	90	128	6	6	97	
OBD.	Large	128	180	3	3	100	
•	Large	180	256			100	
	Small	256	362			100	
BOULDER	Small	362	512			100	
101/L	Medium	512	1024			100	
8	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
			Total	100	100	100	

	Cross-Section 13				
Cha	Channel materials (mm)				
D <sub>16</sub> =	5.6				
D <sub>35</sub> =	26.0				
D <sub>50</sub> =	36.0				
D <sub>84</sub> =	70.9				
D <sub>95</sub> = 113.8					
D <sub>100</sub> =	180.0				







Big Harris Creek Mitigation Site - Area B DMS Project No. 739 Monitoring Year 3 - 2020

USEC Reach 1, Reachwide

		Diame	ter (mm)	Pa	rticle Co	unt	Reach Summary	
Par	ticle Class						Class	Percent
		min	max	Riffle	Pool	Total	Percentage	Cumulative
SILT/CLAY	Silt/Clay	0.000	0.062	3	8	11	11	11
	Very fine	0.062	0.125		5	5	5	16
	Fine	0.125	0.250	4	14	18	18	34
SAND	Medium	0.25	0.50	2	7	9	9	43
Sr.	Coarse	0.5	1.0	2	4	6	6	49
	Very Coarse	1.0	2.0	1	2	3	3	52
	Very Fine	2.0	2.8					52
	Very Fine	2.8	4.0					52
	Fine	4.0	5.6	2	1	3	3	55
	Fine	5.6	8.0	1		1	1	56
.161	Medium	8.0	11.0	2		2	2	58
GRAVEL	Medium	11.0	16.0					58
Ŭ	Coarse	16.0	22.6	1		1	1	59
	Coarse	22.6	32	2	1	3	3	62
	Very Coarse	32	45	3	1	4	4	66
	Very Coarse	45	64	4	2	6	6	72
	Small	64	90	7	1	8	8	80
COBBLE	Small	90	128	2	3	5	5	85
OBU	Large	128	180	12	1	13	13	98
ŭ	Large	180	256	1		1	1	99
	Small	256	362	1		1	1	100
OER	Small	362	512					100
BOULDER	Medium	512	1024					100
<b>V</b> -	Large/Very Large	1024	2048					100
BEDROCK	Bedrock	2048	>2048					100
	•	•	Total	50	50	100	100	100

Reachwide				
Channel materials (mm)				
D <sub>16</sub> =	0.1			
D <sub>35</sub> =	0.3			
D <sub>50</sub> =	1.3			
D <sub>84</sub> =	119.3			
D <sub>95</sub> =	166.4			
D <sub>100</sub> =	362.0			





Big Harris Creek Mitigation Site - Area B


DMS Project No. 739


Monitoring Year 3 - 2020

USEC Reach 1, Cross-Section 15

		Diame	ter (mm)	Riffle 100-	Summary		
Pai	rticle Class			Count	Class	Percent	
		min	max	Count	Percentage	Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062			0	
	Very fine	0.062	0.125			0	
	Fine	0.125	0.250			0	
SAND	Medium	0.25	0.50			0	
51	Coarse	0.5	1.0	1	1	1	
	Very Coarse	1.0	2.0	9	9	10	
	Very Fine	2.0	2.8			10	
	Very Fine	2.8	4.0			10	
	Fine	4.0	5.6	4	4	14	
	Fine	5.6	8.0	5	5	19	
.1EV	Medium	8.0	11.0	3	3	22	
GRAVEL	Medium	11.0	16.0	3	3	25	
	Coarse	16.0	22.6	2	2	27	
	Coarse	22.6	32	2	2	29	
	Very Coarse	32	45	11	11	40	
	Very Coarse	45	64	10	10	50	
	Small	64	90	14	14	64	
COBBLE	Small	90	128	13	13	77	
COBP.	Large	128	180	15	15	92	
•	Large	180	256	5	5	97	
	Small	256	362	3	3	100	
OFR	Small	362	512			100	
OUL	Medium	512	1024			100	
ROULDER	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
			Total	100	100	100	

Cross-Section 15					
Channel materials (mm)					
D <sub>16</sub> =	D <sub>16</sub> = 6.5				
D <sub>35</sub> =	38.5				
D <sub>50</sub> =	64.0				
D <sub>84</sub> =	150.1				
D <sub>95</sub> =	222.4				
D <sub>100</sub> =	362.0				







Big Harris Creek Mitigation Site - Area B DMS Project No. 739 Monitoring Year 3 - 2020

USEC Reach 5, Reachwide

		Diame	ter (mm)	Pa	rticle Co	unt	Reach Summary	
Par	ticle Class						Class	Percent
		min	max	Riffle	Pool	Total	Percentage	Cumulative
SILT/CLAY	Silt/Clay	0.000	0.062		2	2	2	2
	Very fine	0.062	0.125	1	13	14	14	16
_	Fine	0.125	0.250	1	11	12	12	28
SANO	Medium	0.25	0.50	1	9	10	10	38
Sr.	Coarse	0.5	1.0	2	5	7	7	45
	Very Coarse	1.0	2.0	3	4	7	7	52
	Very Fine	2.0	2.8	3	1	4	4	56
	Very Fine	2.8	4.0	3	2	5	5	61
	Fine	4.0	5.6		3	3	3	64
	Fine	5.6	8.0					64
JEL	Medium	8.0	11.0	1		1	1	65
GRAVEL	Medium	11.0	16.0					65
ŭ	Coarse	16.0	22.6	2		2	2	67
	Coarse	22.6	32	3		3	3	70
	Very Coarse	32	45	7		7	7	77
	Very Coarse	45	64	3		3	3	80
	Small	64	90	5		5	5	85
alE	Small	90	128	5		5	5	90
COBBLE	Large	128	180	5		5	5	95
ŭ	Large	180	256	5		5	5	100
	Small	256	362					100
BOULDER	Small	362	512					100
COULT	Medium	512	1024					100
<b>V</b> -	Large/Very Large	1024	2048					100
BEDROCK	Bedrock	2048	>2048					100
	•		Total	50	50	100	100	100

Reachwide				
Channel materials (mm)				
D <sub>16</sub> =	0.1			
D <sub>35</sub> =	0.4			
D <sub>50</sub> =	1.6			
D <sub>84</sub> =	84.1			
D <sub>95</sub> =	180.0			
D <sub>100</sub> =	256.0			





Big Harris Creek Mitigation Site - Area B


DMS Project No. 739


Monitoring Year 3 - 2020

USEC Reach 5, Cross-Section 17

		Diame	ter (mm)	Riffle 100-	Summary		
Pa	rticle Class			Count	Class	Percent	
		min	max	Count	Percentage	Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062			0	
	Very fine	0.062	0.125			0	
	Fine	0.125	0.250	2	2	2	
SAND	Medium	0.25	0.50	2	2	4	
51	Coarse	0.5	1.0	10	10	14	
	Very Coarse	1.0	2.0	9	9	23	
	Very Fine	2.0	2.8	8	8	31	
	Very Fine	2.8	4.0	6	6	37	
	Fine	4.0	5.6	7	7	44	
	Fine	5.6	8.0	1	1	45	
JEL	Medium	8.0	11.0			45	
GRAVEL	Medium	11.0	16.0	2	2	47	
Ť	Coarse	16.0	22.6	2	2	49	
	Coarse	22.6	32	4	4	53	
	Very Coarse	32	45	15	15	68	
	Very Coarse	45	64	8	8	76	
	Small	64	90	10	10	86	
ale	Small	90	128	8	8	94	
CORRIE	Large	128	180	4	4	98	
·	Large	180	256	2	2	100	
	Small	256	362			100	
BOULDER	Small	362	512			100	
101/L	Medium	512	1024			100	
8	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
			Total	100	100	100	

Cross-Section 17				
Channel materials (mm)				
D <sub>16</sub> =	1.2			
D <sub>35</sub> =	3.6			
D <sub>50</sub> =	24.7			
D <sub>84</sub> =	84.1			
D <sub>95</sub> = 139.4				
D <sub>100</sub> =	256.0			





Big Harris Creek Mitigation Site - Area B


DMS Project No. 739


Monitoring Year 3 - 2020

USEC Reach 5, Cross-Section 18

		Diame	ter (mm)	Riffle 100-	Summary		
Pa	rticle Class			Count	Class	Percent	
		min	max	Count	Percentage	Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062			0	
	Very fine	0.062	0.125			0	
_	Fine	0.125	0.250	5	5	5	
SAND	Medium	0.25	0.50	7	7	12	
51	Coarse	0.5	1.0	5	5	17	
	Very Coarse	1.0	2.0	6	6	23	
	Very Fine	2.0	2.8	2	2	25	
	Very Fine	2.8	4.0			25	
	Fine	4.0	5.6	4	4	29	
	Fine	5.6	8.0			29	
.161	Medium	8.0	11.0			29	
GRAVEL	Medium	11.0	16.0			29	
	Coarse	16.0	22.6	4	4	33	
	Coarse	22.6	32	3	3	36	
	Very Coarse	32	45	11	11	47	
	Very Coarse	45	64	12	12	59	
	Small	64	90	7	7	66	
COBBLE	Small	90	128	7	7	73	
OBD.	Large	128	180	20	20	93	
·	Large	180	256	7	7	100	
	Small	256	362			100	
BOULDER	Small	362	512			100	
OUL	Medium	512	1024			100	
8	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
			Total	100	100	100	

	Cross-Section 18				
Channel materials (mm)					
D <sub>16</sub> =	D <sub>16</sub> = 0.9				
D <sub>35</sub> =	28.5				
D <sub>50</sub> =	49.1				
D <sub>84</sub> =	154.4				
D <sub>95</sub> = 199.1					
D <sub>100</sub> =	256.0				





Big Harris Creek Mitigation Site - Area B


DMS Project No. 739


Monitoring Year 3 - 2020

USEC Reach 5, Cross-Section 20

		Diame	ter (mm)	Riffle 100-	Summary		
Pa	rticle Class			Count	Class	Percent	
		min	max	Count	Percentage	Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062			0	
	Very fine	0.062	0.125			0	
_	Fine	0.125	0.250	3	3	3	
SAND	Medium	0.25	0.50	2	2	5	
51	Coarse	0.5	1.0	2	2	7	
	Very Coarse	1.0	2.0	6	6	13	
	Very Fine	2.0	2.8	2	2	15	
	Very Fine	2.8	4.0			15	
	Fine	4.0	5.6	1	1	16	
	Fine	5.6	8.0			16	
JEL	Medium	8.0	11.0			16	
GRAVEL	Medium	11.0	16.0	1	1	17	
Ŭ	Coarse	16.0	22.6	3	3	20	
	Coarse	22.6	32	3	3	23	
	Very Coarse	32	45	19	19	42	
	Very Coarse	45	64	12	12	54	
	Small	64	90	16	16	70	
CORRIE	Small	90	128	7	7	77	
OBV	Large	128	180	17	17	94	
·	Large	180	256	3	3	97	
	Small	256	362	3	3	100	
ROUIDER	Small	362	512			100	
contr	Medium	512	1024			100	
₩.	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
	•		Total	100	100	100	

Cross-Section 20				
Channel materials (mm)				
D <sub>16</sub> =	5.6			
D <sub>35</sub> =	39.7			
D <sub>50</sub> =	56.9			
D <sub>84</sub> =	147.3			
D <sub>95</sub> =	202.4			
D <sub>100</sub> =	362.0			







Big Harris Creek Mitigation Site - Area B DMS Project No. 739 Monitoring Year 3 - 2020

USEC Reach 6, Reachwide

		Diame	ter (mm)	Pa	rticle Co	unt	Reach S	ummary
Par	ticle Class						Class	Percent
		min	max	Riffle	Pool	Total	Percentage	Cumulative
SILT/CLAY	Silt/Clay	0.000	0.062	1	10	11	11	11
	Very fine	0.062	0.125		7	7	7	18
	Fine	0.125	0.250	1	10	11	11	29
SANO	Medium	0.25	0.50	1	10	11	11	40
Sr.	Coarse	0.5	1.0		3	3	3	43
	Very Coarse	1.0	2.0	3	3	6	6	49
	Very Fine	2.0	2.8	1		1	1	50
	Very Fine	2.8	4.0	1	1	2	2	52
	Fine	4.0	5.6					52
	Fine	5.6	8.0	1		1	1	53
JEL	Medium	8.0	11.0	1		1	1	54
GRAVEL	Medium	11.0	16.0	1		1	1	55
ŭ	Coarse	16.0	22.6	1	2	3	3	58
	Coarse	22.6	32	3	1	4	4	62
	Very Coarse	32	45	4	1	5	5	67
	Very Coarse	45	64	6	1	7	7	74
	Small	64	90	7	1	8	8	82
COBBLE	Small	90	128	8		8	8	90
OBL	Large	128	180	6		6	6	96
ŭ	Large	180	256	4		4	4	100
	Small	256	362					100
. OER	Small	362	512					100
BOULDER	Medium	512	1024					100
ν-	Large/Very Large	1024	2048					100
BEDROCK	Bedrock	2048	>2048					100
	•	•	Total	50	50	100	100	100

Reachwide				
Channel materials (mm)				
D <sub>16</sub> =	0.1			
D <sub>35</sub> =	0.4			
D <sub>50</sub> =	2.8			
D <sub>84</sub> =	98.3			
D <sub>95</sub> =	170.1			
D <sub>100</sub> =	256.0			





Big Harris Creek Mitigation Site - Area B


DMS Project No. 739


Monitoring Year 3 - 2020

USEC Reach 6, Cross-Section 22

Particle Class		Diame	ter (mm)	Riffle 100-	Summary		
				Count	Class	Percent	
		min	max	Count	Percentage	Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062	2	2	2	
	Very fine	0.062	0.125	1	1	3	
	Fine	0.125	0.250	5	5	8	
SANO	Medium	0.25	0.50	10	10	18	
5'	Coarse	0.5	1.0			18	
	Very Coarse	1.0	2.0	1	1	19	
	Very Fine	2.0	2.8			19	
	Very Fine	2.8	4.0			19	
	Fine	4.0	5.6			19	
	Fine	5.6	8.0	1	1	20	
181	Medium	8.0	11.0			20	
GRAVEL	Medium	11.0	16.0	4	4	24	
·	Coarse	16.0	22.6	6	6	30	
	Coarse	22.6	32	3	3	33	
	Very Coarse	32	45	18	18	51	
	Very Coarse	45	64	8	8	59	
	Small	64	90	8	8	67	
COBBLE	Small	90	128	19	19	86	
OBD	Large	128	180	12	12	98	
•	Large	180	256			98	
	Small	256	362	2	2	100	
BOULDER	Small	362	512			100	
201/1	Medium	512	1024			100	
<b>v</b>	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
	•	•	Total	100	100	100	

Cross-Section 22				
Channel materials (mm)				
D <sub>16</sub> = 0.4				
D <sub>35</sub> =	33.2			
D <sub>50</sub> =	44.2			
D <sub>84</sub> =	123.3			
D <sub>95</sub> =	165.3			
D <sub>100</sub> =	362.0			





Big Harris Creek Mitigation Site - Area B


DMS Project No. 739


Monitoring Year 3 - 2020

USEC Reach 6, Cross-Section 23

Particle Class		Diame	ter (mm)	Riffle 100-	Summary		
				Count	Class	Percent	
		min	max	Count	Percentage	Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062	2	2	2	
	Very fine	0.062	0.125	2	2	4	
	Fine	0.125	0.250	3	3	7	
SAND	Medium	0.25	0.50	2	2	9	
51	Coarse	0.5	1.0			9	
	Very Coarse	1.0	2.0	7	7	16	
	Very Fine	2.0	2.8	2	2	18	
	Very Fine	2.8	4.0	7	7	25	
	Fine	4.0	5.6			25	
	Fine	5.6	8.0	1	1	26	
.161	Medium	8.0	11.0	1	1	27	
GRAVEL	Medium	11.0	16.0	4	4	31	
·	Coarse	16.0	22.6	2	2	33	
	Coarse	22.6	32	11	11	44	
	Very Coarse	32	45	7	7	51	
	Very Coarse	45	64	17	17	68	
	Small	64	90	9	9	77	
COBBLE	Small	90	128	4	4	81	
COBE	Large	128	180	14	14	95	
•	Large	180	256	3	3	98	
	Small	256	362	2	2	100	
BOULDER	Small	362	512			100	
201/17	Medium	512	1024			100	
φ.	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
	•	•	Total	100	100	100	

Cross-Section 23				
Channel materials (mm)				
D <sub>16</sub> = 2.0				
D <sub>35</sub> =	24.1			
D <sub>50</sub> =	42.9			
D <sub>84</sub> =	137.7			
D <sub>95</sub> =	180.0			
D <sub>100</sub> =	362.0			







Big Harris Creek Mitigation Site - Area B DMS Project No. 739 Monitoring Year 3 - 2020

Elliott Creek, Reachwide

		Diame	ter (mm)	Particle Count			Reach Summary	
Par	ticle Class						Class	Percent
		min	max	Riffle	Pool	Total	Percentage	Cumulative
SILT/CLAY	Silt/Clay	0.000	0.062		2	2	2	2
	Very fine	0.062	0.125					2
	Fine	0.125	0.250		1	1	1	3
SAND	Medium	0.25	0.50		1	1	1	4
Sr.	Coarse	0.5	1.0		3	3	3	7
	Very Coarse	1.0	2.0	1	4	5	5	12
	Very Fine	2.0	2.8	3	11	14	14	26
	Very Fine	2.8	4.0	1	13	14	14	40
	Fine	4.0	5.6	4	3	7	7	47
	Fine	5.6	8.0	3	2	5	5	52
JEL	Medium	8.0	11.0	5		5	5	57
GRAVEL	Medium	11.0	16.0	5	1	6	6	63
Ŭ	Coarse	16.0	22.6	8	2	10	10	73
	Coarse	22.6	32	9	3	12	12	85
	Very Coarse	32	45	8	3	11	11	96
	Very Coarse	45	64	2		2	2	98
	Small	64	90	1		1	1	99
COBBLE	Small	90	128					99
OBU	Large	128	180		1	1	1	100
Ĭ	Large	180	256					100
	Small	256	362					100
OER	Small	362	512					100
BOULDER	Medium	512	1024					100
ν-	Large/Very Large	1024	2048					100
BEDROCK	Bedrock	2048	>2048					100
	•		Total	50	50	100	100	100

Reachwide				
Channel materials (mm)				
D <sub>16</sub> =	2.2			
D <sub>35</sub> =	3.5			
D <sub>50</sub> =	6.9			
D <sub>84</sub> =	31.1			
D <sub>95</sub> =	43.6			
D <sub>100</sub> =	180.0			





Big Harris Creek Mitigation Site - Area B


DMS Project No. 739


Monitoring Year 3 - 2020

Elliott Creek, Cross-Section 24

		Diame	ter (mm)	Riffle 100-	Summary		
Pai	rticle Class			Count	Class	Percent	
		min	max	Count	Percentage	Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062			0	
	Very fine	0.062	0.125			0	
_	Fine	0.125	0.250			0	
SAND	Medium	0.25	0.50			0	
5'	Coarse	0.5	1.0	2	2	2	
	Very Coarse	1.0	2.0	2	2	4	
	Very Fine	2.0	2.8	3	3	7	
	Very Fine	2.8	4.0	8	8	15	
	Fine	4.0	5.6	12	12	27	
	Fine	5.6	8.0	5	5	32	
.161	Medium	8.0	11.0	12	12	44	
GRAVEL	Medium	11.0	16.0	9	9	53	
Ü	Coarse	16.0	22.6	18	18	71	
	Coarse	22.6	32	17	17	88	
	Very Coarse	32	45	8	8	96	
	Very Coarse	45	64	1	1	97	
	Small	64	90	2	2	99	
COBBLE	Small	90	128			99	
COBP	Large	128	180	1	1	100	
v	Large	180	256			100	
	Small	256	362			100	
OER.	Small	362	512			100	
-Only	Medium	512	1024			100	
BOULDER	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
			Total	100	100	100	

Cross-Section 24				
Channel materials (mm)				
D <sub>16</sub> =	4.1			
D <sub>35</sub> =	8.7			
D <sub>50</sub> =	14.1			
D <sub>84</sub> =	29.5			
D <sub>95</sub> =	43.1			
D <sub>100</sub> =	180.0			





Big Harris Creek Mitigation Site - Area B


DMS Project No. 739


Monitoring Year 3 - 2020

Elliott Creek, Cross-Section 26

		Diame	ter (mm)	Riffle 100-	Summary		
Pai	rticle Class			Count	Class	Percent	
		min	max	Count	Percentage	Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062	1	1	1	
	Very fine	0.062	0.125			1	
_	Fine	0.125	0.250			1	
SAND	Medium	0.25	0.50			1	
5'	Coarse	0.5	1.0			1	
	Very Coarse	1.0	2.0			1	
	Very Fine	2.0	2.8	2	2	3	
	Very Fine	2.8	4.0	7	7	10	
	Fine	4.0	5.6	10	10	20	
	Fine	5.6	8.0	17	17	37	
GRAVEL	Medium	8.0	11.0	13	13	50	
GRAV	Medium	11.0	16.0	8	8	58	
	Coarse	16.0	22.6	9	9	67	
	Coarse	22.6	32	12	12	79	
	Very Coarse	32	45	13	13	92	
	Very Coarse	45	64	8	8	100	
	Small	64	90			100	
COBBLE	Small	90	128			100	
OBU	Large	128	180			100	
·	Large	180	256			100	
	Small	256	362			100	
.OER	Small	362	512			100	
BOULDER	Medium	512	1024			100	
•	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
	<u> </u>		Total	100	100	100	

Cross-Section 26					
Channel materials (mm)					
D <sub>16</sub> =	4.9				
D <sub>35</sub> =	7.7				
D <sub>50</sub> =	11.0				
D <sub>84</sub> =	36.5				
D <sub>95</sub> =	51.4				
D <sub>100</sub> =	64.0				







Big Harris Creek Mitigation Site - Area B DMS Project No. 739 Monitoring Year 3 - 2020

Elliott Creek UT1, Reachwide

		Diame	ter (mm)	Pa	rticle Co	unt	Reach Summary	
Par	ticle Class						Class	Percent
		min	max	Riffle	Pool	Total	Percentage	Cumulative
SILT/CLAY	Silt/Clay	0.000	0.062	3	6	9	9	9
	Very fine	0.062	0.125					9
	Fine	0.125	0.250	1	3	4	4	13
SAND	Medium	0.25	0.50	2	1	3	3	16
51	Coarse	0.5	1.0	1	2	3	3	19
	Very Coarse	1.0	2.0	4	5	9	9	28
	Very Fine	2.0	2.8	7	12	19	19	47
	Very Fine	2.8	4.0	5	5	10	10	57
	Fine	4.0	5.6	9	3	12	12	69
	Fine	5.6	8.0	5	4	9	9	78
JEL	Medium	8.0	11.0	6	1	7	7	85
GRAVEL	Medium	11.0	16.0	4	6	10	10	95
Ü	Coarse	16.0	22.6	1	1	2	2	97
	Coarse	22.6	32	1	1	2	2	99
	Very Coarse	32	45	1		1	1	100
	Very Coarse	45	64					100
	Small	64	90					100
CORRIE	Small	90	128					100
COBB	Large	128	180					100
ŭ	Large	180	256					100
	Small	256	362					100
BOULDER	Small	362	512					100
court	Medium	512	1024					100
₩.	Large/Very Large	1024	2048					100
BEDROCK	Bedrock	2048	>2048					100
	•		Total	50	50	100	100	100

Reachwide					
Channel materials (mm)					
D <sub>16</sub> =	0.50				
D <sub>35</sub> =	2.26				
D <sub>50</sub> =	3.1				
D <sub>84</sub> =	10.5				
D <sub>95</sub> =	16.0				
D <sub>100</sub> =	45.0				





Big Harris Creek Mitigation Site - Area B


DMS Project No. 739


Monitoring Year 3 - 2020

Elliott Creek UT1, Cross-Section 27

Particle Class		Diame	ter (mm)	Riffle 100-	Summary		
				Count	Class	Percent	
		min	max	Count	Percentage	Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062	5	5	5	
	Very fine	0.062	0.125			5	
	Fine	0.125	0.250			5	
SAND	Medium	0.25	0.50	1	1	6	
5'	Coarse	0.5	1.0	4	4	10	
	Very Coarse	1.0	2.0	15	15	25	
	Very Fine	2.0	2.8	18	18	43	
	Very Fine	2.8	4.0	22	22	65	
	Fine	4.0	5.6	9	9	74	
	Fine	5.6	8.0	5	5	79	
181	Medium	8.0	11.0	3	3	82	
GRAVEL	Medium	11.0	16.0	8	8	90	
	Coarse	16.0	22.6	4	4	94	
	Coarse	22.6	32	4	4	98	
	Very Coarse	32	45	1	1	99	
	Very Coarse	45	64	1	1	100	
	Small	64	90			100	
ale	Small	90	128			100	
COBBLE	Large	128	180			100	
J	Large	180	256			100	
	Small	256	362			100	
BOULDER	Small	362	512			100	
	Medium	512	1024			100	
	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
	•		Total	100	100	100	

	Cross-Section 27					
Channel materials (mm)						
D <sub>16</sub> =	1.32					
D <sub>35</sub> =	2.4					
D <sub>50</sub> =	3.1					
D <sub>84</sub> =	12.1					
D <sub>95</sub> =	24.7					
D <sub>100</sub> =	64.0					







Big Harris Creek Mitigation Site - Area B DMS Project No. 739 Monitoring Year 3 - 2020

Bridges Creek R1, Reachwide

		Diame	ter (mm)	Particle Count			Reach Summary	
Par	ticle Class						Class	Percent
		min	max	Riffle	Pool	Total	Percentage	Cumulative
SILT/CLAY	Silt/Clay	0.000	0.062	1	12	13	13	13
	Very fine	0.062	0.125					13
	Fine	0.125	0.250					13
SAND	Medium	0.25	0.50		1	1	1	14
Sr.	Coarse	0.5	1.0					14
	Very Coarse	1.0	2.0	2	2	4	4	18
	Very Fine	2.0	2.8	4	3	7	7	25
	Very Fine	2.8	4.0	4	3	7	7	32
	Fine	4.0	5.6	1	4	5	5	37
	Fine	5.6	8.0	1	1	2	2	39
JEL	Medium	8.0	11.0	3	2	5	5	44
GRAVEL	Medium	11.0	16.0	7	4	11	11	55
Ü	Coarse	16.0	22.6	6	6	12	12	67
	Coarse	22.6	32	10	3	13	13	80
	Very Coarse	32	45	7	4	11	11	91
	Very Coarse	45	64	3	2	5	5	96
	Small	64	90		1	1	1	97
COBBLE	Small	90	128	1	2	3	3	100
COBE	Large	128	180					100
ŭ	Large	180	256					100
	Small	256	362					100
DER	Small	362	512					100
BOULDER	Medium	512	1024					100
<b>V</b> -	Large/Very Large	1024	2048					100
BEDROCK	Bedrock	2048	>2048					100
	*		Total	50	50	100	100	100

Reachwide					
Channel materials (mm)					
D <sub>16</sub> =	1.41				
D <sub>35</sub> =	4.9				
D <sub>50</sub> =	13.5				
D <sub>84</sub> =	36.2				
D <sub>95</sub> =	59.6				
D <sub>100</sub> =	128.0				





Big Harris Creek Mitigation Site - Area B


DMS Project No. 739


Monitoring Year 3 - 2020

Bridges Creek R1, Cross-Section 28

		Diame	ter (mm)	Riffle 100-	Summary		
Par	ticle Class			Count	Class	Percent	
		min	max	Count	Percentage	Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062	6	6	6	
	Very fine	0.062	0.125			6	
•	Fine	0.125	0.250			6	
SAND	Medium	0.25	0.50	2	2	8	
۵,	Coarse	0.5	1.0	1	1	9	
	Very Coarse	1.0	2.0	5	5	14	
	Very Fine	2.0	2.8	4	4	18	
	Very Fine	2.8	4.0	6	6	24	
	Fine	4.0	5.6	2	2	26	
	Fine	5.6	8.0	7	7	33	
JEL	Medium	8.0	11.0	7	7	40	
GRAVEL	Medium	11.0	16.0	16	16	56	
-	Coarse	16.0	22.6	13	13	69	
	Coarse	22.6	32	10	10	79	
	Very Coarse	32	45	11	11	90	
	Very Coarse	45	64	5	5	95	
	Small	64	90	5	5	100	
RLE	Small	90	128			100	
COBBLE	Large	128	180			100	
-	Large	180	256			100	
	Small	256	362			100	
ROULDER	Small	362	512			100	
	Medium	512	1024			100	
v	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
			Total	100	100	100	

	Cross-Section 28						
Channel materials (mm)							
D <sub>16</sub> =	2.4						
D <sub>35</sub> =	8.8						
D <sub>50</sub> =	13.9						
D <sub>84</sub> =	37.4						
D <sub>95</sub> =	64.0						
D <sub>100</sub> =	90.0						







Big Harris Creek Mitigation Site - Area B DMS Project No. 739 Monitoring Year 3 - 2020

USEC UT2, Reachwide

		Diame	ter (mm)	Pa	rticle Co	unt	Reach Summary	
Par	ticle Class						Class	Percent
		min	max	Riffle	Pool	Total	Percentage	Cumulative
SILT/CLAY	Silt/Clay	0.000	0.062	2	6	8	8	8
	Very fine	0.062	0.125	18	19	37	37	45
	Fine	0.125	0.250	7	14	21	21	66
SAND	Medium	0.25	0.50	1	7	8	8	74
21	Coarse	0.5	1.0	1	2	3	3	77
	Very Coarse	1.0	2.0	4	1	5	5	82
	Very Fine	2.0	2.8					82
	Very Fine	2.8	4.0	1		1	1	83
	Fine	4.0	5.6	1		1	1	84
	Fine	5.6	8.0	5		5	5	89
JEL	Medium	8.0	11.0	5	1	6	6	95
GRAVEL	Medium	11.0	16.0	3		3	3	98
Ŭ	Coarse	16.0	22.6	1		1	1	99
	Coarse	22.6	32	1		1	1	100
	Very Coarse	32	45					100
	Very Coarse	45	64					100
	Small	64	90					100
alE	Small	90	128					100
CORRIE	Large	128	180					100
·	Large	180	256					100
	Small	256	362					100
DER	Small	362	512					100
BOULDER	Medium	512	1024					100
ν-	Large/Very Large	1024	2048					100
BEDROCK	Bedrock	2048	>2048					100
	*		Total	50	50	100	100	100

Reachwide					
Channel materials (mm)					
D <sub>16</sub> =	0.1				
D <sub>35</sub> =	0.1				
D <sub>50</sub> =	0.1				
D <sub>84</sub> =	5.6				
D <sub>95</sub> =	11.0				
D <sub>100</sub> =	32.0				





Big Harris Creek Mitigation Site - Area B


DMS Project No. 739


Monitoring Year 3 - 2020

USEC UT2, Cross-Section 29

·		Diameter (mm)		Riffle 100-	Summary		
Pai	rticle Class			Count	Class	Percent	
		min	max	Count	Percentage	Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062	3	3	3	
	Very fine	0.062	0.125	11	11	14	
	Fine	0.125	0.250	10	10	24	
SAND	Medium	0.25	0.50	15	15	39	
51	Coarse	0.5	1.0	27	27	66	
	Very Coarse	1.0	2.0	5	5	71	
	Very Fine	2.0	2.8			71	
	Very Fine	2.8	4.0			71	
	Fine	4.0	5.6	1	1	72	
	Fine	5.6	8.0			72	
,EL	Medium	8.0	11.0	3	3	75	
GRAVEL	Medium	11.0	16.0	3	3	78	
	Coarse	16.0	22.6	10	10	88	
	Coarse	22.6	32	6	6	94	
	Very Coarse	32	45	2	2	96	
	Very Coarse	45	64	4	4	100	
	Small	64	90			100	
NE.	Small	90	128			100	
COBBLE	Large	128	180			100	
V	Large	180	256			100	
	Small	256	362			100	
OER	Small	362	512			100	
ROULDER	Medium	512	1024			100	
8	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
	•		Total	100	100	100	

Cross-Section 29				
Channel materials (mm)				
D <sub>16</sub> = 0.1				
D <sub>35</sub> =	0.4			
D <sub>50</sub> =	0.7			
D <sub>84</sub> =	19.7			
D <sub>95</sub> = 37.9				
D <sub>100</sub> =	64.0			







Big Harris Creek Mitigation Site - Area B DMS Project No. 739 Monitoring Year 3 - 2020

USEC UT3, Reachwide

		Diame	ter (mm)	Particle Count			Reach Summary	
Particle Class							Class	Percent
		min	max	Riffle	Pool	Total	Percentage	Cumulative
SILT/CLAY	Silt/Clay	0.000	0.062	3	28	31	31	31
	Very fine	0.062	0.125	2	13	15	15	46
	Fine	0.125	0.250	3	3	6	6	52
SAND	Medium	0.25	0.50	3	3	6	6	58
2,	Coarse	0.5	1.0	3		3	3	61
	Very Coarse	1.0	2.0		1	1	1	62
	Very Fine	2.0	2.8					62
	Very Fine	2.8	4.0	1		1	1	63
	Fine	4.0	5.6	1		1	1	64
	Fine	5.6	8.0	3		3	3	67
JEL	Medium	8.0	11.0					67
GRAVEL	Medium	11.0	16.0	5	1	6	6	73
Ŭ	Coarse	16.0	22.6	6		6	6	79
	Coarse	22.6	32	6	1	7	7	86
	Very Coarse	32	45	5		5	5	91
	Very Coarse	45	64	6		6	6	97
	Small	64	90	1		1	1	98
alE	Small	90	128	1		1	1	99
COBBLE	Large	128	180	1		1	1	100
·	Large	180	256					100
	Small	256	362					100
DER	Small	362	512					100
BOULDER	Medium	512	1024					100
ν-	Large/Very Large	1024	2048					100
BEDROCK	Bedrock	2048	>2048					100
	*		Total	50	50	100	100	100

Reachwide				
Channel materials (mm)				
D <sub>16</sub> =	Silt/Clay			
D <sub>35</sub> =	0.1			
D <sub>50</sub> =	0.2			
D <sub>84</sub> =	29.0			
D <sub>95</sub> = 56.9				
D <sub>100</sub> =	180.0			





Big Harris Creek Mitigation Site - Area B


DMS Project No. 739


Monitoring Year 3 - 2020

USEC UT3, Cross-Section 30

		Diame	ter (mm)	Riffle 100-	Summary		
Pai	rticle Class	min	max	Count	Class Percentage	Percent Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062	22	22	22	
	Very fine	0.062	0.125			22	
	Fine	0.125	0.250			22	
SANO	Medium	0.25	0.50			22	
Sr	Coarse	0.5	1.0			22	
	Very Coarse	1.0	2.0			22	
	Very Fine	2.0	2.8			22	
	Very Fine	2.8	4.0			22	
	Fine	4.0	5.6			22	
	Fine	5.6	8.0	1	1	23	
JEL	Medium	8.0	11.0	4	4	27	
GRAVEL	Medium	11.0	16.0	9	9	36	
Ŭ	Coarse	16.0	22.6	24	24	60	
	Coarse	22.6	32	19	19	79	
	Very Coarse	32	45	8	8	87	
	Very Coarse	45	64	3	3	90	
	Small	64	90	5	5	95	
ale	Small	90	128	5	5	100	
COBBLE	Large	128	180			100	
•	Large	180	256			100	
	Small	256	362			100	
BOULDER	Small	362	512			100	
2011	Medium	512	1024			100	
ν-	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
•			Total	100	100	100	

Cross-Section 30				
Channel materials (mm)				
D <sub>16</sub> =	Silt/Clay			
D <sub>35</sub> =	15.3			
D <sub>50</sub> =	19.6			
D <sub>84</sub> =	39.6			
D <sub>95</sub> = 90.0				
D <sub>100</sub> =	128.0			







Big Harris Creek Mitigation Site - Area B DMS Project No. 739 Monitoring Year 3 - 2020

UFC Reach 2, Reachwide

		Diame	ter (mm)	Particle Count			Reach Summary	
Particle Class							Class	Percent
		min	max	Riffle	Pool	Total	Percentage	Cumulative
SILT/CLAY	Silt/Clay	0.000	0.062		1	1	1	1
	Very fine	0.062	0.125		9	9	9	10
	Fine	0.125	0.250	1	6	7	7	17
SAND	Medium	0.25	0.50		13	13	13	30
2,	Coarse	0.5	1.0	5	10	15	15	45
	Very Coarse	1.0	2.0		4	4	4	49
	Very Fine	2.0	2.8					49
	Very Fine	2.8	4.0	1	1	2	2	51
	Fine	4.0	5.6		1	1	1	52
	Fine	5.6	8.0	2	1	3	3	55
JEL	Medium	8.0	11.0	1		1	1	56
GRAVEL	Medium	11.0	16.0		1	1	1	57
•	Coarse	16.0	22.6	1		1	1	58
	Coarse	22.6	32	3		3	3	61
	Very Coarse	32	45	6		6	6	67
	Very Coarse	45	64	6	2	8	8	75
	Small	64	90	9		9	9	84
COBBLE	Small	90	128	8	1	9	9	93
CORP	Large	128	180	3		3	3	96
•	Large	180	256	3		3	3	99
	Small	256	362	1		1	1	100
OER	Small	362	512					100
BOULDER	Medium	512	1024					100
φ.	Large/Very Large	1024	2048					100
BEDROCK	Bedrock	2048	>2048					100
	•		Total	50	50	100	100	100

Reachwide				
Channel materials (mm)				
D <sub>16</sub> =	0.2			
D <sub>35</sub> =	0.6			
D <sub>50</sub> =	3.3			
D <sub>84</sub> =	90.0			
D <sub>95</sub> =	160.7			
D <sub>100</sub> =	362.0			





Big Harris Creek Mitigation Site - Area B


DMS Project No. 739


Monitoring Year 3 - 2020

UFC Reach 2, Cross-Section 31

		Diame	ter (mm)	Riffle 100-	Summary		
Pai	rticle Class			Count	Class	Percent	
		min	max		Percentage	Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062			0	
	Very fine	0.062	0.125			0	
	Fine	0.125	0.250	7	7	7	
SAND	Medium	0.25	0.50	9	9	16	
'ל	Coarse	0.5	1.0	6	6	22	
	Very Coarse	1.0	2.0	2	2	24	
	Very Fine	2.0	2.8			24	
	Very Fine	2.8	4.0			24	
	Fine	4.0	5.6			24	
	Fine	5.6	8.0	2	2	26	
.1EV	Medium	8.0	11.0	1	1	27	
GRAVEL	Medium	11.0	16.0	2	2	29	
	Coarse	16.0	22.6	5	5	34	
	Coarse	22.6	32	9	9	43	
	Very Coarse	32	45	16	16	59	
	Very Coarse	45	64	11	11	70	
	Small	64	90	16	16	86	
COBBLE	Small	90	128	13	13	99	
COBP.	Large	128	180	1	1	100	
v	Large	180	256			100	
	Small	256	362			100	
OER.	Small	362	512			100	
WILL	Medium	512	1024			100	
BOULDER	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
	****		Total	100	100	100	

	Cross-Section 31				
Channel materials (mm)					
D <sub>16</sub> = 0.5					
D <sub>35</sub> =	23.5				
D <sub>50</sub> =	37.1				
D <sub>84</sub> =	86.2				
D <sub>95</sub> =	114.9				
D <sub>100</sub> =	180.0				





Big Harris Creek Mitigation Site - Area B


DMS Project No. 739


Monitoring Year 3 - 2020

UFC Reach 2, Cross-Section 34

		Diame	ter (mm)	Riffle 100-	Summary		
Pai	rticle Class			Count	Class	Percent	
		min	max	Count	Percentage	Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062			0	
	Very fine	0.062	0.125			0	
	Fine	0.125	0.250			0	
SAND	Medium	0.25	0.50			0	
5'	Coarse	0.5	1.0			0	
	Very Coarse	1.0	2.0			0	
	Very Fine	2.0	2.8			0	
	Very Fine	2.8	4.0			0	
	Fine	4.0	5.6	2	2	2	
	Fine	5.6	8.0	6	6	8	
JEL	Medium	8.0	11.0	5	5	13	
GRAVEL	Medium	11.0	16.0	2	2	15	
Ü	Coarse	16.0	22.6	5	5	20	
	Coarse	22.6	32	6	6	26	
	Very Coarse	32	45	12	12	38	
	Very Coarse	45	64	15	15	53	
	Small	64	90	20	20	73	
COBBLE	Small	90	128	19	19	92	
OBL	Large	128	180	5	5	97	
·	Large	180	256	2	2	99	
	Small	256	362	1	1	100	
.OER	Small	362	512			100	
BOULDER	Medium	512	1024			100	
φ-	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
	•	•	Total	100	100	100	

Cross-Section 34				
Channel materials (mm)				
D <sub>16</sub> = 17.1				
D <sub>35</sub> =	41.3			
D <sub>50</sub> =	59.6			
D <sub>84</sub> =	110.4			
D <sub>95</sub> = 157.1				
D <sub>100</sub> =	362.0			





Big Harris Creek Mitigation Site - Area B


DMS Project No. 739


Monitoring Year 3 - 2020

UFC Reach 2, Cross-Section 35

		Diame	ter (mm)	Riffle 100-	Summary		
Pai	Particle Class			Count	Class	Percent	
		min	max	Count	Percentage	Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062			0	
	Very fine	0.062	0.125			0	
_	Fine	0.125	0.250	7	7	7	
SAND	Medium	0.25	0.50			7	
51	Coarse	0.5	1.0	5	5	12	
	Very Coarse	1.0	2.0	1	1	13	
	Very Fine	2.0	2.8	2	2	15	
	Very Fine	2.8	4.0	1	1	16	
	Fine	4.0	5.6	2	2	18	
GRAVEL	Fine	5.6	8.0	5	5	23	
	Medium	8.0	11.0	1	1	24	
	Medium	11.0	16.0	7	7	31	
	Coarse	16.0	22.6	2	2	33	
	Coarse	22.6	32	2	2	35	
	Very Coarse	32	45	7	7	42	
	Very Coarse	45	64	5	5	47	
	Small	64	90	22	22	69	
COBBLE	Small	90	128	15	15	84	
OBV	Large	128	180	13	13	97	
•	Large	180	256	1	1	98	
	Small	256	362	1	1	99	
OFR	Small	362	512	1	1	100	
ROULDER	Medium	512	1024			100	
	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
			Total	100	100	100	

Cr	Cross-Section 35					
Channel materials (mm)						
D <sub>16</sub> =	4.0					
D <sub>35</sub> =	32.0					
D <sub>50</sub> =	67.0					
D <sub>84</sub> =	128.0					
D <sub>95</sub> =	170.8					
D <sub>100</sub> =	512.0					







Big Harris Creek Mitigation Site - Area B DMS Project No. 739 Monitoring Year 3 - 2020

LFC Reach 1, Reachwide

		Diame	ter (mm)	Pa	rticle Co	unt	Reach Summary	
Par	ticle Class						Class	Percent
		min	max	Riffle	Pool	Total	Percentage	Cumulative
SILT/CLAY	Silt/Clay	0.000	0.062	1	1	2	2	2
	Very fine	0.062	0.125		1	1	1	3
	Fine	0.125	0.250	1	7	8	8	11
SAND	Medium	0.25	0.50	2	13	15	15	26
21	Coarse	0.5	1.0		10	10	10	36
	Very Coarse	1.0	2.0		5	5	5	41
	Very Fine	2.0	2.8					41
	Very Fine	2.8	4.0					41
	Fine	4.0	5.6					41
	Fine	5.6	8.0					41
JEL	Medium	8.0	11.0	3	1	4	4	45
GRAVEL	Medium	11.0	16.0	5	5	10	10	55
Ŭ	Coarse	16.0	22.6	5	2	7	7	62
	Coarse	22.6	32	5	1	6	6	68
	Very Coarse	32	45	6		6	6	74
	Very Coarse	45	64	12		12	12	86
	Small	64	90	6	1	7	7	93
CORRIE	Small	90	128	4	3	7	7	100
CORP	Large	128	180					100
·	Large	180	256					100
	Small	256	362					100
DER	Small	362	512					100
BOULDER	Medium	512	1024					100
ν-	Large/Very Large	1024	2048					100
BEDROCK	Bedrock	2048	>2048					100
	*		Total	50	50	100	100	100

Reachwide					
Channel materials (mm)					
D <sub>16</sub> =	0.3				
D <sub>35</sub> =	0.9				
D <sub>50</sub> =	13.3				
D <sub>84</sub> =	60.4				
D <sub>95</sub> =	99.5				
D <sub>100</sub> =	128.0				





Big Harris Creek Mitigation Site - Area B


DMS Project No. 739


Monitoring Year 3 - 2020

LFC Reach 1, Cross-Section 37

			ter (mm)	Riffle 100-	Summary		
Particle Class		min	max	Count	Class Percentage	Percent Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062	2	2	2	
	Very fine	0.062	0.125			2	
	Fine	0.125	0.250	2	2	4	
SAND	Medium	0.25	0.50			4	
Sr	Coarse	0.5	1.0	2	2	6	
	Very Coarse	1.0	2.0			6	
	Very Fine	2.0	2.8			6	
	Very Fine	2.8	4.0			6	
	Fine	4.0	5.6			6	
	Fine	5.6	8.0			6	
GRAVEL	Medium	8.0	11.0	1	1	7	
	Medium	11.0	16.0	8	8	15	
	Coarse	16.0	22.6	14	14	29	
	Coarse	22.6	32	20	20	49	
	Very Coarse	32	45	16	16	65	
	Very Coarse	45	64	14	14	79	
	Small	64	90	8	8	87	
COBBLE	Small	90	128	3	3	90	
COBL	Large	128	180	6	6	96	
•	Large	180	256	4	4	100	
	Small	256	362			100	
BOULDER	Small	362	512			100	
	Medium	512	1024			100	
	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
<u> </u>			Total	100	100	100	

Cross-Section 37						
Channel materials (mm)						
D <sub>16</sub> =	16.4					
D <sub>35</sub> =	25.1					
D <sub>50</sub> =	32.7					
D <sub>84</sub> =	79.2					
D <sub>95</sub> =	170.1					
D <sub>100</sub> =	256.0					







Big Harris Creek Mitigation Site - Area B DMS Project No. 739 Monitoring Year 3 - 2020

LFC Reach 2, Reachwide

		Diame	ter (mm)	Particle Count			Reach Summary	
Par	ticle Class						Class	Percent
		min	max	Riffle	Pool	Total	Percentage	Cumulative
SILT/CLAY	Silt/Clay	0.000	0.062					0
	Very fine	0.062	0.125	4	9	13	13	13
	Fine	0.125	0.250	2	17	19	19	32
SAND	Medium	0.25	0.50	2	7	9	9	41
Sr.	Coarse	0.5	1.0	3	2	5	5	46
	Very Coarse	1.0	2.0		2	2	2	48
	Very Fine	2.0	2.8					48
	Very Fine	2.8	4.0					48
	Fine	4.0	5.6	2		2	2	50
	Fine	5.6	8.0	1	2	3	3	53
JEL	Medium	8.0	11.0		1	1	1	54
GRAVEL	Medium	11.0	16.0	3	1	4	4	58
Ŭ	Coarse	16.0	22.6	4	1	5	5	63
	Coarse	22.6	32	3	1	4	4	67
	Very Coarse	32	45	4	1	5	5	72
	Very Coarse	45	64	6	1	7	7	79
	Small	64	90	4	2	6	6	85
alE	Small	90	128	4	1	5	5	90
COBBLE	Large	128	180	2		2	2	92
•	Large	180	256	3		3	3	95
	Small	256	362	2	1	3	3	98
. DER	Small	362	512	1		1	1	99
BOULDER	Medium	512	1024				_	99
ν-	Large/Very Large	1024	2048					99
BEDROCK	Bedrock	2048	>2048		1	1	1	100
	•	•	Total	50	50	100	100	100

Reachwide					
Channel materials (mm)					
D <sub>16</sub> =	0.1				
D <sub>35</sub> =	0.3				
D <sub>50</sub> =	5.6				
D <sub>84</sub> =	85.0				
D <sub>95</sub> =	256.0				
D <sub>100</sub> =	>2048				





Big Harris Creek Mitigation Site - Area B


DMS Project No. 739


Monitoring Year 3 - 2020

LFC Reach 2, Cross-Section 39

Particle Class		Diame	ter (mm)	Riffle 100-	Summary		
				Count	Class	Percent	
		min	max	Count	Percentage	Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062			0	
	Very fine	0.062	0.125	3	3	3	
	Fine	0.125	0.250	2	2	5	
SAND	Medium	0.25	0.50			5	
51	Coarse	0.5	1.0	2	2	7	
	Very Coarse	1.0	2.0			7	
	Very Fine	2.0	2.8	2	2	9	
	Very Fine	2.8	4.0			9	
	Fine	4.0	5.6			9	
	Fine	5.6	8.0	1	1	10	
GRAVEL	Medium	8.0	11.0	7	7	17	
CRAV.	Medium	11.0	16.0	7	7	24	
Ü	Coarse	16.0	22.6	17	17	41	
	Coarse	22.6	32	3	3	44	
	Very Coarse	32	45	9	9	53	
	Very Coarse	45	64	4	4	57	
	Small	64	90	5	5	62	
COBBLE	Small	90	128	2	2	64	
COBP.	Large	128	180	9	9	73	
·	Large	180	256	17	17	90	
	Small	256	362	10	10	100	
BOULDER	Small	362	512			100	
	Medium	512	1024			100	
	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048			100	
	•		Total	100	100	100	

Cross-Section 39					
Channel materials (mm)					
D <sub>16</sub> =	10.5				
D <sub>35</sub> =	20.0				
D <sub>50</sub> =	40.2				
D <sub>84</sub> =	226.1				
D <sub>95</sub> =	304.4				
D <sub>100</sub> =	362.0				







Big Harris Creek Mitigation Site - Area C DMS Project No. 739 Monitoring Year 3 - 2020

LBHC Reach 1A, Reachwide

		Diame	ter (mm)	Pa	rticle Co	unt	Reach Summary	
Par	Particle Class						Class	Percent
		min	max	Riffle	Pool	Total	Percentage	Cumulative
SILT/CLAY	Silt/Clay	0.000	0.062					0
	Very fine	0.062	0.125					0
	Fine	0.125	0.250	2	1	3	3	3
SAND	Medium	0.25	0.50		24	24	24	27
51	Coarse	0.5	1.0		7	7	7	34
	Very Coarse	1.0	2.0		1	1	1	35
	Very Fine	2.0	2.8					35
	Very Fine	2.8	4.0		1	1	1	36
	Fine	4.0	5.6		1	1	1	37
	Fine	5.6	8.0		1	1	1	38
JEL	Medium	8.0	11.0					38
GRAVEL	Medium	11.0	16.0	1	1	2	2	40
	Coarse	16.0	22.6		1	1	1	41
	Coarse	22.6	32	5	4	9	9	50
	Very Coarse	32	45	10	5	15	15	65
	Very Coarse	45	64	9	3	12	12	77
	Small	64	90	9		9	9	86
CORRIE	Small	90	128	3		3	3	89
OBU	Large	128	180	11		11	11	100
ŭ	Large	180	256					100
	Small	256	362					100
BOULDER	Small	362	512					100
	Medium	512	1024					100
<b>V</b> 0"	Large/Very Large	1024	2048					100
BEDROCK	Bedrock	2048	>2048					100
			Total	50	50	100	100	100

Reachwide					
Channel materials (mm)					
D <sub>16</sub> =	0.4				
D <sub>35</sub> =	2.0				
D <sub>50</sub> =	32.0				
D <sub>84</sub> =	83.4				
D <sub>95</sub> =	154.2				
D <sub>100</sub> =	180.0				





#### **Reachwide and Cross-Section Pebble Count Plots**

Big Harris Creek Mitigation Site - Area C


DMS Project No. 739


Monitoring Year 3 - 2020

LBHC Reach 1A, Cross-Section 42

		Diame	ter (mm)	Riffle 100-	Summary			
Pai	rticle Class			Count	Class	Percent		
		min	max	Count	Percentage	Cumulative		
SILT/CLAY	Silt/Clay	0.000	0.062			0		
	Very fine	0.062	0.125			0		
_	Fine	0.125	0.250	5	5	5		
SAND	Medium	0.25	0.50	2	2	7		
5'	Coarse	0.5	1.0			7		
	Very Coarse	1.0	2.0			7		
	Very Fine	2.0	2.8			7		
	Very Fine	2.8	4.0			7		
	Fine	4.0	5.6			7		
	Fine	5.6	8.0	1	1	8		
, KL	Medium	8.0	11.0	1	1	9		
GRAVEL	Medium	11.0	16.0	5	5	14		
Ü	Coarse	16.0	22.6	9	9	23		
	Coarse	22.6	32	17	17	40		
	Very Coarse	32	45	16	16	56		
	Very Coarse	45	64	17	17	73		
	Small	64	90	5	5	78		
COBBLE	Small	90	128	9	9	87		
COBE	Large	128	180	11	11	98		
·	Large	180	256	2	2	100		
	Small	256	362			100		
OER	Small	362	512			100		
BOULDER	Medium	512	1024			100		
₩.	Large/Very Large	1024	2048			100		
BEDROCK	Bedrock	2048	>2048			100		
	*	•	Total	100	100	100		

Cross-Section 42								
Channel materials (mm)								
D <sub>16</sub> =	17.3							
D <sub>35</sub> =	28.9							
D <sub>50</sub> =	39.6							
D <sub>84</sub> =	113.8							
D <sub>95</sub> =	164.0							
D <sub>100</sub> =	256.0							






#### **Reachwide and Cross-Section Pebble Count Plots**


Big Harris Creek Mitigation Site - Area C DMS Project No. 739 Monitoring Year 3 - 2020

LBHC Reaches 1B & 2, Reachwide

2		Diame	ter (mm)	Pa	rticle Co	unt	Reach S	ummary
Par	ticle Class						Class	Percent
		min	max	Riffle	Pool	Total	Percentage	Cumulative
SILT/CLAY	Silt/Clay	0.000	0.062					0
	Very fine	0.062	0.125		6	6	6	6
	Fine	0.125	0.250	2	18	20	20	26
SAND	Medium	0.25	0.50		11	11	11	37
Sr.	Coarse	0.5	1.0		7	7	7	44
	Very Coarse	1.0	2.0	1	2	3	3	47
	Very Fine	2.0	2.8					47
	Very Fine	2.8	4.0					47
	Fine	4.0	5.6		1	1	1	48
	Fine	5.6	8.0		2	2	2	50
JEL	Medium	8.0	11.0					50
GRAVEL	Medium	11.0	16.0	1		1	1	51
Ŭ	Coarse	16.0	22.6	2	1	3	3	54
	Coarse	22.6	32	5	2	7	7	61
	Very Coarse	32	45	2		2	2	63
	Very Coarse	45	64	2		2	2	65
	Small	64	90	10		10	10	75
ale	Small	90	128	10		10	10	85
COBBLE	Large	128	180	6		6	6	91
ŭ	Large	180	256	5		5	5	96
	Small	256	362	3		3	3	99
OER	Small	362	512	1		1	1	100
BOULDER	Medium	512	1024					100
•	Large/Very Large	1024	2048					100
BEDROCK	Bedrock	2048	>2048					100
	•		Total	50	50	100	100	100

Reachwide							
Channel materials (mm)							
D <sub>16</sub> =	0.2						
D <sub>35</sub> =	0.4						
D <sub>50</sub> =	8.0						
D <sub>84</sub> =	123.6						
D <sub>95</sub> =	238.6						
D <sub>100</sub> =	512.0						





#### **Reachwide and Cross-Section Pebble Count Plots**

Big Harris Creek Mitigation Site - Area C


DMS Project No. 739


Monitoring Year 3 - 2020

LBHC Reaches 1B & 2, Cross-Section 43

		Diame	ter (mm)	Riffle 100-	Sum	mary	
Pai	rticle Class	min max		Count	Class	Percent Cumulative	
SILT/CLAY	Silt/Clay	0.000	0.062		3 3 1 1 1 1 13 13 13 2 2 2 4 4 4 4 2 2 2 2		
JILIY CEAT	Very fine	0.062	0.125			0	
	Fine	0.125	0.123			0	
SAND	Medium	0.25	0.50	3	3	3	
	Coarse	0.5	1.0			4	
	Very Coarse	1.0	2.0	13	13	17	
	Very Fine	2.0	2.8			17	
	Very Fine	2.8	4.0			17	
	Fine	4.0	5.6	2	2	19	
	Fine	5.6	8.0	4	4	23	
.161	Medium	8.0	11.0	2	2	25	
GRAV	Medium	11.0	16.0	6	6	31	
Ŭ	Coarse	16.0	22.6	2	2	33	
	Coarse	22.6	32			33	
	Very Coarse	32	45	2	2	35	
GRAVEL	Very Coarse	45	64	4	4	39	
	Small	64	90	13	13	52	
COBBLE	Small	90	128	17	17	69	
COBL	Large	128	180	13	13	82	
	Large	180	256	17	17	99	
	Small	256	362	1	1	100	
, OER	Small	362	512			100	
BOULDER	Medium	512	1024			100	
v	Large/Very Large	1024	2048			100	
BEDROCK	Bedrock	2048	>2048	·		100	
			Total	100	100	100	

Cross-Section 43								
Channel materials (mm)								
D <sub>16</sub> =	1.9							
D <sub>35</sub> =	45.0							
D <sub>50</sub> =	85.4							
D <sub>84</sub> =	187.6							
D <sub>95</sub> =	235.6							
D <sub>100</sub> =	362.0							







# Table 14. Verification of Bankfull Events

Big Harris Creek Mitigation Site

DMS Project No. 739

Reach	Monitoring Year	Date of Occurrence	Method					
	MY1	10/11/2018						
		6/7/2019						
Upper Big Harris Creek	MY2							
Reach 2A		8/4/2019						
(SG #1)		2/6/2020						
	MY3	4/30/2020						
		10/11/2020						
		5/30/2018						
		7/24/2018						
	MY1	10/11/2018						
		11/12/20181						
		11/15/2018						
		1/22/2019						
		1/26/2019						
	<u> </u>	1/30/2019 <sup>1</sup>						
	MY2	1/31/2019						
		2/11/2019						
		6/7/2019						
Royster Creek Reach 1		6/8/2019						
(SG #2)		6/9/2019						
		1/11/2020						
		2/6/2020						
		2/13/2020						
		3/25/2020						
		4/13/2020						
	MY3	4/29/2020 - 4/30/2020						
		5/19/2020						
		5/21/2020						
		8/15/2020						
		9/25/2020						
		10/11/2020						
	MY1		Stream Gage					
Scott Creek	MY2							
(SG #3)	MY3	2/6/2020						
		3/8/2020						
	MY1 —	10/11/2018						
		11/15/2018						
		6/7/2019						
	MY2	6/8/2019 <sup>1</sup>						
C		6/9/2019						
Carroll Creek		8/4/2019						
(SG #4)		2/6/2020						
		2/13/2020						
	MY3	4/30/2020						
		5/19/2020						
		8/15/2020						
		10/11/2020						
	MY1	10/11/2018						
		6/7/2019 <sup>1</sup>						
Upper Stick Elliott Creek	MY2	6/8/2019						
Reach 1		8/4/2019						
(SG #5)	1000	2/6/2020	_					
	MY3	2/13/2020	_					
		5/19/2020						
	L	10/11/2018 <sup>1</sup>						
	MY1	11/12/2018						
	ļ	11/15/2018	_					
Upper Stick Elliott Creek	MY2	6/8/2019	_					
Reach 5		8/4/2019						
(SG #6)		2/6/2020	_					
	MY3	4/30/2020						
		5/19/2020						
		10/11/2020						

<sup>&</sup>lt;sup>1</sup> Multiple bankfull events recorded on occurrence date.

<sup>---</sup> No bankfull events reported.


Table 14. Verification of Bankfull Events Big Harris Creek Mitigation Site DMS Project No. 739

Monitoring Year 3 - 2020

Reach	Monitoring Year	Date of Occurrence	Method				
		10/11/2018					
		6/7/2019					
Elliott Creek	IVIYZ	6/8/2019					
(SG #7)		2/6/2020					
(50 #7)	MY3	4/30/2020					
	5						
		10/11/2020					
		 6/9/2010					
	IVIYZ						
UT1 to Elliott Creek			=				
(SG #8)	MY3						
		5/19/2020					
		10/11/2020					
Bridges Creek	MY1	10/11/2018 6/7/2019 6/8/2019 2/6/2020 4/30/2020 5/19/2020 10/11/2020 10/11/2020 3/25/2020 4/30/2020 5/19/2020 3/25/2020 4/30/2020 5/19/2020 10/11/2020 10/11/2020					
(SG #9)	MY1 10/11/2018  MY2 6/8/2019 6/8/2019 6/8/2019 12/6/2020 10/11/2020 10/11/2020 10/11/2020 10/11/2020 10/11/2020 10/11/2020 10/11/2020 10/11/2020 10/11/2020 10/11/2020 10/11/2020 10/11/2020 10/11/2020 10/11/2020 10/11/2020 10/11/2020 10/11/2020 10/11/2020 10/11/2018 11/12/2018 11/12/2018 11/12/2018 11/12/2018 11/12/2018 11/12/2019 12/12/2019 12/12/2019 12/12/2019 12/12/2019 12/12/2019 12/12/2019 12/12/2019 12/12/2019 12/12/2019 12/12/2019 12/12/2020 12/13/2020 12/13/2020 13/12/2020						
(	MY3						
	1.074						
	IVIT		_				
	MV2	6/7/2019 <sup>1</sup>					
	IVITZ	6/8/2019					
T2 to Upper Stick Elliott							
Creek							
(SG #10)			_				
			_				
	MY3						
		5/21/2020					
		8/3/2020					
	MY2						
			Stream Gage				
T3 to Upper Stick Elliott							
Creek	MY2						
(SG #11)	MY3						
			_				
			_				
			=				
	MY1						
Upper Fletcher Creek							
Reach 2	MV2	6/7/2019					
(SG #12)	IVITZ	6/8/2019					
	<u> </u>		4				
	MY3		-				
	$\vdash$		-				
			=				
	MY1		=				
Lower Fletcher Creek							
Reach 1	MV2						
(SG #13)	IVITZ	1/31/2019					
	MY3						
	_		4				
			-				
	NAV1		-				
	IVITI		-				
	+		╡				
Lower Big Harris Creek	MY2		╡				
Reach 1A	····-		7				
(SG #14)	+		7				
• •			7				
	MY3						
		5/19/2020					
		10/11/2020	1				


<sup>&</sup>lt;sup>1</sup> Multiple bankfull events recorded on occurrence date. --- No bankfull events reported.

Big Harris Creek Mitigation Site DMS Project No. 739




## **Recorded In-stream Flow Events**

Big Harris Creek Mitigation Site DMS Project No. 739




## **Recorded In-stream Flow Events**


Big Harris Creek Mitigation Site DMS Project No. 739




Big Harris Creek Mitigation Site DMS Project No. 739




Big Harris Creek Mitigation Site DMS Project No. 739




Big Harris Creek Mitigation Site DMS Project No. 739



Big Harris Creek Mitigation Site DMS Project No. 739




Big Harris Creek Mitigation Site DMS Project No. 739




## **Recorded In-stream Flow Events**


Big Harris Creek Mitigation Site DMS Project No. 739




Big Harris Creek Mitigation Site DMS Project No. 739




Big Harris Creek Mitigation Site DMS Project No. 739




Big Harris Creek Mitigation Site DMS Project No. 739



Big Harris Creek Mitigation Site DMS Project No. 739



Big Harris Creek Mitigation Site DMS Project No. 739



APPENDIX 6. Revised Water Quality Monitoring Correspondence and Technical Memo

From: Tugwell, Todd J CIV USARMY CESAW (US)

To: Melia, Gregory; Wiesner, Paul; Kim Browning; Haupt, Mac; Davis, Erin B

Cc: Jeff Keaton; Shawn Wilkerson

Subject: [External] RE: Big Harris\_DMS# 739\_Technical Memo WQ Monitoring\_6-6-2019

**Date:** Thursday, August 22, 2019 11:55:46 AM

CAUTION: External email. Do not click links or open attachments unless you verify. Send all suspicious email as an attachment to report.spam@nc.gov<mailto:report.spam@nc.gov>

#### Greg,

We discussed the latest plan with the IRT yesterday, and we are fine with the responses. Please proceed and let me know if you have any other questions. I'm sure Mac will jump at the chance to go back out to Big Harris once we get some results.

Todd

----Original Message----

From: Melia, Gregory [mailto:gregory.melia@ncdenr.gov]

Sent: Tuesday, August 13, 2019 5:00 PM

To: Wiesner, Paul <paul.wiesner@ncdenr.gov>; Tugwell, Todd J CIV USARMY CESAW (US)

<Todd.J.Tugwell@usace.army.mil>; Browning, Kimberly D CIV USARMY CESAW (US)

 $<\!\!Kimberly.D.Browning@usace.army.mil\!\!>; Haupt, Mac<\!\!mac.haupt@ncdenr.gov\!\!>; Davis, Erin B$ 

<erin.davis@ncdenr.gov>

Cc: Jeff Keaton < jkeaton@wildlandseng.com>; Shawn Wilkerson < swilkerson@wildlandseng.com> Subject: [Non-DoD Source] RE: Big Harris\_DMS# 739\_Technical Memo WQ Monitoring\_6-6-2019

All,

Attached is the document I had brought to the meeting today. The first 3 pages include the e-mail that was sent by the IRT with questions about the memo as well as the responses I sent back (in blue). The rest of the pages are the final memo revised to address the questions. Paul sent that out on 6/12/19 (see below).

My responses (blue text) in the attached and the final memo have yellow highlighted sections that identify the salient part of my response and shows where in the memo document that we addressed the question/concern.

So, if you focus on those yellow highlighted part of the attached it should expedite things.

If there were other questions, just let us know.

WEI and Western Carolina are trying to complete their contracting for this.

Thanks,

(	j	r	e	į	3

From: Wiesner, Paul <paul.wiesner@ncdenr.gov>

Sent: Wednesday, June 12, 2019 4:35 PM

To: Tugwell, Todd J CIV USARMY CESAW (US) <Todd.J.Tugwell@usace.army.mil>; Kim Browning <Kimberly.D.Browning@usace.army.mil>; Haupt, Mac <mac.haupt@ncdenr.gov>; Davis, Erin B

<erin.davis@ncdenr.gov>

Cc: Melia, Gregory <gregory.melia@ncdenr.gov>; Jeff Keaton <jkeaton@wildlandseng.com>; Shawn Wilkerson <swilkerson@wildlandseng.com>

Subject: Big Harris\_DMS# 739\_Technical Memo WQ Monitoring\_6-6-2019

Erin, Kim, Mac and Todd;

Please find attached the final Big Harris water quality monitoring proposal. It incorporates all and the changes and updates we have discussed to date.

Let us know how you would like to proceed. The potential 507 credits was established in the mitigation plan so there is no increase in project credits. If possible, we would like to move forward with an email approval of the proposal rather than a full mitigation plan addendum.

Thanks

Paul Wiesner

Western Regional Supervisor

North Carolina Department of Environmental Quality

Division of Mitigation Services

828-273-1673 Mobile

paul.wiesner@ncdenr.gov < mailto:paul.wiesner@ncdenr.gov >

Western DMS Field Office
5 Ravenscroft Drive
Suite 102
Asheville, N.C. 28801

Email correspondence to and from this address is subject to the

North Carolina Public Records Law and may be disclosed to third parties.

From: Melia, Gregory

To: Tugwell, Todd J CIV USARMY CESAW (US); Wiesner, Paul; Shawn Wilkerson; Haupt, Mac; Jeff Keaton; Kim

Browning; Russell, Periann

Subject: RE: [External] RE: Big Harris Creek - DMS# 739 - Revised Water Quality Monitoring Proposal Memo

**Date:** Thursday, April 25, 2019 10:49:00 AM

Todd et al.,

Sorry everybody. I've been playing catchup from being out last week. See my responses to your comments below in Blue

----Original Message-----

From: Tugwell, Todd J CIV USARMY CESAW (US) <Todd.J.Tugwell@usace.army.mil>

Sent: Tuesday, April 16, 2019 4:24 PM

To: Melia, Gregory <gregory.melia@ncdenr.gov>; Wiesner, Paul <paul.wiesner@ncdenr.gov>; Shawn Wilkerson <swilkerson@wildlandseng.com>; Haupt, Mac <mac.haupt@ncdenr.gov>; Jeff Keaton <jkeaton@wildlandseng.com>; Kim Browning <Kimberly.D.Browning@usace.army.mil>

Subject: RE: [External] RE: Big Harris Creek - DMS# 739 - Revised Water Quality Monitoring Proposal Memo

CAUTION: External email. Do not click links or open attachments unless you verify. Send all suspicious email as an attachment to report.spam@nc.gov<mailto:report.spam@nc.gov>

Greg,

I have had a chance to review the Big Harris WQ Monitoring proposal as discussed during our meeting last week. After looking over the mitigation plan and comments, I have the following comments and a few more questions:

- 1. With regard to credits, the IRT comments on the draft plan confirm your accounting of the credits with one minor error. I believe the total credit from the mitigation plan (not including the 507 credits from the additional 2%) was 25,330 (rounded up), not 25,331. While it is not clear to me if the additional 2% should have been based on the total credit before or after adding in the 1.5% watershed bonus and the initial 4% water quality bonus, I will agree to the 507 credits because Wildlands response to our comments makes reference to the 507 credits, and it is attached to our approval letter. Understood.
- 2. In the biological monitoring section, the memo indicates three macro-benthic sites will

be monitored on Upper Fletcher above station 1. I didn't see these stations on the map - are they in the restoration reach or the E2 reach? Also, why concentrate three sites on this reach? That is an error we didn't catch in the narrative. The only benthos stations on fletcher are stations 0 and 1. Station 0 is serving as a watershed control station and was assessed for Benthos and Conductivity pre-con. See note A on page 4.

- In the success criteria, the physiochemical parameters are determined successful with a 15% reduction in the mean distribution, and the biological parameters are determined successful with an increase of at least one bio-classification, correct? And then all parameters (both physiochemical and biological) are used to determine the % of credit for that station? For the biological parameters, sampling will be done in year 3 and 5 - does success assume an increase in bio-classification in both year 3 and 5, or only once? Also does it matter if there is an improvement in year 3 but a loss of a bio-classification in year 5? Yes, I remember at one point that Wildlands and I were discussing this uncertainty and apparently we never circled back. As is evident there are a lot of moving parts here. We had 3 options we were discussing at the time as I recall (see below). I had meant to speak with Eric Fleek at the DWR lab to see if B is something they ever do or whether it is advisable. I will contact him about that. The rationale for C was that if the we relied on a single year we could have drought in post-con as compared to the pre-con for example. Let me circle back with Eric Fleek and/or Larry on their thoughts on that and I will get back to you. In addition, some of the habitat development might take longer to indicate a change related to the restoration efforts (e.g. LWD, Leaf Pack etc.). It may be advisable for us to have it for years 4 and 5 instead of 3 and 5 if we maintain 2 years of benthos sampling. If anyone has a compelling argument for one approach or another then chime in, but I would actually lean towards a pooled data set from year 4 and 5 if Eric and Larry bless that approach.
- a. Simply measure in Year 5 and base the entire success/failure on that.
- b. Pool the raw data from Year 3 and 5 to generate a single BI to represent the post-con condition for comparison to pre-con.
- c. Sample both years and choose the year that is the closest in terms of the hydrologic condition (water year) that the site was exposed to in the pre-con sampling.
- 4. In the success criteria, there is a provision for "time series analysis" that I'd like to understand better. This seems to imply that if you don't meet the 15% reduction at the end of monitoring (year 5), but the trend indicates you will meet the 15% at the end of 10 years, you still consider this to be successful, correct? So does this mean you could meet success with as little as a 7.5% reduction at the end of monitoring? Am I reading this right? If so, I'm not sure I agree that such a low percentage is an appropriate standard for success.

Point taken. The intent here was to incorporate standard statistical practices used in assessment of change WQ, which are discussed in the Spooner paper and other literature to include parametric, non-parametric hypothesis testing (referred to as Step change in Spooner's paper) and time series in a tiered approach to investigate change, but I see the problem that the time series presents written as it is. I would say that we need to proceed and revise as follows:

- a. If statistical assumptions of normality and homogeneity of variance are met we rely on parametric hypothesis testing or ANOVA (P<0.05)
- b. If assumptions are not met we utilize non-parametric hypothesis testing (P<0.05) as per standard practice
- c. If the variability of a particular parameter at a particular station does permit detection of significance at 0.05 in either hypothesis testing scheme (a or b) then we attempt to run the data as a time series trend. The variability in a pooled hypothesis test may present differently when subjected to multiple regression techniques plotted against time (time series) and you can may be able tease out changes you could not through a and b. The slope of the time series regression line would have to be significantly different from zero at (P<0.05).

Now, even though we would employ this tiered approach, the one basic minimum threshold that will apply in all cases (a,b,c) is that the difference in the means pre-post must be a minimum of 15%. If that minimum threshold of 15% is not met it doesn't matter if any of the three above are deemed significant, that parameter at that station will be deemed a failure for the purpose of attaining mitigation credit.

5. I haven't seen the as-built yet for this project - do you know if it's available and if there are projected changes to credit?

The As-built is posted on our documents spreadsheet and was sent to DWR and USACE in the Bulk transfer on 12/18/2018. It is my understanding that the credits from the Mit Plan are what WEI used in that report and are being used as the agreed upon credits for the duration. If I have this wrong anybody, just chime in.

I appreciate your bearing with me as I work through this. I know I am asking questions that may seem like I'm getting into the weeds, but the details really matter in this case and we all need to make sure to understand and agree on these points up front so we don't have disagreements on credit at closeout. I've had to learn that lesson the hard way. Understood and thanks for your review.

Thanks,



# **Technical Memorandum**

**Prepared for:** Interagency Review Team

**Project Title:** Big Harris Creek Mitigation Site

**Subject:** Revised Water Quality Monitoring Proposal

**Date:** June 6, 2019

From: Jeff Keaton

#### **INTRODUCTION**


The purpose of this Technical Memorandum is to provide the North Carolina Interagency Review Team (IRT) a summary of the proposed post-construction water quality and biological monitoring program for the Big Harris Creek Mitigation Site. As stated in the final mitigation plan (section 12.7), a 4% credit allowance based on the entire linear footage of the project will be granted for the inclusion of these parameters for a pre/post construction comparison. Also based on the mitigation plan, an additional 2% (507 SMUs) credit allowance will be granted if post-construction water quality monitoring demonstrates improvement as per the plan detailed below.

This memo describes a revised version of the water quality, benthic, and fish monitoring program that has been refined based on an analysis of the pre-construction data and a set of criteria to support statistically reliable detection of change. **This revised monitoring program will supersede the program described in the final mitigation plan.** The memo will also describe the proposed success criteria for the monitoring program.

#### **ANALTICAL BASIS FOR POST-CON SAMPLING PLAN**

Pre-con sampling was completed at 16 stations within the Big Harris watershed and at 4 reference stations in the Little Harris watershed by the Division of Water Resources Watershed Assessments Team (WAT) for nutrient and biological parameters using state certified procedures. Western Carolina University performed automated stormflow monitoring of suspended sediments and discharge at 4 key drainage locations. Selected reaches were also monitored for groundwater hydrology. These monitoring activities were funded by the Division of Mitigation Services (DMS). The pre-construction (baseline) data were analyzed and several criteria were used to determine whether post-construction monitoring of a parameter was warranted at a given station. The statistical analysis was performed by DMS staff member, Greg Melia, with consultation and review by Wildlands Engineering staff. The hierarchy of the criteria used to select post-construction monitoring parameters and stations are as follows:

1. The levels of the pre-con data for a given parameter at a given station had to demonstrate that they were elevated compared to regulatory standards, the Little Harris reference sites, or relevant regional data sets/literature. The main consideration here is whether there is meaningful room for improvement at a given station.




- 2. There exists a reasonable likelihood for improvement in the given parameter at the given location because the direct stressors can be largely addressed. Examples of where stressors might not be addressed include cases where land owner easement grants do not permit capture of the major lateral inputs.
- 3. The pre-construction data indicates that a given station can be adequately represented by one of the pre-construction sampling stations (to include consolidation, where sensible).
- 4. Statistical analysis of the pre-construction distributions using minimal detectable change (MDC) analysis (Spooner et al., 2011) was performed by DMS for each parameter at each station. Using the variance of the pre-construction distribution, the MDC provides an estimate of the minimum percent change in a pollutant concentration that will be required to support statistically reliable detection of that change (assuming and alpha of 0.05). The more variability in the distribution of the data, the greater the MDC must be for reliable change detection. MDC results ≥ 50% were generally considered too variable and resulted in exclusion of that parameter at that station for post-construction monitoring. However, in some case best professional judgement was applied. MDCs that were slightly over 50% may have been included if outliers in the raw data could be identified or the parameter distributions and/or site characteristics exhibited other qualities that made it sensible to override a slightly elevated MDC.
- 5. Statistical Assumptions The use of the MDC in item 4 assumes the approximation of a normal distribution, however in many cases the MDC analysis is robust against the violation of this assumption after pooling the post-con data with the pre-data. Therefore, this criterion was used to assist in decision making, but was a lesser factor than the other criteria.

Wildlands Engineering will contract Western Carolina University (WCU) to collect the post-construction water quality data which will include both baseflow and stormflow monitoring. Table 1 provides the matrix of parameters to be collected at a given station based on the analysis and criteria described above. The locations of the monitoring stations are shown on the attached map (Figure 1). The station numbers in the matrix correspond to the stations listed on the map. The samples will be collected using protocols utilized by the NC Department of Environmental Quality (DEQ), which are consistent with the methods used to collect pre-construction water samples. All samples will be analyzed at the NC DEQ labs in Swannanoa and/or Raleigh.

The four water quality monitoring locations are the four previously monitored sites (Sites 2, 8, 9, 14). ISCO automated samplers will be used to collect the samples at each of these four sites. Samples at the automated ISCO stations listed in will be collected as flow-proportional composites. Samples at the non-automated sites will be collected as grab samples. Fecal coliform will be collected exclusively as grab samples in all cases. Conductivity will be measured directly in-situ with a water quality meter. Baseflow samples will be collected at the frequencies described below. Fifteen to twenty storm events will be targeted between years 2 and 5 to cover storm water samples.

**Table 1. Parameter Matrix** 

Туре	NA	NA	Α	NA	NA	NA	Α	Α	NA	Α	Baseflow	
Station	0	1	2	4	5a	6	8	9	13	14	Stormflow	
Fecal											Base and Storm	
Cond											ISCO Station	Α
TSS											Not Automated	NA



NH3						Watershed Control	
TKN							
NO2-NO3							
TP							
Macrobenthos							
Fish							

## **Baseflow Monitoring**

The base flow monitoring program proposed is as follows:

- a. Fecal coliform Once per month during years 3, 4, and 5 at Stations 2, 4, 8, and 9.
- b. Conductivity Once per month during years 2, 3, and 5 at Stations 0, 1, 2, 8, 9, and 13, and 14 and at stations when benthos or fish are to be sampled.
- c. TSS baseflow solids Once per month during years 3, 4, 5 at Stations 2, 9, and 14.
- d. Ammonia  $(NH_3)$  Once per month during years 4 and 5 at Stations 8 and 9.
- e. Total Kjeldahl nitrogen (TKN) Once per month during years 4 and 5 at Station 9.
- f. Nitrite (NO<sub>2</sub>)-nitrate (NO<sub>3</sub>) nitrogen Once per month during years 4 and 5 at Stations 2, 8, 9, and 14.
- g. Total phosphorous (TP) Once per month during years 4 and 5 at Stations 2, 8, 9, and 14.

#### **Stormflow Monitoring**


The proposed stormflow monitoring program is as follows:

- a. Fecal coliform Sites 2 and 9.
- b. Conductivity Site 1
- c. Ammonia ( $NH_3$ ) –Sites 2, 8, 9, and 14.
- d. Total Kjeldahl nitrogen (TKN) Sites 2, 9, and 14.
- e. Nitrite (NO<sub>2</sub>)-nitrate (NO<sub>3</sub>) nitrogen Sites 2, 8, 9, and 14.
- f. Total phosphorous (TP) Sites 2, 8, 9, and 14.

# **Biological Monitoring**

The proposed fish community and benthic macroinvertebrate monitoring program is as follows:

- a. Fish community sampling will be conducted with a backpack electrofisher once per year during years 4 and 5 at stations 4, 5a, 9, and 13.
- b. Benthic macroinvertebrate sampling will be conducted once per year during years 4 and 5 at stations 0, 1, 4, 6, 8, and 14. Two macro-benthic sites (stations 0 and 1) will be sampled on Upper Fletcher Creek. This is being done to demonstrate the extent of post-construction habitat improvement on this reach as compared to the pre-construction data. The increase in habitat brought about by the restoration treatments should demonstrate a greater extent and improved recruitment of the benthic community. The water quality results for Upper Fletcher Creek will be the result of the synthesis of the benthos data from these stations.



Biological sampling will be performed directly by Wildlands personnel. Approved Qual 4 DEQ Standard Operating Procedures will be followed for all biological sampling. The classification criteria for benthos will follow the NCBI thresholds - for small streams (NC DEQ, 2016).

#### **Notes on Monitoring Plan**

- a. Site 0 will be used as watershed control point using conductivity and benthos as an indicator of incoming water quality. The drainage above this location indicated relatively high pollutant inputs possibly due to hay fields at the drainage headwaters on some very steep slopes. Monitoring station 0 for conductivity as a surrogate for overall water quality will provide comparison to pre-construction levels for any post-construction results below this point.
- b. Site 13 will also serve as a watershed control. It had good water quality pre-construction, but during the design phase an upstream landowner created a large disturbance in this drainage and conductivity will be measured at this point to see how it compares to the pre-con conductivity distribution.
- c. Sites 8 and 9 were only sampled at baseflow pre-construction, but site 7, which was immediately downstream of the confluence of sites 8 and 9 will serve as the stormflow baseline for sites 8 and 9. This was deemed appropriate because when pooled, the baseflow data at sites 8 and 9 closely represented the pre-con baseflow at site 7. The storm data for sites 8 and 9 will be synthesized to provide the post-construction stormflow comparison to Site 7 pre-construction stormflow baseline.
- d. Site 14 was only sampled for baseflow pre-construction, but the distributions for the pre-construction water quality parameters were very similar for sites 10 and 14. Therefore, the storm data from site 10 will serve as the pre-construction storm baseline for the storm data collected at site 14 post-construction.
- e. For all other sites, post-construction baseflow and stormflow data will be compared to preconstruction baseflow and stormflow data respectively for the same sites.

#### **SUCCESS CRITERIA**

Each year when sampling is complete, data will be evaluated for any changes or trends that may be developing. Any observations will be reported in annual monitoring reports. However, ultimate success or failure for each monitoring station will be determined after the final dataset is collected prior to close out. At this time, each parameter in the overall post-construction data set (years 3-5) will be compared to the same parameter in the pre-construction data set using hypothesis testing. Improvement for any given physicochemical parameter will require a minimum of a 15% reduction in the mean of the distribution and demonstrate statistical significance (alpha 0.05). If parametric tests of assumption are not met, non-parametric methods may be employed. If a particular physicochemical parameter at a given station does not demonstrate a 15% improvement while meeting these criteria using hypothesis testing, time series analysis will be applied to demonstrate whether a significant negative trend exists. That is, the trend line will have to demonstrate a negative slope that is significantly different than 0 at an alpha of 0.05. In all cases the reduction between the means of the pre- and post-distributions must meet the minimum threshold of 15% for that parameter to be successful for the purpose of obtaining credit. For biological parameters, success will be determined based on whether there is an improvement of at least one bio-classification level (i.e. fair to good). Data from years 4 and 5 will be pooled to generate one bio-classification outcome to represent the post-construction condition.

The number of parameters that demonstrate success as described above will determine the proportion of credit that would be generated. For example, if there are 4 parameters at a station then each parameter represents 25% of the total available station credits credit. The number of parameters at

station that will contribute to success will include both baseflow and stormflow samples. The following equation will be used to quantify the additional credits:

# of parameters meeting success criteria at station/total # of parameters at station x total available station credits = additional credit

Total available station credits refers to the total possible additional credit that would be given for the reaches of the project that are at or upstream of that station either to the project limits or to another station. The total available station credits to be assigned if complete success is demonstrated at each station are summarized in Table 2 below. Total available station credits for stations 2 and 4 and stations 10 and 14 have been combined to balance out the effort/cost of collecting data with the credit amounts that would be generated by showing success at these stations.


#### **REFERENCES:**

NC Department of Environmental Quality. 2016. Standard Operating Procedures for the Collection and Analysis of Benthic Macroinvertebrates. Division of Water Resources. Raleigh, North Carolina. February 2016

Spooner, Jean; Dressing, Stephen A.; and Meals, Donald W. 2011. Minimum Detectable Change Analysis. Tech Notes 7, December 2011. Developed for U.S. Environmental Protection Agency by Tetra Tech, Inc., Fairfax, VA, 21 p.

Table 2. Total Available Station Credits Assigned by Station

Station	Parameters	Reaches Represented	Credits for Reaches (from MP)	Credits * Multiplier	2% of Credits	2% of Credits * Multiplier
1	Cond, MB	Upper Fletcher Creek R1-R2	2084	2251	42	45
2 & 4	Site 2: FC, Cond, TSS, NH3, TKN, NO2-NO3, TP Site 4:MB, Fish	Lower Fletcher Creek R1-R2	7434	8030	149	161
5a	Fish, Cond	Scott Creek Upper Big Harris R6A	1252	1352	25	27
6	МВ	Lower Stick Elliot Creek	527	569	11	11
8	MB, FC, Cond, NH3,NO2- NO3, TP	Royster Creek R1-R2	2060	2225	41	45
9	Fish, FC, Cond, TSS, NH3, TKN, NO2-NO3, TP	Upper Big Harris Creek R3-R5, Scism Creek	2969	3207	59	64
10 & 14	Site 10: Fish Site 14:MB, Cond, TSS, NH3, TKN, NO2- NO3, TP	Upper Big Harris R6B, Carrol Creek	3674	3969	73	79
13	Fish	Upper Big Harris Creek R1-R2, Cornwell Creek R1-R2, UT1 to Cornwell Creek, Eaker Creek	3451	3728	69	75
Total			23451	25331	469	507
TotalCredits fi	TotalCredits from MP including additional credit for monitoring and watershed approach					
Multiplier to g	Multiplier to get credits per reach (=25331/23451)					





ater Quality Monitori	

# Table 15. WCU Fecal & TSS Water Quality Data

Big Harris Creek Mitigation Site DMS Project No. 739 Monitoring Year 3 - 2020

			Station 0 - Upper Flo	etcher Creek Re	ach 1				
		Conductivity	Fecal	TSS	NOx	NH3-4	TKN	TP	
Date Sampled	Flow Type	(μS/cm)	(CFU/100mL)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	
6/11/2020	Base	65.5							
7/15/2020	Base	68.6							
8/11/2020	Base	67.8							
9/16/2020	Base	64.5	No other parameters collected at this station.						
10/20/2020	Base	61.9							
11/17/2020	Base	63.6							
12/8/2020	Base	N/A							
			Station 1 - Upper Flo	etcher Creek Re	ach 2				
Data Campulad	Flavo Toma	Conductivity	Fecal	TSS	NOx	NH3-4	TKN	TP	
Date Sampled	Flow Type	(μS/cm)	(CFU/100mL)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	
6/11/2020	Base	64.4							
7/15/2020	Base	63.6							
8/11/2020	Base	62.8	No other parameters collected at this station.						
9/16/2020	Base	59.1							
10/20/2020	Base	55.4							
11/17/2020	Base	54.7							
12/8/2020	Base	N/A							
		Station 2 - Lo	wer Stick Elliot Cree	k (downstream	of Stick Elliot R	d.)			
Data Campulad	Flow Type	Conductivity	Fecal	TSS	NOx	NH3-4	TKN	TP	
Date Sampled		(μS/cm)	(CFU/100mL)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	
6/11/2020	Base	98.9		6.2					
7/15/2020	Base	101.8		6.2					
8/11/2020	Base	100.1	180	6.2	Baseflow nutrient sampling to be collected in MY4 - MY5				
9/16/2020	Base	93.6	170	6.2					
10/20/2020	Base	89.5	TBD	TBD					
11/17/2020	Base	89.1	TBD	TBD					
12/8/2020	Base	N/A	TBD	TBD					
10/13/2020	Storm								
		St	ation 4 - Lower Stic	k Elliott Creek F	Reach 6				
Date Sampled	Flow Type	Conductivity	Fecal	TSS	NOx	NH3-4	TKN	TP	
Date Sampled		(μS/cm)	(CFU/100mL)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	
6/11/2020	Base	52.6	140						
7/15/2020	Base	57.3	220	220					
8/11/2020	Base	60.2	120 100 No other parameters collected at this station.						
9/16/2020	Base	51.2							
10/20/2020	Base	50.5	TBD						
11/17/2020	Base	50.0	TBD						
12/8/2020	Base	N/A	TBD						

N/A, No data recorded due to equipment malfunction.

<sup>---,</sup> No data collected.

TBD, Data results are pending. Currently waiting on data result from the lab.

# Table 15. WCU Fecal & TSS Water Quality Data

Big Harris Creek Mitigation Site

DMS Project No. 739

Monitoring Year 3 - 2020

			Station 8 - Roys	ter Creek Reach	2			
Date Sampled	Flow Type	Conductivity	Fecal	TSS	NOx	NH3-4	TKN	TP
Date Sampleu	riow Type	(μS/cm)	(CFU/100mL)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L
6/11/2020	Base	61.4		7.5				
7/15/2020	Base	66.8		6.2	Baseflow nutrient sampling to be			
8/11/2020	Base	67.3	140	6.2				
9/16/2020	Base	59.2	67	6.2	В	collected in M		
10/20/2020	Base	57.8	TBD	TBD		conected in ivi	14 - 10113	
11/17/2020	Base	57.2	TBD	TBD				
12/8/2020	Base	N/A	TBD	TBD				
10/13/2020	Storm				0.6	0.0	1.9	0.5
		S	tation 9 - Upper Big	Harris Creek R	each 5			
		Conductivity	Fecal	TSS	NOx	NH3-4	TKN	TP
Date Sampled	Flow Type	(μS/cm)	(CFU/100mL)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L
6/11/2020	Base	50.0		6.2				
7/15/2020	Base	57.4		6.2	Baseflow nutrient sampling to be collected in MY4 - MY5			
8/11/2020	Base	51.2	150	6.2				
9/16/2020	Base	47.2	530	6.2				
10/20/2020	Base	45.2	TBD	TBD				
11/17/2020	Base	45.0	TBD	TBD				
12/8/2020	Base	N/A	TBD	TBD				
, ,		<u> </u>						
10/13/2020	Storm				1.0	0.2	3.1	1.3
		Sta	ation 13 - Upper Big	Harris Creek Ro	each 2b			
Data Campilad	FI T	Conductivity	Fecal	TSS	NOx	NH3-4	TKN	TP
Date Sampled	Flow Type	(μS/cm)	(CFU/100)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L
6/11/2020	Base	37.6			•	•	•	
7/15/2020	Base	38.9						
8/11/2020	Base	39.5						
9/16/2020	Base	36.8	No other parameters collected at this station.					
10/20/2020	Base	36.1						
11/17/2020	Base	36.3						
12/8/2020	Base	N/A						
		St	ation 14 - Lower Bi	g Harris Creek R	leach 2			
Date Sampled	Flour Tuno	Conductivity	Fecal	TSS	NOx	NH3-4	TKN	TP
Date Sampled	Flow Type	(µS/cm)	(CFU/100)	(mg/L)	(mg/L)	(mg/L)	(mg/L)	(mg/L
6/11/2020	Base	61.2		6.2				
7/15/2020	Base	64.8		6.2				
8/11/2020	Base	66.7		6.2	Baseflow nutrient sampling to be collected in MY4 - MY5			
9/16/2020	Base	60		6.2				
10/20/2020	Base	56.1		TBD				
	Base	57.1		TBD				
11/17/2020								
11/17/2020 12/8/2020	Base	N/A		TBD				
	Base	N/A		TBD	0.9	0.2	2.8	1.3


N/A, No data recorded due to equipment malfunction.

<sup>---,</sup> No data collected.

TBD, Data results are pending. Currently waiting on data result from the lab.


**WCU Stage Gage Data** 

Big Harris Creek Mitigation Site DMS Project No. 739 **Monitoring Year 3 - 2020** 




**WCU Stage Gage Data** 

Big Harris Creek Mitigation Site DMS Project No. 739




**WCU Stage Gage Data** 

Big Harris Creek Mitigation Site DMS Project No. 739 Monitoring Year 3 - 2020



WCU Stage Gage Plot

Big Harris Creek Mitigation Site DMS Project No. 739



**From:** Ian Eckardt [mailto:ieckardt@wildlandseng.com]

**Sent:** Friday, February 12, 2021 1:20 PM **To:** Jerry Miller < <u>imiller@email.wcu.edu</u>>

**Cc:** Kristi Suggs < <a href="mailto:ksuggs@wildlandseng.com">ksuggs@wildlandseng.com</a>; Melia, Gregory <a href="mailto:gregory.melia@ncdenr.gov">gregory.melia@ncdenr.gov</a>; Wiesner,

Paul <paul.wiesner@ncdenr.gov>

**Subject:** [External] RE: Big Harris Water Quality Monitoring Schedule

**CAUTION:** External email. Do not click links or open attachments unless you verify. Send all suspicious email as an attachment to Report Spam.

Jerry,

Thanks for the prompt response. I'll update the final annual monitoring report (MY3) with the adjusted water quality sampling schedule which will extend to June 2023. I'm copying Greg, Paul, and Kristi so that everyone's on the same page.

**Ian Eckardt, PWS** | *Environmental Scientist* **O**: 704.332.7754 x108 **M**: 704.517-4988

#### Wildlands Engineering, Inc.

1430 S. Mint St, Suite 104 Charlotte, NC 28203

From: Jerry Miller < <a href="miller@email.wcu.edu">miller@email.wcu.edu</a> Sent: Friday, February 12, 2021 11:03 AM
To: lan Eckardt < <a href="mailto:ieckardt@wildlandseng.com">ieckardt@wildlandseng.com</a>

Subject: Re: Big Harris Water Quality Monitoring Schedule

Hi lan,

Yes, I agree. I think that continuing the sampling through June 2023 would be best.

Jerry

From: Ian Eckardt < ieckardt@wildlandseng.com >

**Sent:** Friday, February 12, 2021 10:32 AM **To:** Jerry Miller < <u>imiller@email.wcu.edu</u>>

**Subject:** Big Harris Water Quality Monitoring Schedule

**WARNING:** This email originated from a non-WCU email account. Do not click links or open attachments unless you are confident the content is safe.

Jerry,

I wanted to touch base about the end date for the water quality sampling Western Carolina is performing at Big Harris Creek Mitigation Site. Grab samples were originally expected to begin in January 2020 and last for three years; however, due to equipment issues and issues related to COVID,

the WCU sampling wasn't initiated until June 2020. Based on the adjusted start date, water quality sampling is now anticipated to run through June 2023. Please let me know if you concur or need to discuss further.

Thanks,

**Ian Eckardt, PWS** | *Environmental Scientist* **O**: 704.332.7754 x108 **M**: 704.517-4988

Wildlands Engineering, Inc. 1430 S. Mint St, Suite 104 Charlotte, NC 28203