

Agenda Item G-1. Community Development Block Grant - Infrastructure: Project Descriptions

Blue rows = proposed full or partial funding in the scenario [preliminary]

Application Number	Proposed Funding in Scenario?				New Connections in Project													Additional Info. Added?					
		Instance ID	Applicant Name	County		Funding Request per New Connection	Residential Connections	Project Name	Project Description	LMI Method	LMI Claimed	LMI Verified	Application Preparer	Total Project Cost	Funding Requested	Points Claimed by Applicant	Points Verified		Difference in Points Claimed and Verified				
1	Yes	299352	Farmville, Town of	Pitt	0		3,256	Housing Authority Water System Improve	Replace approximately 7,200 LF of existing 4-, 6-, and 10-inch diameter waterlines and appurtenances within the Farmville Housing Authority along Anderson Avenue, Pitt Street, Godwin Drive, Taylors Turn, and Nick's Nook.	Surveys	99.4%	99.4%	Yes	McDavid Associates, Inc.	\$2,000,000	\$2,000,000	76	75.76					
2	Yes	299308	Greenevers, Town of	Duplin	0		290	Brown's Terrace Sanitary Sewer Improveme	Replace approximately 2,070 LF of aged gravity sewer infrastructure along Brown' s Terrace Lane and Brown' s Terrace Circle appurtenant to the Brown' s Terrace Housing Authority replace/rehabilitate existing influent Pump Station #1.	Surveys	100.0%	100.0%	Yes	McDavid Associates, Inc.	\$2,000,000	\$2,000,000	70	70					
3	Yes	299542	Belhaven, Town of	Beaufort	0		754	Belhaven WWTP Rehabilitation	Improve headworks, influent pump station, rapid mix basin, aeration basin and systems, clarifier, tertiary filter, UV basin, final aeration basin, solids processing. TReplace the old SCADA system, add cybersecurity, add security cameras, and repair perimeter fencing.	ACS	54.4%	54.4%	No	WithersRavenel, Inc.	\$6,000,000	\$3,000,000	70	64.39	2.N.2 (-5) Project relocate and/or improves infrastructure in 100-year flood event				
4	Yes	299481	Lumberton, City of	Robeson	0		9,468	South Lumberton Sewer Improvements	Rehabilitate approximately 7,330 LF of 8- to 15-inch gravity sewer piping, 28 manholes, 72 service laterals, and associated appurtenances.	Surveys	97.6%	97.6%	No	The Adams Company, Inc	\$3,000,000	\$3,000,000	59	59.02	4.F (-0.01) LMI				
5	Yes	299316	Columbia, Town of	Tyrrell	0		396	Columbia WWTP Improvements	Renovate existing secondary clarifiers; replace aging oxidation ditch rotors, and and improve electrical work.	ACS	69.6%	69.6%	Yes	McDavid Associates, Inc.	\$3,000,000	\$3,000,000	54	53.59					

Incomplete and Ineligible Applications

Application Number	Proposed Funding in Scenario?	Instance ID	Applicant Name	County	New Connections in Project	Funding Request per New Connection	Residential Connections	Project Name	Project Description	LMI Method	LMI Claimed	LMI Verified	Additional Info. Added?	Application Preparer	Total Project Cost	Funding Requested	Points	Points	Reason for Incompleteness/Ineligibility
																	Claimed by Applicant	Verified	
INEL _1	No	299415	Cherryville, City of	Gaston	0		2,837	CDBG-I Water Project	Replace approximately 4,011 LF of existing 2- and 6-inch diameter water main with 6-inch diameter pipe; install 14 fire hydrants, and 105 service connections and meters along Howell Street, Putnam Street, Ray Street, Church Street, Brookwood Avenue, Hillcrest Drive, and West First Avenue.	ACS	68.1%	68.1%	Yes	Burch Environmental	\$1,727,023	\$1,737,023	62	42.03	Incomplete application - Public Hearing documentation missing, FY-25 Audit missing (LGC recorded), supporting documentation missing.
INEL _2	No	299426	Cherryville, City of	Gaston	0		2,661	CBDG-I Sewer Project	Line with CIPP approximately 9,502 CIPP 8-inch terra cotta sewer mains built in the 1940; rehabilitate via lining 41 manholes; replace 105 service connections from tap to clean out.	ACS	68.1%	68.1%	Yes	Burch Environmental	\$1,737,023	\$1,737,023	62	19.03	Incomplete application - Public Hearing documentation missing, FY-25 Audit missing (LGC recorded), supporting documentation missing.
INEL _3	No	299401	Long View, Town of	Catawba	0		2,655	CDBG-I Water Project	Replace approximately 1,140 LF of 8-inch cast iron pipe and 6,361LF of 6-inch cast iron pipe with new PVC water mains. Install approximately 240 LF of new 6-inch PVC water line to create a looped connection and 17 new fire hydrant assemblies. Replace 70 service taps to meters, ensuring reliable and consistent service connections to all residences in the project area.	ACS	56.1%	56.1%	No	Twiggs Planning Consultants	\$1,487,131	\$1,487,130	50	7.08	Incomplete application - Public Hearing documentation missing, FY-25 Audit missing (LGC recorded), supporting documentation missing.
INEL _4	No	299400	Long View, Town of	Catawba	0		2,569	CDBG-I Sewer Project	Rehabilitate via CIPP 8-inch terra cotta sewer mains using cured- in-place pipe (CIPP) lining along the following: 22nd St Ave – 2,790 LF, 21st St Ave (including 8th Ave SW) – 2,306 LF, 20th St Ave (including 5th Ave SW) – 1,259 LF, 19th St SW – Section 2 – 530 LF, 19th St SW – Section 3 – 303 LF, and 7th Ave SW – 750 LF. Replace and/or install in 19th St SW (Section 1): 340 LF of 4-inch terra cotta sewer with 8-inch PVC and 4th Ave SW: 365 LF of new 8-inch PVC sewer line. Improve 74 sewer tap-to-cleanout replacements for all homes located along project streets. Rehabilitate and/or install 17 existing brick manholes.	ACS	56.1%	56.1%	No	Twiggs Planning Consultants	1458397	1458397	47	7.08	Incomplete application - Public Hearing documentation missing, FY-25 Audit missing (LGC recorded), supporting documentation missing.