Categorical Exclusion

North Carolina Division of Water Infrastructure

Project Applicant:	Town of Murfreesboro
Date:	September 21, 2026
Project Name:	Townwide Lift Station Improvements
Project Number:	SRF-W-0036 & SRP-W-134-0320
Estimated Project Cost:	$6,186,166
Estimated Funding Amount:	$6,110,156*

**Note: the estimated funding amount includes an SRF portion of $ 3,800,500 and a 134 portion of $2,309,656.*

Project Description:

Storey Road LS #1
Rehabilitation of lift station to include replacement of two (2) 145 GPM (like-for-like) suction lift pumps; and installation of telemetry, bypass pump connection, ATS, and standby generator.

West Main Street LS #2
Rehabilitation of lift station to include replacement of two (2) 175 GPM (like-for-like) suction lift pumps; installation of telemetry, bypass pump connection, ATS, standby generator, and grating & fall-through protection (for open hatch); and repair of wooden building.

West Broad Street LS #3
Rehabilitation of lift station to include replacement of one (1) 150 GPM (like-for-like) submersible pump, manhole, and wetwell; and installation of manhole frame and cover, site fencing, telemetry, ATS, and standby generator.

Jay Trail LS #4
Rehabilitation of lift station to include replacement of two (2) 250 GPM (like-for-like) suction lift pumps; installation of telemetry, bypass pump connection, ATS, standby generator; and repair of wooden building.

Harrell Street LS #5
Rehabilitation of lift station to include replacement of one (1) 150 GPM (like-for-like) submersible pump, manhole, and wetwell; and installation of manhole frame and cover, fencing, telemetry, ATS, and standby generator.

Holly Hill Road LS #7
Rehabilitation of lift station to include replacement of two (2) 150 GPM (like-for-like) suction lift pumps; and installation of fencing & gates, telemetry, bypass pump connection, ATS, and standby generator.

Lakeview Drive LS #8
Rehabilitation of lift station to include replacement of one (1) 150 GPM (like-for-like) submersible pump, manhole, and wetwell; and installation of manhole frame and cover, fencing, telemetry, ATS, and standby generator.

Quail Hollow Road LS #9
Rehabilitation of lift station to include replacement of one (1) 30 GPM (like-for-like) submersible pump, manhole, and wetwell; and installation of manhole frame and cover, fencing, telemetry, ATS, and standby generator.

East Vance Street LS #11
Rehabilitation of lift station to include replacement of one (1) 150 GPM (like-for-like) submersible pump, manhole, and wetwell; and installation of manhole frame and cover, fencing, telemetry, ATS, and standby generator.

NC Hwy. 11 LS #12
Rehabilitation of lift station to include replacement of two (2) 175 GPM (like-for-like) suction lift pumps; installation of telemetry, bypass pump connection, ATS, standby generator, grating & fall-through protection (for open hatch), and fencing & gates; and repair of block/brick building.

Scott street LS #14
Rehabilitation of lift station to include replacement of one (1) 150 GPM (like-for-like) submersible pump, manhole, and wetwell; and installation of manhole frame and cover, fencing, telemetry, ATS, and standby generator.

New Street LS #15
Rehabilitation of lift station to include replacement of one (1) 150 GPM (like-for-like) submersible pump, manhole, and wetwell; and installation of manhole frame and cover, fencing, telemetry, ATS, and standby generator.

Rose Road LS #16
Rehabilitation of lift station to include replacement of two (2) 100 GPM (like-for-like) suction lift pumps; and installation of telemetry, bypass pump connection, ATS, and standby generator.

Sycamore Street LS # 17
Rehabilitation of lift station to include replacement of one (1) 150 GPM (like-for-like) submersible pump manhole, and wetwell; and installation of manhole frame and cover, fencing, telemetry, ATS, and standby generator.

And removal and replacement of pavement, roadways, driveways and curbs, and sedimentation and erosion-control devices; and electrical, valves, vaults, yard piping, and associated appurtenances.

The above-named applicant will receive funding assistance from the State Revolving Fund. The North Carolina Department of Environmental Quality, Division of Water Infrastructure (**Division**) has conducted a review of the project in accordance with the NCGS §159G-38. The Division has determined that this project is below the minor construction activities threshold outlined in the 15A NCAC 01C .0408; therefore, the project is exempt from inter-agency review, and the preparation of additional environmental documents is not required.

This determination shall become effective upon its distribution by the Division and will be available on the Division's website (https://deq.nc.gov/about/divisions/water-infrastructure/division-water-infrastructure/environmental-documents). This determination can be revoked at any time adverse information is made available. The documentation to support this decision will be on file with the Division, and is available for public scrutiny upon request.

Comments concerning this decision may be addressed in writing to Ms. Stephanie Suter, Deputy Director, Division of Water Infrastructure, North Carolina Department of Environmental Quality, 1633 Mail Service Center, Raleigh, North Carolina 27699. Alternatively, she can be reached via telephone at 919.707.9044 or via e-mail at stephanie.suter@deq.nc.gov.

Sincerely,

Trupti Desai

Trupti Desai, P.E., Supervisor
Wastewater and Stormwater Projects Unit
Division of Water Infrastructure