



# CONSTRUCTION NOTES:

- CONTRACTOR SHALL MUCK OUT APPROXIMATE 24" WITHIN THE PROPOSED 25' BY 32' WORK AREA WITHIN THE CANAL
- CONTRACTOR SHALL INSTALL MIRAFL HP370 FABRIC OR EQUIVALENT AS UNDERLAYMENT BENEATH THE PROPOSED RIPRAP
- CONTRACTOR SHALL REFER TO STRUCTURAL DESIGN PLANS PROVIDED BY GARY GREENE ENGINEERS
- APPROX. 80 TONS OF RIPRAP PER STRUCTURE

